

Amended Preliminary Master Plan - Planned Unit Development

Somerville,
Massachusetts

Prepared for Federal Realty Investment Trust
5 Middlesex Avenue, 4th floor
Somerville, Massachusetts, 02145

Prepared by **VHB/Vanasse Hangen Brustlin, Inc.**
Transportation, Land Development, Environmental Services
101 Walnut Street
P.O. Box 9151
Watertown, Massachusetts 02471-9151
617 924 1770

Date: February 2017

Table of Contents

| | |
|---|----|
| Introduction | |
| Report, & Study Description | 3 |
| Existing Utility Conditions | 4 |
| Water Supply and Distribution Systems..... | |
| Existing Conditions | 5 |
| Proposed Conditions..... | 7 |
| Sanitary Sewer | |
| Existing Conditions | 10 |
| Proposed Conditions..... | 11 |
| Stormwater Drainage Design..... | |
| Existing Conditions | 12 |
| Proposed Conditions..... | 13 |
| Gas | |
| Existing Conditions | 15 |
| Proposed Conditions..... | 15 |
| Electrical Distribution System..... | |
| Existing Conditions | 16 |
| Proposed Conditions..... | 16 |
| Telephone Distribution System..... | |
| Existing Conditions | 17 |
| Proposed Conditions..... | 17 |
| Fire Alarm System..... | |
| Existing Conditions | 18 |
| Proposed Conditions..... | 18 |
| Cable TV..... | |
| Existing Conditions | 19 |
| Proposed Conditions..... | 19 |
| Summary | 20 |

List of Figures

Figure 1: Site Location Map
Figure 2: Existing Water Demand
Figure 3.1: Existing Sewer Generation
Figure 3.2: Estimated Proposed Sewer Generation and Water Demand

Appendices

| | |
|------------|--|
| Appendix A | Water System Analysis |
| Appendix B | MWRA Meter 91 Readings |
| Appendix C | Stormwater Drainage System Analysis |
| Appendix D | Grading, Drainage, and Utility Plans May 2014 (1 thru 5) |

Introduction

1. INTRODUCTION

1.1 Report

This report is submitted in connection with the site plan submission entitled, “Amended Preliminary Master Plan, Planned Unit Development, Assembly Square Drive (APMP PUD ASD), Somerville, Massachusetts”, dated May 2014 (the “Project”) and the previously approved “Amended Preliminary Master Plan, Planned Unit Development, Assembly Square Drive (PMP PUD ASD), Somerville, Massachusetts”, dated June 2010.

For Site Location Map refer to Figure 1.

For existing utilities referenced in this report please refer to the drawings in the Site Plans entitled:

- Utility As-Builts SV-1 thru SV-13 dated March 9, 2012

For proposed utilities referenced in this report please refer to the drawings submission entitled:

- Grading, Drainage and Utility Plans 1 thru 5 dated May 2014.

1.2 Study Description

This report confirms and updates findings in a report by Green International Affiliates, Inc., (GIA), which analyzed for the Somerville Office of Housing and Community development (OHCD), all existing utilities, and future improvements within the Assembly Square Revitalization Area (ASRA). The GIA report is entitled “Utility Analysis Report (UAR) for Assembly Square Revitalization Area Somerville, Massachusetts” and was completed in November, 2001. The report describes the locations, sizes and capacities of the following existing utility systems: sanitary sewers, water mains, storm-water surface drainage, telephone, gas, electric, cable TV, communication and fire alarms. The OHCD developed a potential build-out scenario in that report for the entire ASRA which was used as the base for the existing utility analyses and to identify the necessary improvements needed to support the potential build-out.

This report confirms the existing utility findings in the GIA Report and suggests proposed utility improvements in a similar format as was presented in the GIA report to support this Project.

This report was prepared using some of the information contained in the 2001 GIA Utility Analyses. In order to avoid repeated references to the GIA 2001 Utility Analyses, this report contains all the utility existing information, data and analyses that are valid for current conditions. Any additional information regarding existing utility information that has been recognized since the previously approved PMP PUD is also reflected in this report.

1.3 Existing Utilities

Existing utilities information within the PUD area were obtained from actual on the ground instrument survey performed by Vanasse Hangen Brustlin, Inc. (VHB) in March of 2010 and March of 2012. Some underground utilities are based on field observation and information of record. They are not warranted to be exact.

1.4 Existing Utility Improvements follow-up

The master developer, Federal Realty Investment Trust, has constructed all necessary utility infrastructure for the full buildout of the Project in the proposed streets of the PUD area in 2010 and 2012.

Water Distribution System

Existing Conditions

2 WATER SUPPLY AND DISTRIBUTION SYSTEM

2.1 Existing Water Supply and Distribution System

The City of Somerville owns and maintains the public water distribution system that services the Assembly Square Revitalization Area (ASRA). The City's water distribution system supplies both domestic and fire protection water to the area. This system is part of a city-wide interconnected network that is supplied by the Massachusetts Water Resources Authority (MWRA) through seven metered connections. The City is supplied by both MWRA's high service and low service pressure systems. The water distribution system within the Assembly Square area is part of the City's low service system.

MWRA Meter 91 is located at the intersection of the Fellsway West and Middlesex Avenue and provides the closest supply of water to the Assembly Square area from a 48-inch cast iron water main located in Middlesex Fells Parkway (Fellsway). The City does not have any water storage facilities or any pumping stations that service this area.

The MWRA has preformed water main improvements to Meter 91 and the existing 48-inch water main located in Middlesex Fells Parkway. The water main improvements consisted of cleaning, cement-mortar lining, internally sealed joints, 48-inch restrained joint pipe and valving.

Information provided by the MWRA concerning Meter 91 is as follows:

The Average Hydraulic Grade Line Elevations is 184 ft. (Boston City Base Datum)

Refer to Appendix "B" for the MWRA Meter 91 water readings and Somerville's total daily water flows between 2004 and 2006.

The existing system is comprised of water mains ranging in age from 1917 to 1982 and in varying conditions. The water distribution system is described as follows:

- More that half of the system was installed in the 1920's while most of the remaining mains were installed during the 1970's and 1980's.
- The City's water mains sizes are all 8-inch diameter and larger which meets the minimum recommended size for adequate fire flows.
- The primary connection to the MWRA meter is a 20-inch diameter cast iron main installed in 1925 by the City within and along Middlesex Avenue.
- Several branch lines of varying diameter feed off the 20-inch main between Middlesex Avenue and the Fellsway.
- The remainder of the system along Foley Street, Assembly Square Drive and Mystic Avenue consist of a 12-inch diameter pipe interconnected to create several loops.

- The piping network in this area, for the most part, was installed to create a looped system around buildings sites and is interconnected to the city-wide network at several locations.
- The piping has generally been installed within the limits of the City's roadway system and has sufficient valving at most intersections to facilitate isolation and redirection of the flow during emergency or maintenances situations.
- As part of the ongoing approved work a portion of the existing 12-inch water main within Assembly Square Drive was replaced due to its poor condition. Also, a 20-inch water main has been constructed within Foley Street and the future extension of Assembly Square Drive in order to service the future development.

2.1.2 Existing Water System Demands

Average Day and Maximum Day Demands

Currently, the ASRA is primarily being used for retail, office and industrial purposes. Existing water demand was calculated for the average day and the maximum day demand based on the existing uses that make up the ASRA. Based on existing information the flow rates calculated for the existing uses for the average day demand and maximum day demand were 64 GPM and 115 GPM, respectively.

Needed Fire Flow

The water system within the Project area provides both domestic and fire flow water supply. The City's existing water distribution network within this area has, on average, fire hydrants located 300 feet apart throughout the entire area. This spacing meets the typical maximum recommended distance between hydrants in an urban setting.

The minimum Needed Fire Flow (NFF) for MWRA Meter 91 and maximum Insurance Services Office (ISO) requirements for a Community are:

| | <u>Fire Flowrate</u> |
|--|----------------------|
| Estimated minimum NFF requirements to be supplied by MWRA for meter 91: | 2,000 gpm |
| Maximum requirements a community is required to supply according to the ISO: | 3,500 gpm |

The required minimum residual pressure at any location within the distribution system during a fire flow situation is 20 psi.

2.1.3 Existing Water System Analysis

Computer hydraulic analysis was performed by GIA, and confirmed by VHB, for the existing ASRA area water distribution system to determine system capacity and to provide a baseline for comparison of future system demands. The analysis included a limited computer network model on order to simulate several scenarios including:

1. Existing Average Day Demand
2. Existing Maximum Day Demand
3. Existing Maximum Day Demand Plus 2,000 gpm Fire Flow

The computer hydraulic analysis has indicated that the existing system has sufficient capacity for all scenarios.

Proposed Conditions

2.2 PROPOSED WATER SYSTEM

2.2.1 Proposed System Demands

The full build out of Amended Preliminary Master Plan within the Project area will result in an increase in the water demands on the existing system. The future average day flowrates and maximum day flowrates were developed by utilizing proposed land use areas as shown in Figure 3.2.

2.2.2 Proposed System Analysis

VHB performed a preliminary computer hydraulic analysis of the proposed conditions utilizing information obtained from the MWRA and hydrant flow test information to further explore the availability of water flow at the higher flow rate set by the ISO. The computer model was calibrated based on a hydrant flow test performed by VHB on September 13, 2006, at the intersections of McGrath Highway and Kensington Avenue with Middlesex Avenue. This hydrant is connected to the 20-inch water main in Middlesex Avenue. The hydrant flow test computation converted to a base of 20 psi resulted in a flow of 5,645 gpm. VHB performed additional hydrant flow tests on March 14, 2007 and August 18, 2011, September 12, 2014 and November, 2015 in order to further refine and confirm the computer model. Refer to Appendix "A" for hydrant flow test computations.

A preliminary hydraulic analysis was performed for future demands on the existing/proposed water distribution systems. The analysis includes utilizing the Future conditions model and performing several scenarios including:

| | |
|---|-----------|
| 1. Future Average Day Demand | 704 gpm |
| 2. Future Maximum Day Demand | 1,060 gpm |
| 3. Future Maximum Day Demand Plus 2,000 gpm Fire Flow | 3,060 gpm |
| 4. Future Maximum Day Demand Plus 3,500 gpm Fire Flow | 4,560 gpm |

A fire flow of 3,500 gpm is the maximum requirement a community is required to supply according to the ISO standards.

Based on VHB analysis the Future Maximum Day Demand and 3,500 gpm fire flow can be achieved within the Project area after the proposed water improvements are constructed.

2.3 Proposed Water System Improvements

The following proposed water mains will be installed or have already been constructed as part of the ongoing approved work in order to provide loop connections throughout the Assembly Square PUD area.

- Connected a new 20-inch water main from the existing 20-inch water main in Middlesex Avenue, continued along the future extension of Assembly Square drive to Foley Street then continued west along Foley Street to Middlesex Avenue where the new 20-inch water main was connected back into the existing 20-inch water main in Middlesex Avenue. The newly constructed 20-inch main in Foley Street replaced the existing 12-inch water main installed in 1928.
- Extended water mains, ranging in size from 8 to 20-inch, from the newly constructed 20-inch water main in Grand Union Boulevard along Artisan Way, Great River Road, Canal Street, Foley Street and Revolution Drive where they are interconnected in order to create multiple looped systems.

- Loop a proposed 12-inch water main on the Parcel 11A site from the recently replaced 12-inch water main in Grand Union Boulevard to Revolution Drive.

Sanitary Sewer

Existing Conditions

3.1 Existing Sewer System

The City of Somerville owns and maintains the sanitary sewer system in the ASRA area. The sanitary sewer system within the area is a separated system with storm drainage collected in an independent system.

All of the master planned sanitary sewer mains have been installed in the ASRA. The pipe starts as an 8" at the north end of the Site. The pipe sizes increase to an 18" as they discharge towards the southern end of the Site. The reconfigured and reconstructed sewer system in N. Union Street connects to a 24" pipe prior to discharging to the City of Somerville Regulator Manhole, which is the connection to the MWRA system.

Proposed Conditions

3.2.1 Proposed Sewer System

All of the sewer mains in the ASRA have been constructed as part of the previous construction phases of the project. All of the improvements have been consistent with the Preliminary Master Plan and PUD approval processes. The total amount of sewer flow from the project is essentially unchanged. The distribution of the sewer flow to the system is also basically unchanged. The sewer system has adequate capacity to handle the sewer flows from the project as proposed.

3.2.2 Proposed Sewer System Analysis

The average daily wastewater flows rates used in the analysis are based on Commonwealth of Massachusetts, Sewer System Extension and Connection, regulation 314 CMR 7. Wastewater peak flows rates were determined by multiplying the average daily flow by a peaking factor of four. The proposed land use areas and calculated flow rates are shown on Figure 3.2. The proposed development in the PUD-ASD area will increase wastewater flows to the MWRA interceptor sewer.

3.2.2 Proposed System Improvements

Based on the sewerage flows generated by the proposed development it was necessary to replace the existing 12-inch sewer lines within Assembly Square Drive with proposed 18-inch and 12-inch sewer trunk lines. These improvements have already been made as part of the ongoing approved work. The total peak sewer flows from the proposed development will generate 3.11 +/- mgd. The 18-inch sewer trunk line has a design capacity of 5.1 +/- mgd at a slope of 0.003 +/- with an average velocity of 5 ft per second. The 18-inch sewer trunk line

will have the capacity to handle all peak sewer demands of the Proposed Development with an excess capacity of 2.0 +/- mgd.

To address existing sewer configuration issues at the intersection of Assembly Square Drive and North Union Street, the following new sewer alignment and connections were constructed and are shown on the submitted PUD drawings:

- The new 18-inch trunk line within North Union Street will pick up the sewer flows from the existing 12-inch sewer, which collects sewer discharge from the Home Depot and Circuit City at SMH 32.
- The installation of a Special Drop Sewer Manhole will be constructed over the existing 24-inch sewer and 18-inch metal sewer at the existing drop connection of the existing 12-inch sewer. The new 18-inch trunk line connects into the Special Drop Sewer Manhole.

3.2.4 **Sewer Mitigation**

The Project has received two Sewer Extension and Connection Permits from DEP for discharging into the municipal and MWRA collection system. The first permit was approved on October 8, 2009 (Permit No. X229252) and included details of the sewer mitigation plan. Mitigation to offset flows is required to be implemented as part of the conditions for granting the connection. The mitigation program has been approved by the reviewing agencies. The second permit dated November 10, 2011 (Permit No. X239330) was for the connection of additional flow from a new phase of the development consistent with the master plan. A sewer permit application for the remaining flows from the entire project has been reviewed and approved by the City of Somerville Engineering and DPW departments. The proposed mitigation for the entire project has remained unchanged.

The mitigation took measures to reduce and/or eliminate non-sanitary sewerage flows, including the completed sewer improvements in Assembly Square Drive, the completed improvements in Foley Street and Mystic Avenue, off-site improvements completed in the Ten Hills neighborhood, removal of illicitly-connected catch basins on Mystic Avenue, Lombardi Street and Broadway, reduction of flows into the Somerville Marginal Conduit and a financial contribution to the City of Somerville in the form of funds specifically designated for I/I improvements.

The specific inflows and infiltration to be removed from the system are as follows:

Total Build Out (District A-1 and B-1 minus Yacht Club)

| | |
|---|-------------------|
| Proposed Project Added Total Sewer Flows = | 777,116 gpd |
| <u>Minus Existing Redeveloped Areas within District B-1 =</u> | <u>30,361 gpd</u> |
| Proposed Net Increase in Sewer Flows= | 746,755 gpd |
| Required DEP 4:1 Mitigation= | 2,987,020 gpd |

Proposed Mitigation @4:1 (Completed)

- The proponent has constructed improvements in the Ten Hills Area including sewer main replacement, sewer manhole replacement and pipe lining to complete the Sewer Inflow and Infiltration mitigation requirements for 610,000 gallons.
- Infiltration into the existing vitrified clay sewer pipes within the entire PUD area has been eliminated with the installation of approximately 1,800 feet of new 18-inch sewer pipes and 3,400 feet of 12-inch sewer pipes. Flow metering of existing pipes determined the potential for elimination of 78,000 gallons per day. The conditions of the sewer extension permit require future flow monitoring to determine if this volume reduction has been achieved.

- Disconnection of illicitly-connected catch basins on Mystic Avenue, Lombardi Street and Broadway that will remove approximately 294,000 gallons per day has been completed.
- Approximately 1,200,000 gallons per day will be removed from the Somerville Marginal Conduit by stormwater improvements in the PUD.
- The proponent has made a financial contribution to the City of Somerville specifically designated for Infiltration/Inflow removal projects, offsetting 810,000 gpd of new sewer flows.

Summary:

| | |
|--|-----------------------|
| Proposed Project Total Sewer Flows = | 777,116 gpd |
| Required Mitigation = | 2,987,020 gpd |
| <u>Mitigation Description</u> | <u>Sewer Flows</u> |
| Ten Hills Area = | 610,000 gpd |
| I/I reduction from existing PUD sewers = | 56,000 gpd |
| Illicitly Connected CB disconnection = | 73,553 gpd |
| Removal of flows from SMC = | 1,200,000 gpd |
| <u>Financial Contribution offset =</u> | <u>1,047,467 gpd</u> |
| | Total = 2,987,020 gpd |

Stormwater Drainage System

Pre-Existing Conditions

4.1 Pre-Existing Drainage System

In 2001 Green International Affiliates, Inc. (GIA) prepared a Utility Analysis Report (UAR) of the Assembly Square Revitalization Area for the City of Somerville, Office of Housing and Community Development (OHCD). This report contains an inventory and analysis of the existing stormwater drainage infrastructure as well as some recommendations for drainage improvements during future development of the area. The GIA Report was used in conjunction with field survey information to analyze the existing stormwater drainage system for this Amended Preliminary Master Plan, Planned Unit Development (PUD) submission.

The proposed Project Site is located on Assembly Square Drive in the City of Somerville, Massachusetts. The majority of the Project Site was previously covered with existing buildings, roadways, and parking lots or areas that were previously developed and demolished. The Project Site is generally flat, ranging from approximate elevation 9 feet (NGVD) to 12 feet (NGVD) with the exception of a portion of Assembly Square Drive that slopes rapidly to reach an elevation of 30 feet (NGVD) at its connection to Mystic Avenue. The majority of the Project Site is covered by impervious or near-impervious surfaces. NRCS Soil Maps for Middlesex County (NRCS Web Soil Survey, 4-13-95) show the existing soils to be Urban land with wet substratum (603) and Udorthents with wet substratum (655). Geotechnical information available at the time of this report classifies the soils as hydrologic soils group D, which has low infiltration potential. Detailed soils information and a soils map are included in Appendix C. The cover condition and soils present in the Project Site result in minimal infiltration of stormwater under existing conditions. Areas at the north and east of the Project Site that were historically occupied with railroad and manufacturing facilities are currently vacant or unmaintained. Under pre-existing conditions, much of the stormwater collected in the Project Site discharges untreated to the existing Massachusetts Water Resources Authority (MWRA) 84-inch Somerville Marginal Conduit (SMC) or to the Mystic River as overland flow or via pipe upstream of the Amelia Earhart Dam. The MWRA 84-inch SMC discharges downstream of the Amelia Earhart Dam to the tidally influenced portion of the Mystic River. Stormwater runoff discharging to the MWRA 84-inch SMC has been an ongoing area of concern for the MWRA as the SMC currently acts as a combined sewer overflow (CSO) during some large storm events and high tide conditions at the outfall.

Under current conditions, a new dedicated 72-inch drainage outfall discharges downstream of the Amelia Earhart Dam to redirect stormwater flows and to help alleviate the potential for CSOs into the Mystic River. This is consistent with the goals for improving water quality in the Mystic River.

Proposed Conditions

4.2 Proposed Stormwater Management System

The Project was designed to comply fully with the Massachusetts Stormwater Management Regulations for a re-development project and the applicable City of Somerville requirements. The Proponent constructed improvements to existing roadways, construction of new roadways and drives, expansion of the DCR waterfront park and the expansion and upgrade of underground utility infrastructure. The proposed design includes LID and water quality measures that will protect the surrounding natural resources, as described in this report, from degradation as a result of stormwater runoff.

The design options for the storm drain system required close consideration of the adjacent properties, including the MBTA Orange Line, the existing DCR waterfront park and existing commercial uses. Another key consideration of the storm drain system in the Assembly Square area is the existing 36-inch connection to the MWRA 84-inch SMC. As previously mentioned, during large storm events and high tide conditions at the SMC outfall, the SMC has historically experienced combined sewer overflows into the non-tidal portion of the Mystic River, upstream of the Amelia Earhart Dam. In order to avoid any increased impacts to the MWRA 84-inch SMC, it is proposed to abandon the existing 36-inch connection to the MWRA 84-inch SMC and construct a new 72-inch storm drain trunk line that will discharge at a new outfall downstream of the Amelia Earhart Dam, in the tidal portion of the Mystic River. The MWRA has analyzed the benefits that the disconnection of the 36-inch pipe will have on the MWRA 84-inch SMC. This new storm drain trunk line includes a tide-gate near the outfall to prevent tidal waters from entering and surcharging the new drainage system during periods of high tide.

The new trunk line proposed for the Project was constructed within the extension of Foley Street, and then continued under the MBTA tracks and through property owned by the Commonwealth of Massachusetts. A portion of this pipe was constructed in 2009 as part of the infrastructure necessary for the approved Phase 1-AA. See attached plans for the location of the 72-inch storm drain outfall. This design will significantly decrease stormwater runoff to the Mystic River above the Amelia Earhart Dam, and eliminate stormwater flows from the Project Site to the MWRA 84-inch SMC. As a result, the design would help alleviate backups within the MWRA 84-inch SMC and decrease the amount of combined sewer overflows (CSOs) above the Amelia Earhart Dam.

Goals for the design of the proposed drainage system for the Project include the following:

- Reduce discharge to the MWRA 84-inch SMC.
- Incorporate LID techniques into the design to the maximum extent practicable.
- Design systems for long-term efficiency by providing concise operation and maintenance requirements.
- Upgrade existing drainage system components to ensure adequate capacity is provided for a 10-year storm event at a minimum.
- Improve the water quality of runoff for the proposed redevelopment areas.

These goals are fulfilled through many design components as described below.

The full-build drainage system follows the Stormwater Management Regulations and Best Management Practices as outlined in this report in order to provide long-term protection of natural resources in and around the Project.

Stormwater runoff from the Project will be collected in deep-sump catch basins with oil/debris traps and treated in off-line water quality units before discharging to the new 72-inch stormwater outfall. Regular sweeping programs for roads, parking and loading areas and a scheduled catch basin cleaning program are proposed for

pollutant source reduction. LID stormwater management techniques have been incorporated into the design as much as possible for stormwater quality and temperature control and are further described in this report.

Water Quantity and Quality Control

The proposed stormwater management system includes a number of proprietary structural and non-structural Best Management Practices (BMPs) to provide water quality mitigation for land uses with higher potential pollutant loads (LUHPPL) due to high intensity use. It should be noted that in the full build out condition the majority of the proposed parking spaces that attribute to the high intensity use of the Project will be in underground or structured garages rather than large surface parking lots. Any oil and grit in the runoff from the garages will be captured in structured separators prior to discharge to the sanitary sewer system rather than the stormwater closed pipe drainage system. Proposed surface parking facilities utilized during interim phases will discharge to the stormwater closed pipe drainage system and will be in compliance with the Massachusetts Stormwater Management Regulations. Additionally, upon completion of the MBTA Orange Line Station the number of vehicle trips to the Project Site will be significantly reduced further reducing the impacts of oil and grit. Stormwater runoff from the small percentage of proposed on-street parking, in addition to street sweeping and deep sump catch basins, will be treated by specific structural stormwater BMPs that are suitable for such an application. Although the 72-inch stormwater outfall will discharge into the tidal portion of the Mystic River which is currently a “Prohibited” shellfish growing area, the first inch of runoff has been designed to be treated consistent with the DEP requirement for treatment of one inch for critical areas. Water quality BMPs are designed to provide at least 80 percent total suspended solids (TSS) removal in accordance with the Massachusetts Stormwater Management Regulations. Source control, an operation and maintenance program, snow management, and spill prevention BMPs will be implemented within the Project. Other BMPs that may be used throughout the Project include water quality units, bioretention basins, biofiltration islands, green roofs, tree filter boxes, rainwater recovery, permeable asphalt and permeable pavers. Specific BMPs will be evaluated and reviewed for each future individual phase by the Somerville Conservation Commission (SCC).

4.2.1 Analysis of Stormwater Management Revisions

The proposed changes to the hydrology of the Site since the Amended Preliminary Master Plan revision dated June 2010 to the present application includes a reduction in impervious material cover type that will result in a reduction in stormwater runoff. The revisions to the Project areas are summarized in the following :

- The revisions to Block 6 include a larger roof area and a removal of the small rain garden. The rain garden was provided for water quality purposes only and did not provide detention volume. Water quality treatment will be provided with a suitable structure for parking deck rooftop.
- The revisions to both Block 7 and 8 include a reduction in block area to account for the additional area located in the median (Median Park) of Assembly Row. For the purposes of the closed pipe calculations this additional park area was analyzed as entirely impervious as a conservative assumption.
- The revisions to Parcel 11A consist of a large increase in landscaped area as compared to the previous designs and submissions.

The peak discharge from the project site has been reduced from the previously approved discharge rates. See following table of closed pipe calculations for the peak discharge rates using StormCAD and the high tide elevation for a tailwater condition.

Closed Pipe Calculations - Peak Discharge Rates (cubic feet per second)

| | 10-year | 25-year | 100-year |
|-------------------------------|---------|---------|----------|
| 72" Stormwater Outfall | | | |
| Previous Design | 108.9 | 156.7 | 221.2 |
| Current Design | 104.2 | 139.4 | 181.1 |

4.2.2 Proposed Stormwater Management System Improvements

The purpose of the Stormwater Management Plan (the Plan) is to provide long-term protection of natural resources in and around the Project Site. This is achieved by implementing water quality and quantity control measures designed to decrease the amount of pollutants discharged from the Project Site, increase the quality of stormwater recharged on the Project Site, and control discharge rates. A final stormwater management plan for each future individual phase will be locally reviewed and approved by the Somerville Conservation Commission.

Low Impact Development (LID) Features

Low impact development techniques combine functional site design with pollution prevention in order to reduce impacts to nearby water resources. LID can be very effective for new and ultra urban areas, where space is a limiting factor, by selecting LID practices that focus on decentralizing stormwater management at the Project Site and incorporating vegetated stormwater management techniques into the design as much as possible to reduce peak runoff rates and provide treatment to improve water quality. The practices that may be implemented include: green roofs, bioretention basins (rain gardens), biofiltration islands, tree box filters, porous pavements, and rainwater recovery. In addition to improving water quality, these LID practices will also reduce the temperature of the stormwater discharging at the proposed 72-inch outfall.

Mitigation Measures

The Project will include mitigation measures to safely protect surrounding resource areas from the discharge of runoff. The stormwater management system has been designed to meet or exceed the standards contained in the DEP Stormwater Management Regulations.

After being collected in the Project's closed pipe drainage system, the Project's stormwater runoff will be treated and then discharged via the proposed 72-inch stormwater outfall that was constructed by the Proponent for the City of Somerville. The outfall pipe was included in those activities and granted a waiver from further review under MEPA in the Final Record of Decision on this Project. The proposed 72-inch storm drain will be operational prior to the opening of the first building constructed as part of the mixed use development. In addition to the proposed 72-inch stormwater outfall, the Project Site will feature multiple LID measures and over two and half miles of brand new stormwater drainage infrastructure including the replacement of aged existing drainage systems where necessary.

Over 3 million gallons of combined sewer overflows from the MWRA 84-inch SMC entered the Mystic River during wet weather events in 2006. Stormwater runoff entering the MWRA 84-inch SMC from the Project Site will be redirected to the proposed 72-inch outfall and will therefore reduce the amount of combined sewer overflows to the Mystic River. The MWRA has performed an analysis of the benefits of removing the flows from the SMC. The analysis shows that removal of flows will reduce the average annual treated combined sewer overflow volume at Outfall MWR205A located near the Fellsway by Wellington Bridge from 2.35 million gallons to 1.70 million gallons, a 28% reduction in annual discharge volume. Outfall MWR205A



discharges treated combined sewer flows to the upstream portion of the Mystic River during high tide and extreme wet weather events. A reduction of discharges in this location will present a direct environmental benefit by improving the water quality of the Mystic River.

Long-Term Maintenance Program

The Proponent has entered into a long term maintenance agreement with the City of Somerville to provide for the Proponent's commitments to the City in order to maintain sidewalks within the Project and to maintain the non-standard stormwater quality structures. The City will be responsible for the maintenance of the streets, sewer, water and standard drainage structures (e.g. catch basins, manholes, pipes). The Proponent will maintain the streetscape and plaza landscaping within the Project as part of its responsibilities under the long-term maintenance agreement. A sample Long-Term BMP Maintenance/Evaluation Checklist is included in Appendix C.

Gas

Existing Conditions

5.1 Existing Gas Distribution System

NationalGrid, formerly the Keyspan Company, is the provider of the gas to the Project area. The closest gas source to the area is a low pressure 16-inch to 20-inch welded steel gas line located in an easement which runs across the MBTA tracks near Assembly Square Drive and North Union Street. Other gas lines within the Project area branch off of the 20-inch line.

Proposed Conditions

5.2 Proposed Gas System Requirements

In past communications between VHB and NationalGrid, NationalGrid has stated that the findings in the GIA report are not relevant today. VHB has provided information to NationalGrid regarding the building program and approximate loads in order for NationalGrid to estimate and identify the size, sources and costs for their gas system improvements. NationalGrid ran an analysis of the existing and proposed systems and determined that due to the size of the development that a higher pressure gas system than is currently available will be required to service the Project.

5.3 Proposed Gas System Improvements

The nearest source of the higher pressure gas to the Project is located in Pinckney Street in East Somerville. A 12-inch steel gas line was installed from Pinckney Street to the Project along Pearl Street, Mt. Vernon Street, Lombardi, and Assembly Square Drive. The gas line mains have been installed into the project area for connection to the future development blocks.

Electrical Distribution System

Existing Conditions

6.1 Existing Electrical Distribution System

Eversource supplies electricity to the Assembly Square area with four 13.8 kV electrical services lines in the Assembly Square Revitalization Area. The four 13.8 kV service lines serve the following

- Assembly Square Marketplace
- Foley Street
- Office Building/Vacant Theater
- Back-up

Proposed Conditions

6.2 Proposed Electrical Distribution System Requirements

In past communications between VHB and NStar, NStar has stated that the findings in the GIA report are not relevant today. VHB has provided information to NStar regarding the building program and approximate loads in order for NStar to estimate and identify the size, sources and costs for their electrical system improvements. VHB will design the conduit and manhole system in conjunction with NStar in order to accommodate the required electrical infrastructure.

6.3 Proposed Electrical Distribution System Improvements

The electrical infrastructure, including ductbanks and manholes, have been constructed by the Proponent in the ASRA for the future electrical system improvements.

Telephone Distribution System

Existing Conditions

Existing Telephone Distribution System

Verizon supplies telephone service to the Project area. The system consists of underground lines and overhead telephone wires between poles.

Proposed Conditions

7.2 Proposed Telephone Distribution System Requirements

In past communications between VHB and Verizon, Verizon stated the findings in the GIA report are not relevant today. VHB has provided information to Verizon regarding the building program and approximate loads in order for NStar to estimate and identify the size, sources and costs for their telephone system improvements. VHB will design the conduit and manhole system in conjunction with Verizon in order to accommodate the required telephone infrastructure.

7.3 Proposed Telephone Distribution System Improvements

The telephone infrastructure, including ductbanks and manholes, have been constructed by the Proponent in the ASRA for the future telecommunications system improvements.

Fire Alarm System

Existing Conditions

8.1 Existing Fire Alarm System

The City of Somerville's Electric Lines and Light Department has jurisdictions over the fire alarm systems within the City. The fire alarm system consists of manholes and fire boxes within the Project area.

Proposed Conditions

8.2 Proposed Fire Alarm system Requirements and Improvements

The City of Somerville has requested that a wireless radio frequency fire alarm system be used to serve the Project area. In order to provide sufficient coverage and equipment for the wireless system VHB has coordinated final locations of the fire boxes with the City's Fire Chief.

Cable TV

Existing Conditions

9. Cable TV

9.1 Existing Cable Television System

The only location that is serviced by Comcast/RCN cable within the Project area is along Middlesex Avenue near Foley Street and the Assembly Square Marketplace.

Proposed Conditions

9.2 Proposed Cable Television System Requirements and Improvements

VHB contacted the current suppliers of cable and telecommunications who service the Project area to determine the level of services offered and the magnitude of the improvements. Sufficient conduit and manholes have been provided to support future cable and telecommunications providers.

10


Summary

10. SUMMARY

The proposed buildings and utilities within the Project area will be constructed in multiple phases over the course of the project. All necessary infrastructure for the full build out of the Project has been constructed in the streets of the PUD area. The construction of the utility infrastructure began in 2009. Coordination with private utilities is ongoing and will continue throughout the construction of the Project. The water system adequately provides water during the average day demand and peak fire flow conditions. The sewer system is sized to carry all flows from the proposed development and adjacent properties to the Medford-Somerville branch sewer. The sewer flows generated will be mitigated at a 4:1 ratio. The stormwater management system has been sufficiently designed to meet all applicable local and state regulations. All future phases of the Project will be reviewed by the City of Somerville as part of the Special Permit with Site Plan Review (SPSR) process.

List of Figures

- Figure 1. Site Location Map
- Figure 2. Existing Water Demand
- Figure 3.1. Existing Sewer Generation
- Figure 3.2. Estimated Proposed Sewer Generation and Water Demand



Vanasse Hangen Brustlin, Inc.

Figure 1
July 2010



0 500 1000 Feet

Site Location Map
Assembly Row
at Assembly Square
Amended Preliminary Master Plan
Planned Unit Development
Somerville, MA

Consulting Engineers and Planners
101 Walnut Street
Watertown, MA 02172
(617) 924-1770

Figure 2: Existing Water Demand

Project: Assembly Square Planned Unit Development Proj. No. : 8518.05
Date: 6/8/2010
Location: Somerville, Massachusetts
Rev. Date
Computed by: MVG
Checked by:

File: \\Mawald\ld\08518.05\docs\VARIOUS\AmPUD\Utilities\Water\08518.05 Existing Water Demand.xml\Water Demands Fig 4

1. Average flows for Massachusetts are based on 314 CMR 7: Sewer System Extension and Connection Program.

Existing Uses to remain out side of Phase 1-AA but within the Planned Unit Development

| Building Identification | Use | Square Feet | Quantity | Unit | Unit Flow (gal/Unit) | Average Flow (GPD) | Total Bldg. Flow (GPM) | Total Peak Bldg. Flow (GPM) ¹ |
|-------------------------|---------------|-------------|-----------|-----------|-------------------------|-----------------------|---------------------------|---|
| Assembly Marketplace | Retail | 328,806 | 329 | 1,000 SF | 50 | 16,440 | 11 | 20 |
| Yacht Club | Marina | - | 80 | Slip | 10 | 800 | 1 | 1 |
| Amelia Earhart Dam | Offices | 1,000 | 1 | 1000 SF | 75 | 75 | 0 | 1 |
| Spaulding Brick | Industrial | 11,700 | 12 | 1000 SF | 75 | 878 | 1 | 1 |
| Trucking Company | Industrial | 26,910 | 27 | 1000 SF | 75 | 2,018 | 1 | 2 |
| La Quinta Inn | Hotel | 77,678 | 172 | 1 Bedroom | 110 | 18,920 | 13 | 23 |
| Religious | Institutional | 15,842 | 16 | 1000 SF | 50 | 792 | 1 | 1 |
| County | Institutional | 32,432 | 32 | 1000 SF | 75 | 2,432 | 2 | 3 |
| Sunrise Cuisine | Restaurant | 4,326 | 40 | 1 Seat | 35 | 1,400 | 1 | 2 |
| Dunkin Donuts | Restaurant | 4,006 | 12 | 1 Seat | 20 | 240 | 0 | 1 |
| Warehouse | Industrial | 8,369 | 8 | 1000 SF | 75 | 628 | 0 | 1 |
| 99 Restaurant | Restaurant | 11,382 | 393 | 1 Seat | 35 | 13,755 | 10 | 17 |
| Office | Offices | 114,559 | 115 | 1000 SF | 75 | 8,592 | 6 | 10 |
| Loew's Cinema | Cinema | 80,000 | 2,400 | 1 Seat | 5 | 12,000 | 8 | 15 |
| Home Depot | Retail | 147,608 | 148 | 1000 SF | 50 | 7,380 | 5 | 9 |
| Circuit City | Retail | 33,488 | 33 | 1000 SF | 50 | 1,674 | 1 | 2 |
| Enterprise Rent A Car | Retail | 2,000 | 2 | 1000 SF | 50 | 100 | 0 | 1 |
| Hillside Service Center | Commercial | 4,656 | Min Allow | 2 | 150 | 300 | 0 | 1 |
| Ashton Fuel | Commerical | 15,405 | 15 | 1,000 | 50 | 770 | 1 | 1 |
| Tracer Technologies | Industrial | 30,995 | 31 | 1,000 | 75 | 2,325 | 2 | 3 |
| | | | | | | 91,520 | 64 | 115 |

1) Maximum Day Demand Peaking Factor = 1.75 Times Average Day Demand. Minimum peak flow =1 PGM

**Amended Preliminary Master Plan
Existing Sewer Generation within Assembly Square Revitalization Area
Somerville, MA**

| Building Identification | Use | Building (SF. Ft.) | Number | Unit | Unit Flow Rate (GPD) | Flows Removed Phase 1 | Flows Removed Full Build | Flows To Remain |
|---|------------------------------------|--------------------|--------|---------|----------------------|-----------------------|--------------------------|-----------------|
| 85 Foley St.- Cab repair ¹ | Gasoline Station with Service Bays | 3,677 | 1 | Island | 300 | | 300 | |
| | | | 4 | Bay | 125 | | 500 | |
| 99 Foley St.- Central Steel ¹ | Industrial ² | 51,217 | 13 | Person | 15 | | 195 | |
| | Office | 2,961 | 3 | 1000 SF | 75 | | 222 | |
| 123 Foley St.- Spaulding Brick ¹ | Industrial ³ | 16,880 | 5 | Person | 15 | 75 | | |
| | Office | 2,920 | 3 | 1000 SF | 75 | 219 | | |
| 147 Foley St. American Propane | Office | 1,050 | 1 | 1000 SF | 75 | 79 | | |
| 100 Sturtevant | Industrial ² | 22,760 | 15 | Person | 15 | 225 | | |
| | Office | 3,772 | 4 | 1000 SF | 75 | 283 | | |
| Yacht Club | Marina | | 80 | slip | 10 | | | 800 |
| Goodtime Billiards ⁴ | - | 109,232 | | | | | | |
| | Restaurant/ Tavern/ Lounge | | 508 | Seat | 35 | 17,780 | | |
| | Bowling Alley | | 4 | Alley | 100 | 400 | | |
| | Function Hall | | 438 | Seat | 15 | 6,570 | | |
| Boston Paintball | Retail | 39,162 | 39 | 1000 SF | 50 | 1,958 | | |
| World Gym | Retail | 26,606 | 27 | 1000 SF | 50 | 1,330 | | |
| Graybar | Industrial ³ | 26,609 | 15 | Person | 15 | 225 | | |
| Home Depot | Retail | 147,608 | 148 | 1000 SF | 50 | | | 7,380 |
| Circuit City | Retail | 33,488 | 33 | 1000 SF | 50 | | | 1,675 |
| Amelia Earhart Dam | Office | 1,000 | 1 | 1000 SF | 75 | | | 75 |
| Totals: | | | | | | 29,144 | 1,217 | 9,930 |

1. Flows to be removed before next phases.

2. Population for Industrial uses based on available parking spaces.

3. Assumed population.

4. Goodtime sewer generation based on floor plan received from City of Somerville Inspectional Services on August 4, 2009.



Vanasse Hangen Brustlin, Inc.
Consulting Engineers and Planners
101 Walnut Street
Watertown, MA 02172
(617) 924-1770

Figure 3.2 - Estimated Sewer Generation and Water Demand

Project: Assembly Square Planned Unit Development
Full Build Sewer Generation - 2014 Program
Location: Somerville, Massachusetts

Proj. No.: 08518.05
Date: 4/28/2014
Computed by: HGH
Checked by:

Development Program and Projected Sewer Flows


| Phase | Block | Comments ¹ | Use ² | Area ³ (SF) | Unit | Quantity | Unit Flow ⁴ (Gal/Unit) | Average Flow (GPD) | Total Block Flow (GPD) | Total Phase Flow (GPD) ⁵ | Water Flow GPM | Peak Water GPM | | | |
|-------|-----------------------------|-----------------------|------------------|------------------------|----------------|----------|-----------------------------------|--------------------|------------------------|-------------------------------------|----------------|----------------|--------|--|--|
| 1AA | 10 | 4,500 | Restaurant | 4,500 | 1 Seat | 98 | 20 | 1,960 | 1,960 | 172,244 | 120 | 209 | | | |
| 1A | 1 | 67,530 | Retail | 43,818 | 1,000 SF | 44 | 50 | 2,191 | 76,421 | | | | | | |
| | | | Apartments | 225,615 | 1 Bedroom | 293 | 110 | 32,230 | | | | | | | |
| | | | Apartments | | Dwelling Units | 195 | | | | | | | | | |
| | | | Restaurant | 23,712 | 1 Seat | 1,200 | 35 | 42,000 | | | | | | | |
| | | | Office | 93,183 | 1,000 SF | 93 | 75 | 6,989 | | | | | | | |
| | 2B | 30,000 | Retail | 18,000 | 1,000 SF | 18 | 50 | 900 | 21,889 | | | | | | |
| | | | Restaurant | 12,000 | 1 Seat | 400 | 35 | 14,000 | | | | | | | |
| | | 122,914 | Retail | 113,914 | 1,000 SF | 114 | 50 | 5,696 | | | | | | | |
| | 3 | | Cinema | 60,000 | 1 Seat | 1,590 | 5 | 7,950 | 21,896 | | | | | | |
| | | | Bowling | 0 | 1 Lane | 0 | 100 | 0 | | | | | | | |
| | | | Restaurant | 4,500 | 1 Seat | 150 | 35 | 5,250 | | | | | | | |
| | | | Fast Food | 4,500 | 1 Seat | 150 | 20 | 3,000 | | | | | | | |
| | | | Apartments | 249,964 | 1 Bedroom | 389 | 110 | 42,790 | | | | | | | |
| | 4 | | Apartments | | Dwelling Units | 253 | | | 48,539 | | | | | | |
| | | 43,975 | Retail | 40,775 | 1,000 SF | 41 | 50 | 2,039 | | | | | | | |
| | | | Restaurant | 3,200 | 1 Seat | 106 | 35 | 3,710 | | | | | | | |
| | KIOSK | 3,605 | Fast Food | 3,605 | 1 Seat | 77 | 20 | 1,540 | 1,540 | | | | | | |
| | Full Build Remaining Phases | 5 | 60,000 | Retail | 43,200 | 1,000 SF | 43 | 50 | 2,160 | | | | 57,805 | | |
| | | | | Office | 250,000 | 1,000 SF | 250 | 75 | 18,750 | | | | | | |
| | | | Apartments | 0 | 1.7 Bedroom | 0 | 187 | 0 | | | | | | | |
| | | | Fast Food | 3,800 | 1 Seat | 152 | 20 | 3,040 | | | | | | | |
| | | | Hotel | 104,550 | 1 Bedroom | 170 | 110 | 18,700 | | | | | | | |
| | | | Restaurant | 13,000 | 1 Seat | 433 | 35 | 15,155 | | | | | | | |
| 6A | | 35,000 | Retail | 25,000 | 1,000 SF | 25 | 50 | 1,250 | 12,000 | | | | | | |
| | | | Office | 0 | 1,000 SF | 0 | 75 | 0 | | | | | | | |
| | | | Fast Food | 2,500 | 1 Seat | 100 | 20 | 2,000 | | | | | | | |
| | | | Restaurant | 7,500 | 1 Seat | 250 | 35 | 8,750 | | | | | | | |
| 6B | | - | Condo | 486,000 | 1.7 Bedroom | 405 | 187 | 75,735 | 75,735 | | | | | | |
| | | | Retail | 0 | 1,000 SF | 0 | 50 | 0 | | | | | | | |
| | | | Fast Food | 0 | 1 Seat | 0 | 20 | 0 | | | | | | | |
| | | | Restaurant | 0 | 1 Seat | 0 | 35 | 0 | | | | | | | |
| 7 | | 48,500 | Retail | 30,000 | 1,000 SF | 30 | 50 | 1,500 | 175,230 | | | | | | |
| | | | Office | 450,000 | 1,000 SF | 450 | 75 | 33,750 | | | | | | | |
| | | | Office | 0 | 1,000 SF | 0 | 75 | 0 | | | | | | | |
| | | | Condo | 768,000 | 1.7 Bedroom | 640 | 187 | 119,680 | | | | | | | |
| | | | Fast Food | 3,500 | 1 Seat | 140 | 20 | 2,800 | | | | | | | |
| | | | Restaurant | 15,000 | 1 Seat | 500 | 35 | 17,500 | | | | | | | |
| 8 | | 36,000 | Retail | 20,000 | 1,000 SF | 20 | 50 | 1,000 | 125,136 | | | | | | |
| | | | Office | 553,150 | 1,000 SF | 553 | 75 | 41,486 | | | | | | | |
| | | | Fast Food | 4,000 | 1 Seat | 160 | 20 | 3,200 | | | | | | | |
| | | | Restaurant | 12,000 | 1 Seat | 400 | 35 | 14,000 | | | | | | | |
| | | | Condo | 420,000 | 1.7 Bedroom | 350 | 187 | 65,450 | | | | | | | |
| 9 | | | Office | 300,000 | 1,000 SF | 300 | 75 | 22,500 | 22,500 | | | | | | |
| 11 | | 75,000 | Retail | 40,000 | 1,000 SF | 40 | 50 | 2,000 | 133,970 | | | | | | |
| | | | Office | 1,155,000 | 1,000 SF | 1,155 | 75 | 86,625 | | | | | | | |
| | | | Fast Food | 15,000 | 1 Seat | 600 | 20 | 12,000 | | | | | | | |
| | | | Restaurant | 20,000 | 1 Seat | 667 | 35 | 23,345 | | | | | | | |
| | | | Health Club | 50,000 | 1 Locker | 500 | 20 | 10,000 | | | | | | | |
| | | | | 5,692,486 | 774,620 | | | | FULL BUILD TOTAL | 774,620 | 538 | 941 | | | |

Notes:

- 1) Retail was space allocated at by 20.3% for estimated restaurant areas and by 6.0% for fast food within all future Blocks.
Future Phase Building Program info taken from Street-Works LLC Proposed Phasing Schedule dated 2/13/09. Total restaurant area - 121,701 square feet (includes Block 10 and IKEA).
- 2) Restaurant seats are based on 30 square feet per seat within future phases.
- 3) Average flows for Massachusetts are based on 314 CMR 7: Sewer System Extension and Connection Program.
- 4) Not used.
- 5) The previously permitted sewer flow for both Phase 1AA and Phase 1A is 173,146 gpd. The current building program from actual tenanting information for Phase 1AA and 1A is 1,257 gpd less than permitted. The surplus sewer flow will be applied to the Full Build Remaining Phases.
- 6) The Full Build Remaining Phases requested permit flows are 650,003 gpd. The sewer flow shown on this table for the Full Build Remaining Phases includes surplus sewer flow from previous phases (1,257 gpd).

Appendix A

Water System Analysis



Vanasse Hangen Brustlin, Inc.

Water Model May 2, 2014

Water Plan Full Build Out
Assembly Square PUD
Assembly Square Drive
Somerville, Massachusetts



Flow Test Information Sheet

VHB project number: 11496.00
VHB project name: BLOCK 1 & BLOCK 4

Location of test: ASSEMBLY SQUARE DRIVE (NEW SECTION)
(Fire hydrant number if any)

Date & time of test: Date: 8/18/2011 Time: 9:00 (pm)(pm)

Temperature: 80 (F)

Test conducted by: RICHARD P. MATTHEWS JR. PE - VHB

Test witnessed by: TIMOTHY HAYES - VHB SOMERVILLE WATER DEPT


Name of Water District: CITY OF SOMERVILLE

Name of Fire District: " " "

Source of Water Supply: Gravity ☐ Pump ☐ Other MWRA

Is water supply provided by: PRV STA's ☐ YES ☐ NO ☐

Area Map: (Draw Sketch showing property location; bounding streets and names, north arrow, hydrant location and identification numbers, distances from hydrants to property, elevations of hydrants and building floors & grade, all water mains and sizes interconnection valves, etc.)




Flow Test Data:

| Flow at Hydr. No. | Elevation at Hydr | Static at Hydr. No. | Static PSIG | Residual PSIG | Flow PSIG | Outlet size and coefficient | GPM |
|-------------------|---------------------|---------------------|-------------|---------------|-----------|-----------------------------|-------------|
| <u>2</u> | <u>13</u> <u>13</u> | <u>1</u> | <u>77</u> | <u>69</u> | <u>57</u> | <u>2.5"</u> <u>0.9</u> | <u>1265</u> |
| | | | | | | | |
| | | | | | | | |

Miscellaneous comments: HYDRANTS ARE MSH MODEL 929 5 1/4"
W/ 2 1/2" HOSE CONNECTIONS

Signed: [Signature]

Witness: [Signature]



Flow Test Information Sheet

VHB project number: 08518.03

VHB project name: Assembly Square PUD

Location of test: Middlesex Ave @ Memory Ln / McGrath Highway / Kensington
(Fire hydrant number if any)

Date & time of test: Date: 9/13/06 Time: 10:20 (am) (pm)

Temperature: _____ (F)

Test conducted by: Lenny Dodge & Dennis Grieco

Test witnessed by: _____


Name of Water District: Somerville, MA

Name of Fire District: Somerville, MA

Source of Water Supply: Gravity ☐ Pump ☒ Other _____

Is water supply provided by: PRV STA's ☐ YES ☐ NO ☐

Area Map: (Draw Sketch showing property location; bounding streets and names, north arrow, hydrant location and identification numbers, distances from hydrants to property, elevations of hydrants and building floors & grade, all water mains and sizes interconnection valves, etc.)



ASSEMBLY SQUARE MALL




Flow Test Data:

| Flow at Hydr. No. | Elevation at Hydr. | Static at Hydr. No. | Static PSIG | Residual PSIG | Flow PSIG | Outlet size and coefficient | | GPM Co. (@ 20') |
|-------------------|--------------------|---------------------|-------------|---------------|-----------|-----------------------------|-----|-----------------|
| 1 | | 2 | 72 | 69 | 52 | 2 1/2 | 0.9 | 5645 |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

Miscellaneous comments: _____

Signed: _____

Witness: _____





Computations

Project: ASSEMBLY SQUARE Project # 08518-03

Location: SOMERVILLE, MA Sheet 1 of 1

Calculated by: DAG Date: 9/13/06

Checked by: MVH Date: 9/13/06

Title

HYDRANT FLOW TEST

RESIDUAL HYDRANT - #2

FLOWED HYDRANT - #1

2 1/2" ORIFICE

OUTLET SMOOTH AND ROUNDED - C = 0.9

STATIC PRESSURE #2 = 72 PSI

RESIDUAL PRESSURE #2 = 69 PSI

FLOWING PITOT PRESSURE #1 = 52 PSI
(VELOCITY HEAD)

THEORETICAL FLOW = 1344 GPM

ACTUAL FLOW = $0.9(1344)$
= 1210 GPM

⇒ CONVERSION TO BASE OF 20 PSI

$$Q_R = Q_F \times \frac{h_r^{.54}}{h_f^{.54}}$$

$$Q_R = 1210 \times \frac{(72-20)^{.54}}{(72-59)^{.54}} \quad \begin{matrix} (8.46) \\ (1.81) \end{matrix}$$

$Q_R = 5645 \text{ GPM @ 20 PSI}$



Flow Test Information Sheet

VHB project number: 08518.03

VHB project name: ASSEMBLY SQUARE - IKEA

Location of test: SOMERVILLE, MA @ ASSEMBLY SQUARE DRIVE.
(Fire hydrant number if any)

Date & time of test: Date: 3/14/07 Time: 1:45 (am) (pm)

Temperature: 71° (F)

Test conducted by: DENNIS GRIFFICI & MICHAEL GOODMAN

Test witnessed by: _____

Name of Water District: _____

Name of Fire District: _____

Source of Water Supply: Gravity ☐

Pump ☐

Other _____


Is water supply provided by: PRV STA's ☐

YES ☐

NO ☐

Area Map:

(Draw Sketch showing property location; bounding streets and names, north arrow, hydrant location and identification numbers, distances from hydrants to property, elevations of hydrants and building floors & grade, all water mains and sizes interconnection valves, etc.)






Flow Test Data:

| Flow at Hydr. No. | Elevation at Hydr. | Static at Hydr. No. | Static PSIG | Residual PSIG | Flow PSIG | Outlet size and coefficient | GPM @ (20') |
|-------------------|--------------------|---------------------|-------------|---------------|-----------|-----------------------------|-------------|
| 1 | | 2 | 73 | 68 | 58 | 2 1/2" 0.9 | 4573 |
| 3 | | 4 | 66 | 61 | 48 | 2 1/2" 0.9 | 3855 |

Miscellaneous comments: _____

Signed: Mark De

Witness: Ken





Computations

Project: ASSEMBLY SQ / IKEA

Project # 0851802

Location: LOWELL, MA

Sheet 1 of

Calculated by: DAG

Date: 3/16/02

Checked by: MUG

Date: 3/16/07

Title

HYDRANT FLOW TEST #1

RESIDUAL HYDRANT - # 2

FLOWED HYDRANT - # 1

2 1/2" ORIFICE

OUTLET SMOOTH & ROUNDED C = 0.90

STATIC PRESSURE @ #2 = 73 PSI

RESIDUAL PRESSURE @ #2 = 68 PSI

FLOWING PITOT PRESSURE @ #1 = 58

THEORETICAL FLOW : $Q = 29.83 C d^2 \sqrt{P}$

$$Q = 29.83 (.9) (2.5^2) (\sqrt{58}) = 1277.9 \text{ GPM}$$

⇒ CONVERSION TO BASE OF 20 PSI

$$Q_R = Q_F \times \frac{H_R^{.54}}{H_F^{.54}}$$

$$Q_R = 1278 \times \frac{(73 - 20)^{.54}}{(73 - 68)^{.54}} = \underline{\underline{4573 \text{ GPM @ 20 PSI}}}$$



Computations

Project:

Location:

Calculated by: DAG

Checked by:

Title

Project # 08518.03

Sheet 2 of 2

Date: 3/14/07

Date:

HYDRANT FLOW TEST #2

RESIDUAL HYDRANT - #3

FLOWED HYDRANT - #4

2 1/2" ORIFICE

OUTLET SMOOTH & ROUNDED $C = 0.90$

STATIC PRESSURE @ #3 = 66 PSI

RESIDUAL PRESSURE @ #3 = 61 PSI

FLOWING PRESSURE @ #4 = 48 PSI

THEORETICAL FLOW: $Q = 29.83 C d^2 \sqrt{P}$

$$Q = 29.83 (.9) (2.5^2) \sqrt{48} = 1162.5 \text{ GPM}$$

⇒ CONVERSION TO BASE OF 20 PSI

$$Q_R = Q_F \times \frac{H_R^{.54}}{H_F^{.54}}$$

$$Q_R = 1163 \times \frac{(66-20)^{.54}}{(66-61)^{.54}} = \underline{3855 \text{ GPM @ 20 PSI}}$$



Flow Test Information Sheet

VHB project number: 08518.05

VHB project name: Assembly Row

Location of test: Block 6
(Fire hydrant number if any)

Date & time of test: Date: 09-12-2014 Time: 10:30 am (am) (pm)

Temperature: 68°F (F)

Test conducted by: Richard Mathews - VHB ; Mi Lian - VHB

Test witnessed by: (Water Dept) P. Brennan - WSP


Name of Water District: Somerville Water Department

Name of Fire District: Somerville Fire Department

Source of Water Supply: Gravity ☐ Pump ☐ Other MWRA

Is water supply provided by: PRV STA's ☐ YES ☐ NO ☐

Area Map: (Draw Sketch showing property location; bounding streets and names, north arrow, hydrant location and identification numbers, distances from hydrants to property, elevations of hydrants and building floors & grade, all water mains and sizes interconnection valves, etc.)




Flow Test Data:

| Flow at Hydr. No. | Elevation at Hydr. | Static at Hydr. No. | Static PSIG | Residual PSIG | Flow PSIG | Outlet size and coefficient | | GPM |
|-------------------|--------------------|---------------------|-------------|---------------|-----------|-----------------------------|-----|------|
| # 2 | 13.5 | # 1 | 68 | 66 | 52 | 2 1/2 | 0.9 | 1210 |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

Miscellaneous comments: Hydrants are m & H model 929 5 1/4"
w/ 2 1/2" hose connections

Signed: _____

Witness: _____



Project:
Location:
Calculated by:
Checked by:
Title

Assembly Row
Block 6
Mi Lian
R. Mathews
Flow Test - Block 6

Project # 08518-05
Sheet 1 of 2
Date: 9-12-2014
Date: 9-15-2014

Hydrant Flow Test

Residual Hydrant - #1

Flowed Hydrant - #2

2 1/2" Orifice

Outlet Smooth and Rounded - C = 0.90

Static Pressure #1 = 68 psi

Residual Pressure #1 = 66 psi

flowing pitot pressure #2 = 52 psi

$$\begin{aligned} \text{Actual Flow} \rightarrow Q_f &= 29.83 C \cdot d^2 \cdot \sqrt{P} \\ &= 29.83 \times 0.90 \times 2.5^2 \cdot \sqrt{52} \\ &= 1209.98 \\ &= 1210 \text{ gpm} \end{aligned}$$



Project:

Location:

Calculated by:

Checked by:

Title

Assembly Row

Block 6

N. Lian

R. Mathews

Flow Test - Block 6

Project #

08518.05

Sheet

2 of 2

Date:

9-12-2014

Date:

9-15-2014

Conversion To Base of 20 psf

$$Q_r = Q_f \cdot \frac{h_r^{0.54}}{h_f^{0.54}} \cdot \frac{(\text{Pressure drop to desired pressure})^{0.54}}{(\text{Pressure drop during test})^{0.54}}$$

$$= 1210 \cdot \frac{(68 - 20)^{0.54}}{(68 - 66)^{0.54}}$$

$$= 1210 \cdot 5.563$$


$$= 6731 \text{ GPM @ 20 psi}$$



Water Flow Test Summary Sheet

Conducted by Richard Mathews Location Block 6 Date 09-12-2014
Hydrant coefficient 0.90 Elevation 13.5 Static 68 Residual 66 @ Flow 1210 gpm


CENTER



Flow Test Information Sheet


VHB project number: 08518.05VHB project name: Block 5Location of test: Canal St
(Fire hydrant number if any)Date & time of test: Date: 11/19/15 Time: 10:15 (am) (pm)Temperature: 49°F (F)Test conducted by: Dale Horsman, PE -VHB Richard Mathews Jr., PE VHBTest witnessed by: Richard Mathews Jr., PE-UHB SOMERVILLE WATER DEPT.Name of Water District: City of SomervilleName of Fire District: " " "Source of Water Supply: Gravity ☐ Pump ☐ Other MWRAIs water supply provided by: PRV STA's ☐ YES ☐ NO ☐

Area Map: (Draw Sketch showing property location; bounding streets and names, north arrow, hydrant location and identification numbers, distances from hydrants to property, elevations of hydrants and building floors & grade, all water mains and sizes interconnection valves, etc.)



Flow Test Data:


| Flow at Hydr. No. | Elevation at Hydr. | Static at Hydr. No. | Static PSIG | Residual PSIG | Flow PSIG | Outlet size and coefficient | | GPM |
|-------------------|--------------------|---------------------|-------------|---------------|-----------|-----------------------------|-----|------|
| 1 | 13.0 | 2 | 72 | 70 | 60 | 2 1/2 | 0.9 | 1300 |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

Miscellaneous comments: HYDRANTS ARE M&H MODEL 929 5 1/4" W 2 1/2"
HOSE CONNECTIONSSigned: Dale A. Horsman PEWitness: Richard Mathews Jr. PE



Water Flow Test Summary Sheet

Conducted by Dale Husman Location Black 5 Canal St Date 11/17/15
Hydrant coefficient 0.90 Elevation _____ Static 72 Residual 70 @ Flow 1300





Computations

Project: Block 5 Canal St. Project # 08518.05

Location: SOMERVILLE MA Sheet 2 of 2

Calculated by: DAN

Date: 11/19/15

Checked by: R.M.

Date:

Title Flow Test - Block 5 Canal St.

HYDRANT FLOW TEST

RESIDUAL HYDRANT #2

FLOWED HYDRANT - #1

2 1/2 ORIFICE, OUTLET SMOOTH AND ROUNDED C=0.9

STATIC PRESSURE #2 = 72 psi

RESIDUAL PRESSURE #2 = 70 psi

FLOWING PILOT PRESSURE #1 = 60 psi

$$\begin{aligned} \text{Actual FLOW} \rightarrow Q_F &= 29.83 C d^2 \sqrt{P} \\ &= 29.83 \times .90 \times 2.5^2 \sqrt{60} \\ &= 1299.72 \approx 1300 \text{ GPM} \end{aligned}$$

Conversion to Base 20 psi

$$\begin{aligned} Q_r &= Q_f \frac{h_r^{0.54}}{h_f^{0.54}} = \frac{(\text{Pressure drop to desired Pressure})^{0.54}}{(\text{Pressure drop during test})^{0.54}} \\ &= 1300 \times \left(\frac{(72-20)^{0.54}}{(72-70)^{0.54}} \right) \\ &= 1300 \times 5.809 \\ &= 7551.43 \text{ GPM @ } 20 \text{ psi} \end{aligned}$$



Flow Test Information Sheet

VHB project number: 08518.05

VHB project name: Block 5

Location of test: Foley St.
(Fire hydrant number if any)

Date & time of test: Date: 11/19/15 Time: 10:00 (am) (pm)

Temperature: 49°F (F)

Test conducted by: Dale Horsman, PE - VHB Richard Mathews, JR, PE VHB

Test witnessed by: Richard Mathews, JR, PE VHB SOMERVILLE WATER DEPT.


Name of Water District: City of SOMERVILLE

Name of Fire District: " " "

Source of Water Supply: Gravity ☐ Pump ☐ Other MWRA

Is water supply provided by: PRV STA's ☐ YES ☐ NO ☐

Area Map: (Draw Sketch showing property location; bounding streets and names, north arrow, hydrant location and identification numbers, distances from hydrants to property, elevations of hydrants and building floors & grade, all water mains and sizes interconnection valves, etc.)




Flow Test Data:

| Flow at Hydr. No. | Elevation at Hydr. | Static at Hydr. No. | Static PSIG | Residual PSIG | Flow PSIG | Outlet size and coefficient | | GPM |
|-------------------|--------------------|---------------------|-------------|---------------|-----------|-----------------------------|------------|-------------|
| <u>1</u> | <u>12.95</u> | <u>2</u> | <u>74</u> | <u>72</u> | <u>62</u> | <u>2 1/2"</u> | <u>0.9</u> | <u>1321</u> |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

Miscellaneous comments: HYDRANTS ARE M&H MODEL 929 5 1/4" w/ 2 1/2"
HOSE CONNECTIONS


Signed: Dale A. Horsman, PE
Witness: Richard Mathews, JR, PE





Water Flow Test Summary Sheet

Conducted by Dale Hanson Location Block 5 Fokus St Date 11/19/15
Hydrant coefficient .90 Elevation Static 74 Residual 72 @ Flow 1321



200 400 600 800 1000 1200 1400 1600 1800 2000 Scale A
400 800 1200 1600 2000 2400 2800 3200 3600 4000 Scale B
800 1600 2400 3200 4000 4800 5600 6400 7200 Scale C



Computations

ASSEMBLY SQUARE

Project: BLOCK 5 FOLEY ST

Project # 08518.05

Location: SOME

Sheet 2 of 2

Calculated by: DAH

Date: 11/19/15

Checked by:

Date:

Title

HYDRANT FLOW TEST

RESIDUAL HYDRANT - #2

FLOWED HYDRANT - #1

2-1/2" ORIFICE, OUTLET SMOOTH AND ROUNDED $C=0.9$

STATIC PRESSURE #2 = 74 psi

RESIDUAL PRESSURE #2 = 72 psi

FLOWING PILOT PRESSURE #1 = 62 psi

$$\begin{aligned}\text{Actual Flow } \rightarrow Q_f &= 29.83 \text{ c} d^2 \sqrt{P} \\ &= 29.83 \times .90 \times 2.5^2 \times \sqrt{62} \\ &= 1321.21 \approx 1321 \text{ GPM}\end{aligned}$$

Conversions to base 20 psi

$$Q_r = Q_f \times \frac{h_r^{0.54}}{h_f^{0.54}} \quad \frac{(\text{PRESSURE DROP TO DESIRED PRESSURE})^{0.54}}{(\text{PRESSURE DROP DURING TEST})^{0.54}}$$

$$= 1321 \text{ GPM} \times \left(\frac{(74-20)^{0.54}}{(74-72)^{0.54}} \right)$$

$$= 1321 \text{ GPM} \times 5.928$$

$$= 7831.40 \text{ GPM @ } 20 \text{ psi}$$

Scenario: 3,500 ISO
Current Time Step: 0.000 Hr
Fire Flow Node FlexTable: Fire Flow Report

| Label | Zone | Fire Flow Iterations | Satisfies Fire Flow Constraints? | Fire Flow (Needed) (gpm) | Fire Flow (Available) (gpm) | Flow (Total Needed) (gpm) | Flow (Total Available) (gpm) | Pressure (Residual Lower Limit) (psi) |
|-----------------------|--------|----------------------|----------------------------------|--------------------------|-----------------------------|---------------------------|------------------------------|---------------------------------------|
| A C Moore | Zone | 11 | False | 3,500.00 | 2,247.37 | 3,503.00 | 2,250.37 | 20.0 |
| Ashton Fuel/Hillside | Zone | 4 | False | 3,500.00 | 3,190.13 | 3,502.00 | 3,192.13 | 20.0 |
| Bed Bath & Beyond | Zone | 9 | False | 3,500.00 | 2,923.59 | 3,503.00 | 2,926.59 | 20.0 |
| Block 1 | Zone | 4 | True | 3,500.00 | 4,166.05 | 3,583.00 | 4,249.05 | 20.0 |
| Block 2 | Zone | 4 | True | 3,500.00 | 4,119.76 | 3,540.00 | 4,159.76 | 20.0 |
| Block 3 | Zone | 4 | True | 3,500.00 | 4,054.81 | 3,660.00 | 4,214.81 | 20.0 |
| Block 4A | Zone | 4 | True | 3,500.00 | 4,136.68 | 3,570.00 | 4,206.68 | 20.0 |
| Block 5 | Zone | 4 | True | 3,500.00 | 4,157.55 | 3,604.00 | 4,261.55 | 20.0 |
| Block 6A | Zone | 4 | True | 3,500.00 | 4,082.57 | 3,524.00 | 4,106.57 | 20.0 |
| Block 6B/C | Zone | 4 | True | 3,500.00 | 4,116.45 | 3,601.00 | 4,217.45 | 20.0 |
| Block 7A | Zone | 4 | True | 3,500.00 | 4,111.53 | 3,636.00 | 4,247.53 | 20.0 |
| Block 8A | Zone | 4 | True | 3,500.00 | 4,017.12 | 3,543.00 | 4,060.12 | 20.0 |
| Block 8B | Zone | 4 | True | 3,500.00 | 4,121.07 | 3,581.00 | 4,202.07 | 20.0 |
| Block 9 | Zone | 4 | True | 3,500.00 | 4,131.42 | 3,545.00 | 4,176.42 | 20.0 |
| Block 10 | Zone | 3 | True | 3,500.00 | 3,608.71 | 3,511.00 | 3,619.71 | 20.0 |
| Christian Assembly | Zone | 4 | True | 3,500.00 | 4,337.15 | 3,501.00 | 4,338.15 | 20.0 |
| Christmas Tree Shops | Zone | 10 | False | 3,500.00 | 2,387.65 | 3,504.00 | 2,391.65 | 20.0 |
| Circuit City | Zone | 4 | True | 3,500.00 | 4,224.06 | 3,502.00 | 4,226.06 | 20.0 |
| Court | Zone | 4 | True | 3,500.00 | 4,250.56 | 3,503.00 | 4,253.56 | 20.0 |
| Dam | Zone | 4 | True | 3,500.00 | 4,288.47 | 3,501.00 | 4,289.47 | 20.0 |
| Dunkin Donuts/Sunrise | Zone | 4 | True | 3,500.00 | 4,359.93 | 3,503.00 | 4,362.93 | 20.0 |
| Ecco Tracer | Zone | 3 | False | 3,500.00 | 3,370.73 | 3,503.00 | 3,373.73 | 20.0 |
| Enterprise | Zone | 4 | False | 3,500.00 | 3,153.23 | 3,501.00 | 3,154.23 | 20.0 |
| H-2 | <None> | 4 | True | 3,500.00 | 3,698.38 | 3,500.00 | 3,698.38 | 20.0 |
| H-3 | <None> | 4 | True | 3,500.00 | 4,148.00 | 3,500.00 | 4,148.00 | 20.0 |
| Home Depot | Zone | 4 | True | 3,500.00 | 4,201.57 | 3,509.00 | 4,210.57 | 20.0 |
| J-2 | Zone | 5 | True | 3,500.00 | 4,397.65 | 3,500.00 | 4,397.65 | 20.0 |
| J-5 | Zone | 4 | True | 3,500.00 | 4,183.30 | 3,500.00 | 4,183.30 | 20.0 |
| J-6 | Zone | 3 | False | 3,500.00 | 3,480.22 | 3,500.00 | 3,480.22 | 20.0 |
| J-7 | Zone | 3 | False | 3,500.00 | 3,415.77 | 3,500.00 | 3,415.77 | 20.0 |
| J-8 | Zone | 4 | False | 3,500.00 | 3,253.81 | 3,500.00 | 3,253.81 | 20.0 |
| J-9 | Zone | 4 | False | 3,500.00 | 3,161.09 | 3,500.00 | 3,161.09 | 20.0 |
| J-9 | Zone | 5 | True | 3,500.00 | 4,363.44 | 3,500.00 | 4,363.44 | 20.0 |
| J-10 | Zone | 4 | False | 3,500.00 | 3,160.21 | 3,500.00 | 3,160.21 | 20.0 |
| J-11 | Zone | 3 | False | 3,500.00 | 3,323.55 | 3,500.00 | 3,323.55 | 20.0 |
| J-12 | Zone | 3 | False | 3,500.00 | 3,417.63 | 3,500.00 | 3,417.63 | 20.0 |
| J-14 | Zone | 4 | False | 3,500.00 | 3,179.46 | 3,500.00 | 3,179.46 | 20.0 |
| J-15 | Zone | 9 | False | 3,500.00 | 2,932.48 | 3,500.00 | 2,932.48 | 20.0 |
| J-16 | Zone | 10 | False | 3,500.00 | 2,829.30 | 3,500.00 | 2,829.30 | 20.0 |
| J-17 | Zone | 10 | False | 3,500.00 | 2,620.32 | 3,500.00 | 2,620.32 | 20.0 |
| J-18 | Zone | 11 | False | 3,500.00 | 2,459.28 | 3,500.00 | 2,459.28 | 20.0 |
| J-19 | Zone | 10 | False | 3,500.00 | 2,471.68 | 3,500.00 | 2,471.68 | 20.0 |
| J-20 | Zone | 9 | False | 3,500.00 | 2,938.55 | 3,500.00 | 2,938.55 | 20.0 |
| J-21 | Zone | 4 | True | 3,500.00 | 3,828.23 | 3,500.00 | 3,828.23 | 20.0 |
| J-29 | Zone | 4 | False | 3,500.00 | 2,986.81 | 3,500.00 | 2,986.81 | 20.0 |
| J-30 | Zone | 4 | True | 3,500.00 | 4,239.23 | 3,500.00 | 4,239.23 | 20.0 |
| J-33 | Zone | 5 | True | 3,500.00 | 4,411.58 | 3,500.00 | 4,411.58 | 20.0 |
| J-34 | Zone | 5 | True | 3,500.00 | 4,403.80 | 3,500.00 | 4,403.80 | 20.0 |
| J-44 | Zone | 4 | True | 3,500.00 | 3,739.90 | 3,500.00 | 3,739.90 | 20.0 |
| J-45 | Zone | 4 | True | 3,500.00 | 3,992.06 | 3,500.00 | 3,992.06 | 20.0 |
| J-46 | Zone | 4 | True | 3,500.00 | 4,044.44 | 3,500.00 | 4,044.44 | 20.0 |
| J-47 | Zone | 4 | True | 3,500.00 | 4,109.79 | 3,500.00 | 4,109.79 | 20.0 |
| J-49 | Zone | 4 | True | 3,500.00 | 4,088.97 | 3,500.00 | 4,088.97 | 20.0 |
| J-51 | Zone | 4 | True | 3,500.00 | 4,175.76 | 3,500.00 | 4,175.76 | 20.0 |
| J-54 | Zone | 5 | True | 3,500.00 | 4,366.35 | 3,500.00 | 4,366.35 | 20.0 |
| J-54 | Zone | 4 | True | 3,500.00 | 4,291.90 | 3,500.00 | 4,291.90 | 20.0 |
| J-56 | Zone | 4 | True | 3,500.00 | 4,242.00 | 3,500.00 | 4,242.00 | 20.0 |
| J-57 | Zone | 4 | True | 3,500.00 | 4,260.68 | 3,500.00 | 4,260.68 | 20.0 |
| J-59 | Zone | 4 | True | 3,500.00 | 4,155.64 | 3,500.00 | 4,155.64 | 20.0 |
| J-60 | Zone | 4 | True | 3,500.00 | 4,096.89 | 3,500.00 | 4,096.89 | 20.0 |
| J-62 | Zone | 4 | True | 3,500.00 | 4,282.19 | 3,500.00 | 4,282.19 | 20.0 |
| J-63 | Zone | 4 | True | 3,500.00 | 4,268.72 | 3,500.00 | 4,268.72 | 20.0 |

| | | | | | | | | |
|------------------------------|--------|----|-------|----------|----------|----------|----------|------|
| J-64 | Zone | 4 | True | 3,500.00 | 4,332.45 | 3,500.00 | 4,332.45 | 20.0 |
| J-65 | Zone | 4 | True | 3,500.00 | 4,313.64 | 3,500.00 | 4,313.64 | 20.0 |
| J-66 | Zone | 4 | True | 3,500.00 | 4,299.40 | 3,500.00 | 4,299.40 | 20.0 |
| J-67 | Zone | 4 | True | 3,500.00 | 4,290.76 | 3,500.00 | 4,290.76 | 20.0 |
| J-68 | Zone | 4 | True | 3,500.00 | 4,297.96 | 3,500.00 | 4,297.96 | 20.0 |
| J-68 | Zone | 4 | True | 3,500.00 | 4,233.26 | 3,500.00 | 4,233.26 | 20.0 |
| J-70 | Zone | 4 | True | 3,500.00 | 4,293.58 | 3,500.00 | 4,293.58 | 20.0 |
| J-70 | Zone | 4 | True | 3,500.00 | 4,260.99 | 3,500.00 | 4,260.99 | 20.0 |
| J-75 | Zone | 4 | True | 3,500.00 | 4,292.65 | 3,500.00 | 4,292.65 | 20.0 |
| J-75 | Zone | 4 | True | 3,500.00 | 4,319.20 | 3,500.00 | 4,319.20 | 20.0 |
| J-77 | Zone | 4 | True | 3,500.00 | 4,319.67 | 3,500.00 | 4,319.67 | 20.0 |
| J-79 | Zone | 3 | True | 3,500.00 | 3,588.90 | 3,500.00 | 3,588.90 | 20.0 |
| J-82 | Zone | 4 | True | 3,500.00 | 4,290.11 | 3,500.00 | 4,290.11 | 20.0 |
| J-83 | Zone | 4 | True | 3,500.00 | 4,287.28 | 3,500.00 | 4,287.28 | 20.0 |
| J-84 | Zone | 4 | True | 3,500.00 | 4,285.59 | 3,500.00 | 4,285.59 | 20.0 |
| J-85 | Zone | 4 | True | 3,500.00 | 4,285.99 | 3,500.00 | 4,285.99 | 20.0 |
| J-115 | Zone | 3 | True | 3,500.00 | 3,561.61 | 3,500.00 | 3,561.61 | 20.0 |
| J-159 | <None> | 5 | True | 3,500.00 | 4,687.00 | 3,500.00 | 4,687.00 | 20.0 |
| J-160 | <None> | 5 | True | 3,500.00 | 4,489.73 | 3,500.00 | 4,489.73 | 20.0 |
| J-161 | <None> | 4 | True | 3,500.00 | 4,185.66 | 3,500.00 | 4,185.66 | 20.0 |
| J-162 | <None> | 4 | True | 3,500.00 | 3,970.62 | 3,500.00 | 3,970.62 | 20.0 |
| La Quinta | Zone | 3 | True | 3,500.00 | 3,647.98 | 3,523.00 | 3,670.98 | 20.0 |
| Office | Zone | 4 | True | 3,500.00 | 4,128.02 | 3,510.00 | 4,138.02 | 20.0 |
| Parcel 11A (Domestic) | Zone | 4 | True | 3,500.00 | 4,168.72 | 3,620.00 | 4,288.72 | 20.0 |
| Parcel 11A (Fire Connection) | Zone | 4 | True | 3,500.00 | 4,257.46 | 3,500.00 | 4,257.46 | 20.0 |
| Pub 99 Restaurant | Zone | 4 | True | 3,500.00 | 4,281.75 | 3,517.00 | 4,298.75 | 20.0 |
| Spaulding Brick | Zone | 4 | True | 3,500.00 | 4,300.10 | 3,501.00 | 4,301.10 | 20.0 |
| Sports Authority | Zone | 4 | False | 3,500.00 | 3,043.81 | 3,503.00 | 3,046.80 | 20.0 |
| Staples | Zone | 10 | False | 3,500.00 | 2,575.26 | 3,503.00 | 2,578.26 | 20.0 |
| T J Maxx | Zone | 4 | False | 3,500.00 | 2,984.14 | 3,504.00 | 2,988.14 | 20.0 |
| Theater | Zone | 4 | True | 3,500.00 | 4,308.47 | 3,515.00 | 4,323.48 | 20.0 |
| Truck Company | Zone | 5 | True | 3,500.00 | 4,378.08 | 3,502.00 | 4,380.08 | 20.0 |
| Warehouse | Zone | 4 | True | 3,500.00 | 4,281.17 | 3,501.00 | 4,282.17 | 20.0 |
| WHYC | Zone | 4 | True | 3,500.00 | 4,285.77 | 3,501.00 | 4,286.77 | 20.0 |

\\Vhb\proj\Wat-LD\08518.05\tech\WaterCad\0851805 Water AmPUD MAY-2014.wtg

Scenario: 3,500 ISO
Current Time Step: 0.000 Hr
Pipe FlexTable:

| Label | Length (Scaled) (ft) | Start Node | Stop Node | Diameter (in) | Material | Hazen- Williams C | Minor Loss Coefficient (Local) |
|-------|----------------------------|----------------------|-----------------------|------------------|--------------|-------------------------|---|
| P-63 | 308.53 | J-63 | J-64 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-66 | 263.28 | J-66 | J-67 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-32 | 96.71 | J-33 | Truck Company | 20.0 | Ductile Iron | 130.0 | 1.280 |
| P-22 | 498.70 | Spaulding Brick | Court | 20.0 | Ductile Iron | 80.0 | 0.390 |
| P-64 | 140.75 | J-64 | J-65 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-65 | 47.49 | J-65 | J-66 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-36 | 257.64 | J-68 | J-54 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-35 | 50.22 | J-54 | J-9 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-49 | 267.82 | J-49 | J-51 | 12.0 | Ductile Iron | 110.0 | 1.280 |
| P-31 | 187.12 | Truck Company | Dunkin Donuts/Sunrise | 20.0 | Ductile Iron | 80.0 | 0.390 |
| P-3 | 299.22 | Christian Assembly | Spaulding Brick | 20.0 | Ductile Iron | 80.0 | 0.390 |
| P-24 | 205.30 | Pub 99 Restaurant | Warehouse | 16.0 | Ductile Iron | 100.0 | 0.390 |
| P-25 | 207.72 | Warehouse | Dunkin Donuts/Sunrise | 12.0 | Ductile Iron | 80.0 | 0.390 |
| P-23 | 278.25 | J-2 | Pub 99 Restaurant | 16.0 | Ductile Iron | 80.0 | 0.390 |
| P-68 | 235.11 | J-68 | J-68 | 20.0 | Ductile Iron | 130.0 | 1.280 |
| P-69 | 196.43 | J-68 | J-70 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-70 | 238.60 | J-70 | J-54 | 20.0 | Ductile Iron | 130.0 | 1.280 |
| P-46 | 226.19 | J-47 | J-46 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-45 | 70.90 | J-46 | J-45 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-44 | 275.57 | J-45 | J-44 | 12.0 | Ductile Iron | 110.0 | 0.390 |
| P-43 | 286.46 | J-44 | Ecco Tracer | 12.0 | Ductile Iron | 110.0 | 0.390 |
| P-42 | 167.96 | Ecco Tracer | Ashton Fuel/Hillside | 12.0 | Ductile Iron | 110.0 | 0.390 |
| P-12 | 113.26 | J-12 | J-21 | 8.0 | Ductile Iron | 100.0 | 0.800 |
| P-20 | 343.17 | J-21 | J-20 | 8.0 | Ductile Iron | 110.0 | 0.390 |
| P-19 | 842.47 | J-20 | J-19 | 8.0 | Ductile Iron | 110.0 | 0.390 |
| P-18 | 395.68 | J-19 | J-18 | 8.0 | Ductile Iron | 110.0 | 0.390 |
| P-17 | 544.73 | J-18 | J-17 | 8.0 | Ductile Iron | 110.0 | 0.390 |
| P-16 | 196.86 | J-17 | J-16 | 8.0 | Ductile Iron | 100.0 | 0.390 |
| P-5 | 138.06 | J-5 | J-6 | 8.0 | Ductile Iron | 100.0 | 0.390 |
| P-30 | 62.05 | Court | J-30 | 20.0 | Ductile Iron | 80.0 | 1.280 |
| P-27 | 387.48 | Christian Assembly | La Quinta | 8.0 | Ductile Iron | 80.0 | 0.390 |
| P-26 | 198.54 | La Quinta | Pub 99 Restaurant | 8.0 | Ductile Iron | 100.0 | 0.390 |
| P-29 | 903.03 | J-30 | J-29 | 8.0 | Ductile Iron | 90.0 | 1.280 |
| P-28 | 299.41 | J-29 | La Quinta | 8.0 | Ductile Iron | 100.0 | 0.390 |
| P-34 | 266.62 | J-9 | J-34 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-33 | 32.58 | J-34 | J-33 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-21 | 99.15 | J-21 | J-34 | 8.0 | Ductile Iron | 110.0 | 0.390 |
| P-39 | 400.51 | Office | J-49 | 12.0 | Ductile Iron | 100.0 | 0.800 |
| P-41 | 259.85 | Ashton Fuel/Hillside | Enterprise | 12.0 | Ductile Iron | 90.0 | 0.800 |
| P-40 | 1,255.92 | Enterprise | J-49 | 12.0 | Ductile Iron | 90.0 | 0.800 |
| P-15 | 59.46 | J-16 | J-15 | 8.0 | Ductile Iron | 100.0 | 0.390 |
| P-14A | 129.72 | J-15 | Staples | 6.0 | Ductile Iron | 120.0 | 0.390 |
| P-14 | 103.47 | J-15 | J-14 | 8.0 | Ductile Iron | 100.0 | 0.390 |
| P-13A | 241.80 | J-14 | Christmas Tree Shops | 6.0 | Ductile Iron | 120.0 | 1.280 |
| P-6 | 15.75 | J-6 | J-7 | 8.0 | Ductile Iron | 100.0 | 0.390 |
| P-6A | 194.43 | J-7 | Sports Authority | 8.0 | Ductile Iron | 120.0 | 0.390 |
| P-13 | 210.30 | J-14 | J-5 | 8.0 | Ductile Iron | 100.0 | 0.390 |
| P-4A | 198.17 | J-5 | A C Moore | 6.0 | Ductile Iron | 120.0 | 0.390 |
| P-7 | 144.89 | J-7 | J-8 | 8.0 | Ductile Iron | 100.0 | 0.390 |
| P-8 | 162.77 | J-8 | J-9 | 8.0 | Ductile Iron | 100.0 | 0.390 |
| P-9 | 43.65 | J-9 | J-10 | 8.0 | Ductile Iron | 100.0 | 0.390 |
| P-10 | 265.23 | J-10 | J-11 | 8.0 | Ductile Iron | 100.0 | 0.390 |
| P-11 | 37.85 | J-11 | J-12 | 8.0 | Ductile Iron | 100.0 | 0.390 |
| P-9A | 180.47 | J-10 | T J Maxx | 8.0 | Ductile Iron | 120.0 | 0.390 |
| P-7A | 181.77 | J-8 | Bed Bath & Beyond | 8.0 | Ductile Iron | 120.0 | 0.390 |
| P-4 | 72.49 | J-5 | Spaulding Brick | 12.0 | Ductile Iron | 100.0 | 0.390 |
| P-RV | 26.87 | R-1 | PMP-1 | 30.0 | Ductile Iron | 130.0 | 0.000 |
| P-1 | 49.52 | PMP-1 | J-65 | 30.0 | Ductile Iron | 130.0 | 0.000 |
| P-57 | 179.00 | J-70 | J-57 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-56 | 114.20 | J-57 | J-56 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-47 | 172.73 | Circuit City | J-47 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-51 | 326.19 | J-51 | J-54 | 12.0 | Ductile Iron | 110.0 | 0.390 |
| P-52 | 188.85 | J-54 | Home Depot | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-50 | 1,286.01 | J-46 | J-51 | 10.0 | Ductile Iron | 110.0 | 0.390 |

| | | | | | | | |
|-------|----------|------------------------------|------------------------------|------|--------------|-------|-------|
| P-67 | 370.36 | J-67 | J-68 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-77 | 83.16 | J-75 | J-77 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-76 | 380.49 | J-77 | J-65 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-75 | 188.99 | J-75 | J-75 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-73 | 149.94 | J-75 | WHYC | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-81 | 140.24 | J-68 | J-82 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-78 | 299.65 | J-67 | J-79 | 8.0 | Ductile Iron | 130.0 | 0.390 |
| P-79 | 171.30 | J-79 | J-115 | 8.0 | Ductile Iron | 130.0 | 0.390 |
| P-85 | 84.37 | Dam | J-85 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-84 | 186.51 | J-85 | J-84 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-76B | 76.22 | Block 1 | J-77 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-75B | 111.32 | Block 2 | J-75 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-81B | 72.10 | J-82 | Block 5 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-84B | 104.77 | Block 6B/C | J-85 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-83A | 203.07 | Block 8A | J-84 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-84A | 102.44 | Block 8B | J-85 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-69A | 53.57 | Block 9 | J-70 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-55 | 241.85 | J-56 | Parcel 11A (Fire Connection) | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-54 | 162.57 | Parcel 11A (Fire Connection) | J-54 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-37 | 380.14 | Truck Company | Theater | 20.0 | Ductile Iron | 80.0 | 0.800 |
| P-38 | 279.28 | Theater | Office | 12.0 | Ductile Iron | 100.0 | 0.800 |
| P-60 | 675.92 | J-60 | J-70 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-58 | 83.19 | Circuit City | J-59 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-59 | 398.81 | J-59 | J-60 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-53 | 99.53 | Home Depot | Parcel 11A (Domestic) | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-48 | 330.28 | Parcel 11A (Domestic) | Circuit City | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-76A | 169.97 | J-77 | Block 3 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-75A | 93.56 | J-75 | Block 4A | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-83B | 141.24 | Block 6A | J-84 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-61 | 1,024.72 | Court | J-62 | 20.0 | Ductile Iron | 130.0 | 0.800 |
| P-62 | 277.24 | J-62 | J-63 | 20.0 | Ductile Iron | 130.0 | 0.800 |
| P-61A | 89.16 | J-62 | Block 10 | 8.0 | Ductile Iron | 130.0 | 0.390 |
| P-71 | 612.22 | Dam | J-70 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-82 | 323.16 | J-83 | J-82 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-83 | 91.32 | J-84 | J-83 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-2 | 280.48 | Christian Assembly | J-2 | 20.0 | Ductile Iron | 80.0 | 0.390 |
| P-1A | 213.28 | J-2 | Dunkin Donuts/Sunrise | 20.0 | Ductile Iron | 80.0 | 0.390 |
| P-74 | 819.64 | J-63 | J-75 | 8.0 | Ductile Iron | 130.0 | 0.390 |
| P-81A | 97.06 | Block 7A | J-82 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-80 | 349.19 | J-115 | J-83 | 8.0 | Ductile Iron | 130.0 | 0.390 |
| P-56A | 458.24 | J-57 | J-83 | 12.0 | Ductile Iron | 130.0 | 0.390 |
| P-242 | 517.45 | WHYC | J-159 | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-243 | 374.38 | J-159 | Dam | 20.0 | Ductile Iron | 130.0 | 0.390 |
| P-244 | 151.05 | J-159 | J-160 | 12.0 | Ductile Iron | 130.0 | 0.000 |
| P-245 | 281.80 | J-160 | J-161 | 12.0 | Ductile Iron | 130.0 | 0.000 |
| P-247 | 11.17 | J-160 | H-3 | 6.0 | Ductile Iron | 130.0 | 0.000 |
| P-248 | 34.32 | J-161 | J-162 | 8.0 | Ductile Iron | 130.0 | 0.000 |
| P-249 | 12.61 | J-162 | H-2 | 6.0 | Ductile Iron | 130.0 | 0.000 |

\\Vhb\proj\Wat-LD\08518.05\tech\WaterCad\0851805 Water AmPUD MAY-2014.wtg

Scenario: 3,500 ISO
Current Time Step: 0.000 Hr
Junction FlexTable:

| Label | Elevation (ft) | Demand (gpm) | Hydraulic Grade (ft) | Pressure (psi) |
|-----------------------|-------------------|-----------------|----------------------------|-------------------|
| Court | 12.60 | 3.00 | 168.88 | 67.6 |
| J-63 | 13.40 | 0.00 | 168.89 | 67.3 |
| J-64 | 12.00 | 0.00 | 168.90 | 67.9 |
| J-66 | 13.20 | 0.00 | 168.90 | 67.4 |
| J-67 | 13.00 | 0.00 | 168.88 | 67.4 |
| J-68 | 12.50 | 0.00 | 168.87 | 67.7 |
| J-9 | 10.00 | 0.00 | 168.87 | 68.7 |
| J-33 | 8.20 | 0.00 | 168.87 | 69.5 |
| Truck Company | 9.10 | 2.00 | 168.87 | 69.1 |
| Spaulding Brick | 10.70 | 1.00 | 168.87 | 68.4 |
| J-65 | 13.00 | 0.00 | 168.90 | 67.5 |
| J-70 | 12.00 | 0.00 | 168.86 | 67.9 |
| J-56 | 13.50 | 0.00 | 168.86 | 67.2 |
| J-54 | 10.00 | 0.00 | 168.87 | 68.7 |
| J-49 | 12.00 | 0.00 | 168.86 | 67.9 |
| J-51 | 10.70 | 0.00 | 168.86 | 68.4 |
| Dunkin Donuts/Sunrise | 9.20 | 3.00 | 168.87 | 69.1 |
| Christian Assembly | 9.50 | 1.00 | 168.87 | 69.0 |
| Pub 99 Restaurant | 9.20 | 17.00 | 168.87 | 69.1 |
| Warehouse | 8.40 | 1.00 | 168.87 | 69.4 |
| J-2 | 7.80 | 0.00 | 168.87 | 69.7 |
| J-68 | 14.00 | 0.00 | 168.86 | 67.0 |
| J-70 | 13.00 | 0.00 | 168.86 | 67.4 |
| J-54 | 12.00 | 0.00 | 168.86 | 67.9 |
| Home Depot | 11.00 | 9.00 | 168.86 | 68.3 |
| J-47 | 10.50 | 0.00 | 168.86 | 68.5 |
| J-46 | 11.00 | 0.00 | 168.86 | 68.3 |
| J-45 | 11.30 | 0.00 | 168.86 | 68.2 |
| J-44 | 15.50 | 0.00 | 168.86 | 66.4 |
| Ecco Tracer | 26.00 | 3.00 | 168.86 | 61.8 |
| Ashton Fuel/Hillside | 31.50 | 2.00 | 168.86 | 59.4 |
| J-12 | 9.00 | 0.00 | 168.87 | 69.2 |
| J-21 | 9.50 | 0.00 | 168.87 | 69.0 |
| J-20 | 9.10 | 0.00 | 168.87 | 69.1 |
| J-19 | 10.80 | 0.00 | 168.87 | 68.4 |
| J-18 | 11.50 | 0.00 | 168.87 | 68.1 |
| J-17 | 12.00 | 0.00 | 168.87 | 67.9 |
| J-16 | 10.70 | 0.00 | 168.87 | 68.4 |
| J-5 | 10.70 | 0.00 | 168.87 | 68.4 |
| J-6 | 10.10 | 0.00 | 168.87 | 68.7 |
| J-10 | 8.00 | 0.00 | 168.87 | 69.6 |
| J-30 | 12.20 | 0.00 | 168.88 | 67.8 |
| La Quinta | 10.50 | 23.00 | 168.87 | 68.5 |
| J-29 | 11.50 | 0.00 | 168.87 | 68.1 |
| J-34 | 8.50 | 0.00 | 168.87 | 69.4 |
| Office | 9.80 | 10.00 | 168.86 | 68.8 |
| Enterprise | 31.50 | 1.00 | 168.86 | 59.4 |
| J-15 | 10.10 | 0.00 | 168.87 | 68.7 |
| Staples | 11.40 | 3.00 | 168.87 | 68.1 |
| J-14 | 8.40 | 0.00 | 168.87 | 69.4 |
| Christmas Tree Shops | 11.40 | 4.00 | 168.87 | 68.1 |
| J-7 | 10.30 | 0.00 | 168.87 | 68.6 |
| Sports Authority | 10.80 | 3.00 | 168.87 | 68.4 |
| A C Moore | 11.40 | 3.00 | 168.87 | 68.1 |
| J-8 | 7.50 | 0.00 | 168.87 | 69.8 |

| | | | | |
|------------------------------|-------|--------|--------|------|
| J-9 | 8.00 | 0.00 | 168.87 | 69.6 |
| J-11 | 9.50 | 0.00 | 168.87 | 69.0 |
| T J Maxx | 10.60 | 4.00 | 168.87 | 68.5 |
| Bed Bath & Beyond | 11.10 | 3.00 | 168.87 | 68.3 |
| J-57 | 13.00 | 0.00 | 168.86 | 67.4 |
| Circuit City | 9.00 | 2.00 | 168.86 | 69.2 |
| J-83 | 12.50 | 0.00 | 168.86 | 67.7 |
| J-115 | 12.20 | 0.00 | 168.87 | 67.8 |
| J-75 | 11.90 | 0.00 | 168.87 | 67.9 |
| WHYC | 12.60 | 1.00 | 168.87 | 67.6 |
| Dam | 12.50 | 1.00 | 168.86 | 67.7 |
| J-77 | 12.00 | 0.00 | 168.88 | 67.9 |
| J-75 | 12.50 | 0.00 | 168.87 | 67.7 |
| J-82 | 12.50 | 0.00 | 168.86 | 67.7 |
| J-79 | 12.00 | 0.00 | 168.88 | 67.9 |
| J-84 | 12.50 | 0.00 | 168.86 | 67.7 |
| J-85 | 12.50 | 0.00 | 168.86 | 67.7 |
| Block 1 | 13.00 | 83.00 | 168.87 | 67.4 |
| Block 2 | 13.00 | 40.00 | 168.87 | 67.4 |
| Block 3 | 13.00 | 160.00 | 168.86 | 67.4 |
| Block 4A | 13.00 | 70.00 | 168.87 | 67.4 |
| Block 5 | 13.00 | 104.00 | 168.86 | 67.4 |
| Block 6A | 13.00 | 24.00 | 168.86 | 67.4 |
| Block 6B/C | 13.00 | 101.00 | 168.86 | 67.4 |
| Block 7A | 13.50 | 136.00 | 168.86 | 67.2 |
| Block 8A | 13.00 | 43.00 | 168.86 | 67.4 |
| Block 8B | 13.00 | 81.00 | 168.86 | 67.4 |
| Block 9 | 14.20 | 45.00 | 168.86 | 66.9 |
| Parcel 11A (Fire Connection) | 13.00 | 0.00 | 168.86 | 67.4 |
| Theater | 9.31 | 15.00 | 168.87 | 69.0 |
| J-60 | 11.00 | 0.00 | 168.86 | 68.3 |
| J-59 | 10.30 | 0.00 | 168.86 | 68.6 |
| Parcel 11A (Domestic) | 11.00 | 120.00 | 168.86 | 68.3 |
| J-62 | 12.50 | 0.00 | 168.89 | 67.7 |
| Block 10 | 12.00 | 11.00 | 168.89 | 67.9 |
| J-159 | 0.00 | 0.00 | 168.87 | 73.1 |
| J-160 | 0.00 | 0.00 | 168.87 | 73.1 |
| J-161 | 0.00 | 0.00 | 168.87 | 73.1 |
| J-162 | 0.00 | 0.00 | 168.87 | 73.1 |

\\Vhb\proj\Wat-LD\08518.05\tech\WaterCad\0851805 Water AmPUD MAY-2014.wtg

Appendix B


MWRA Meter 91 Readings

Somerville - Total Daily Flow

8/8/2006

Low Service

| Month | 2004 Flow (MGD) | 2005 Flow (MGD) | 2006 Flow (MGD) |
|---------|--------------------|--------------------|--------------------|
| Jan | 4.280 | 3.796 | 3.727 |
| Feb | 4.321 | 3.897 | 3.739 |
| Mar | 3.879 | 3.878 | 3.789 |
| Apr | 3.750 | 3.895 | 3.814 |
| May | 3.877 | 3.889 | 3.880 |
| Jun | 4.196 | 4.187 | 3.564 |
| Jul | 4.240 | 4.181 | 2.864 |
| Aug | 4.234 | 4.093 | |
| Sep | 3.852 | 4.034 | |
| Oct | 3.826 | 3.813 | |
| Nov | 3.642 | 3.736 | |
| Dec | 3.632 | 3.787 | |
| Average | 3.978 | 3.929 | |



Meter 91 Flows:

MWRA Meter 91 daily Flows

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|-----------------|----------------|---------------------|
| 12/9/2003 0:00 | 1.053 | |
| 12/10/2003 0:00 | 1.042 | |
| 12/11/2003 0:00 | 1.081 | |
| 12/12/2003 0:00 | 1.079 | |
| 12/13/2003 0:00 | 1.103 | |
| 12/14/2003 0:00 | 1.121 | |
| 12/15/2003 0:00 | 1.212 | |
| 12/16/2003 0:00 | 1.046 | |
| 12/17/2003 0:00 | 1.019 | |
| 12/18/2003 0:00 | 1.026 | |
| 12/19/2003 0:00 | 0.998 | |
| 12/20/2003 0:00 | 0.96 | |
| 12/21/2003 0:00 | 0.95 | |
| 12/22/2003 0:00 | 1.021 | |
| 12/23/2003 0:00 | 0.912 | |
| 12/24/2003 0:00 | 0.874 | |
| 12/25/2003 0:00 | 0.822 | |
| 12/26/2003 0:00 | 0.953 | |
| 12/27/2003 0:00 | 0.976 | |
| 12/28/2003 0:00 | 0.976 | |
| 12/29/2003 0:00 | 1.046 | |
| 12/30/2003 0:00 | 1.077 | |
| 12/31/2003 0:00 | 1.071 | |
| 1/1/2004 0:00 | 0.959 | |
| 1/2/2004 0:00 | 0.943 | |
| 1/3/2004 0:00 | 0.928 | |
| 1/4/2004 0:00 | 0.949 | |
| 1/5/2004 0:00 | 0.941 | |
| 1/6/2004 0:00 | 1.027 | |
| 1/7/2004 0:00 | 1.094 | 186.27 |
| 1/8/2004 0:00 | 1.132 | 186.61 |
| 1/9/2004 0:00 | 1.127 | 187.009 |
| 1/10/2004 0:00 | 1.159 | 186.525 |
| 1/11/2004 0:00 | 1.199 | 187.002 |
| 1/12/2004 0:00 | 1.238 | 187.934 |
| 1/13/2004 0:00 | 1.103 | 184.955 |
| 1/14/2004 0:00 | 1.079 | 183.661 |
| 1/15/2004 0:00 | 1.093 | 184.041 |
| 1/16/2004 0:00 | 1.128 | 183.913 |
| 1/17/2004 0:00 | 1.163 | 183.674 |
| 1/18/2004 0:00 | 1.083 | 183.203 |
| 1/19/2004 0:00 | 1.131 | 183.886 |
| 1/20/2004 0:00 | 1.11 | 184.27 |
| 1/21/2004 0:00 | 1.094 | 184.339 |
| 1/22/2004 0:00 | 1.08 | 183.91 |
| 1/23/2004 0:00 | 1.096 | 184.261 |
| 1/24/2004 0:00 | 1.134 | 183.889 |
| 1/25/2004 0:00 | 1.127 | 183.916 |
| 1/26/2004 0:00 | 1.162 | 184.783 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 1/27/2004 0:00 | 1.188 | 184.651 |
| 1/28/2004 0:00 | 1.176 | 184.672 |
| 1/29/2004 0:00 | 1.29 | 184.858 |
| 1/30/2004 0:00 | 1.147 | 184.736 |
| 1/31/2004 0:00 | 1.169 | 184.103 |
| 2/1/2004 0:00 | 1.172 | 184.044 |
| 2/2/2004 0:00 | 1.156 | 184.602 |
| 2/3/2004 0:00 | 1.15 | 184.545 |
| 2/4/2004 0:00 | 1.188 | 184.682 |
| 2/5/2004 0:00 | 1.168 | 184.376 |
| 2/6/2004 0:00 | 1.105 | 184.078 |
| 2/7/2004 0:00 | 1.127 | 183.566 |
| 2/8/2004 0:00 | 1.119 | 183.341 |
| 2/9/2004 0:00 | 1.111 | 183.88 |
| 2/10/2004 0:00 | 1.12 | 183.813 |
| 2/11/2004 0:00 | 1.096 | 183.707 |
| 2/12/2004 0:00 | 1.147 | 184.23 |
| 2/13/2004 0:00 | 1.151 | 184.278 |
| 2/14/2004 0:00 | 1.179 | 183.346 |
| 2/15/2004 0:00 | 1.152 | 183.133 |
| 2/16/2004 0:00 | 1.179 | 183.671 |
| 2/17/2004 0:00 | 1.224 | 184.984 |
| 2/18/2004 0:00 | 1.293 | 185.555 |
| 2/19/2004 0:00 | 1.26 | 184.254 |
| 2/20/2004 0:00 | 1.135 | 183.789 |
| 2/21/2004 0:00 | 1.104 | 182.821 |
| 2/22/2004 0:00 | 1.126 | 182.732 |
| 2/23/2004 0:00 | 1.107 | 183.268 |
| 2/24/2004 0:00 | 1.085 | 182.854 |
| 2/25/2004 0:00 | 1.079 | 183.323 |
| 2/26/2004 0:00 | 1.052 | 182.972 |
| 2/27/2004 0:00 | 1.051 | 183.495 |
| 2/28/2004 0:00 | 1.087 | 183.115 |
| 2/29/2004 0:00 | 1.057 | 183.172 |
| 3/1/2004 0:00 | 1.05 | 183.546 |
| 3/2/2004 0:00 | 1.024 | 183.23 |
| 3/3/2004 0:00 | 0.998 | 183.318 |
| 3/4/2004 0:00 | 0.913 | 183.468 |
| 3/5/2004 0:00 | 0.896 | 183.562 |
| 3/6/2004 0:00 | 0.928 | 183.358 |
| 3/7/2004 0:00 | 0.937 | 183.492 |
| 3/8/2004 0:00 | 0.898 | 183.907 |
| 3/9/2004 0:00 | 0.894 | 183.808 |
| 3/10/2004 0:00 | 0.917 | 184.006 |
| 3/11/2004 0:00 | 0.911 | 178.064 |
| 3/12/2004 0:00 | 0.887 | 184.164 |
| 3/13/2004 0:00 | 1.14 | 183.785 |
| 3/14/2004 0:00 | 0.949 | 183.044 |
| 3/15/2004 0:00 | 0.92 | 183.777 |
| 3/16/2004 0:00 | 0.883 | 184.157 |
| 3/17/2004 0:00 | 0.901 | 184.455 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 3/18/2004 0:00 | 0.896 | 184.393 |
| 3/19/2004 0:00 | 0.907 | 184.771 |
| 3/20/2004 0:00 | 0.952 | 184.715 |
| 3/21/2004 0:00 | 0.941 | 184.932 |
| 3/22/2004 0:00 | 0.898 | 185.155 |
| 3/23/2004 0:00 | 0.904 | 185.471 |
| 3/24/2004 0:00 | 0.911 | 185.2 |
| 3/25/2004 0:00 | 0.904 | 185.309 |
| 3/26/2004 0:00 | 0.908 | 185.167 |
| 3/27/2004 0:00 | 0.945 | 185.037 |
| 3/28/2004 0:00 | 0.947 | 184.92 |
| 3/29/2004 0:00 | 0.919 | 185.067 |
| 3/30/2004 0:00 | 0.901 | 185.161 |
| 3/31/2004 0:00 | 0.896 | 184.609 |
| 4/1/2004 0:00 | 1.07 | 184.851 |
| 4/2/2004 0:00 | 1.098 | 184.303 |
| 4/3/2004 0:00 | 1.034 | 184.423 |
| 4/4/2004 0:00 | 0.986 | 183.897 |
| 4/5/2004 0:00 | 0.908 | 183.592 |
| 4/6/2004 0:00 | 0.919 | 184.742 |
| 4/7/2004 0:00 | 0.914 | 184.556 |
| 4/8/2004 0:00 | 0.901 | 184.444 |
| 4/9/2004 0:00 | 0.924 | 184.554 |
| 4/10/2004 0:00 | 0.953 | 184.119 |
| 4/11/2004 0:00 | 0.905 | 183.978 |
| 4/12/2004 0:00 | 0.905 | 183.985 |
| 4/13/2004 0:00 | 0.95 | 184.309 |
| 4/14/2004 0:00 | 0.914 | 183.866 |
| 4/15/2004 0:00 | 0.896 | 183.84 |
| 4/16/2004 0:00 | 0.9 | 183.918 |
| 4/17/2004 0:00 | 0.944 | 183.671 |
| 4/18/2004 0:00 | 0.922 | 183.498 |
| 4/19/2004 0:00 | 0.945 | 183.555 |
| 4/20/2004 0:00 | 0.942 | 183.431 |
| 4/21/2004 0:00 | 0.917 | 183.004 |
| 4/22/2004 0:00 | 0.944 | 182.497 |
| 4/23/2004 0:00 | 0.878 | 182.829 |
| 4/24/2004 0:00 | 0.931 | 182.881 |
| 4/25/2004 0:00 | 0.928 | 183.059 |
| 4/26/2004 0:00 | 0.888 | 182.84 |
| 4/27/2004 0:00 | 0.903 | 182.996 |
| 4/28/2004 0:00 | 0.911 | 182.905 |
| 4/29/2004 0:00 | 0.931 | 182.59 |
| 4/30/2004 0:00 | 0.959 | 182.481 |
| 5/1/2004 0:00 | 0.969 | 181.757 |
| 5/2/2004 0:00 | 0.958 | 181.638 |
| 5/3/2004 0:00 | 0.925 | 181.967 |
| 5/4/2004 0:00 | 0.916 | 181.415 |
| 5/5/2004 0:00 | 0.931 | 181.994 |
| 5/6/2004 0:00 | 0.913 | 182.41 |
| 5/7/2004 0:00 | 0.936 | 181.368 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 5/8/2004 0:00 | 0.931 | 182.06 |
| 5/9/2004 0:00 | 0.905 | 182.338 |
| 5/10/2004 0:00 | 0.919 | 182.568 |
| 5/11/2004 0:00 | 0.982 | 181.67 |
| 5/12/2004 0:00 | 0.971 | 181.285 |
| 5/13/2004 0:00 | 0.964 | 180.856 |
| 5/14/2004 0:00 | 0.954 | 181.781 |
| 5/15/2004 0:00 | 1.384 | 181.6 |
| 5/16/2004 0:00 | 0.994 | 180.943 |
| 5/17/2004 0:00 | 0.994 | 181.465 |
| 5/18/2004 0:00 | 1.006 | 181.987 |
| 5/19/2004 0:00 | 0.992 | 181.153 |
| 5/20/2004 0:00 | 1.016 | 181.083 |
| 5/21/2004 0:00 | 1.025 | 181.117 |
| 5/22/2004 0:00 | 1.016 | 180.858 |
| 5/23/2004 0:00 | 1.029 | 181.418 |
| 5/24/2004 0:00 | 0.97 | 181.776 |
| 5/25/2004 0:00 | 0.966 | 182.062 |
| 5/26/2004 0:00 | 0.968 | 182.125 |
| 5/27/2004 0:00 | 0.983 | 182.003 |
| 5/28/2004 0:00 | 0.962 | 182.169 |
| 5/29/2004 0:00 | 0.982 | 182.22 |
| 5/30/2004 0:00 | 0.953 | 182.047 |
| 5/31/2004 0:00 | 1.05 | 181.508 |
| 6/1/2004 0:00 | 0.976 | 181.894 |
| 6/2/2004 0:00 | 1.046 | 180.872 |
| 6/3/2004 0:00 | 1.037 | 180.715 |
| 6/4/2004 0:00 | 1.025 | 180.56 |
| 6/5/2004 0:00 | 0.988 | 180.576 |
| 6/6/2004 0:00 | 0.972 | 180.926 |
| 6/7/2004 0:00 | 0.989 | 180.982 |
| 6/8/2004 0:00 | 1.125 | 180.521 |
| 6/9/2004 0:00 | 1.148 | 180.085 |
| 6/10/2004 0:00 | 1.025 | 180.566 |
| 6/11/2004 0:00 | 1.073 | 180.752 |
| 6/12/2004 0:00 | 1.095 | 180.918 |
| 6/13/2004 0:00 | 1.106 | 180.879 |
| 6/14/2004 0:00 | 1.116 | 180.995 |
| 6/15/2004 0:00 | 1.202 | 180.671 |
| 6/16/2004 0:00 | 1.185 | 180.985 |
| 6/17/2004 0:00 | 1.151 | 181.841 |
| 6/18/2004 0:00 | 1.077 | 180.721 |
| 6/19/2004 0:00 | 1.083 | 181.318 |
| 6/20/2004 0:00 | 1.037 | 181.308 |
| 6/21/2004 0:00 | 1.09 | 181.206 |
| 6/22/2004 0:00 | 1.131 | 183.46 |
| 6/23/2004 0:00 | 1.147 | 182.82 |
| 6/24/2004 0:00 | 1.168 | 183.442 |
| 6/25/2004 0:00 | 1.127 | 182.216 |
| 6/26/2004 0:00 | 1.025 | 181.045 |
| 6/27/2004 0:00 | 1.027 | 180.998 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 6/28/2004 0:00 | 1.18 | 181.958 |
| 6/29/2004 0:00 | 1.202 | 182.761 |
| 6/30/2004 0:00 | 1.269 | 183.446 |
| 7/1/2004 0:00 | 1.257 | 183.088 |
| 7/2/2004 0:00 | 1.162 | 179.79 |
| 7/3/2004 0:00 | 1.085 | 178.764 |
| 7/4/2004 0:00 | 1.047 | 179.172 |
| 7/5/2004 0:00 | 1.068 | 179.666 |
| 7/6/2004 0:00 | 1.176 | 181.74 |
| 7/7/2004 0:00 | 1.222 | 180.83 |
| 7/8/2004 0:00 | 1.221 | 182.651 |
| 7/9/2004 0:00 | 1.236 | 183.054 |
| 7/10/2004 0:00 | 1.181 | 181.521 |
| 7/11/2004 0:00 | 1.157 | 182.012 |
| 7/12/2004 0:00 | 1.269 | 183.443 |
| 7/13/2004 0:00 | 1.179 | 182.362 |
| 7/14/2004 0:00 | 1.171 | 183.765 |
| 7/15/2004 0:00 | 1.218 | 184.137 |
| 7/16/2004 0:00 | 1.257 | 183.798 |
| 7/17/2004 0:00 | 1.244 | 184.4 |
| 7/18/2004 0:00 | 1.201 | 183.184 |
| 7/19/2004 0:00 | 1.2 | 183.704 |
| 7/20/2004 0:00 | 1.281 | 184.344 |
| 7/21/2004 0:00 | 1.316 | 184.086 |
| 7/22/2004 0:00 | 1.352 | 184.327 |
| 7/23/2004 0:00 | 1.328 | 184.797 |
| 7/24/2004 0:00 | 1.17 | 182.528 |
| 7/25/2004 0:00 | 1.151 | 181.981 |
| 7/26/2004 0:00 | 1.212 | 182.973 |
| 7/27/2004 0:00 | 1.149 | 182.429 |
| 7/28/2004 0:00 | 1.112 | 182.124 |
| 7/29/2004 0:00 | 1.191 | 183.06 |
| 7/30/2004 0:00 | 1.242 | 183.112 |
| 7/31/2004 0:00 | 1.195 | 182.185 |
| 8/1/2004 0:00 | 1.146 | 181.463 |
| 8/2/2004 0:00 | 1.266 | 182.715 |
| 8/3/2004 0:00 | 1.298 | 183.515 |
| 8/4/2004 0:00 | 1.26 | 182.979 |
| 8/5/2004 0:00 | 1.193 | 183.007 |
| 8/6/2004 0:00 | 1.17 | 182.869 |
| 8/7/2004 0:00 | 1.211 | 182.123 |
| 8/8/2004 0:00 | 1.117 | 181.966 |
| 8/9/2004 0:00 | 1.237 | 183.096 |
| 8/10/2004 0:00 | 1.261 | 185.377 |
| 8/11/2004 0:00 | 1.249 | 185.825 |
| 8/12/2004 0:00 | 1.264 | 185.782 |
| 8/13/2004 0:00 | 1.074 | 178.869 |
| 8/14/2004 0:00 | 0.992 | 175.663 |
| 8/15/2004 0:00 | 0.969 | 176.109 |
| 8/16/2004 0:00 | 0.983 | 174.155 |
| 8/17/2004 0:00 | 0.984 | 176.065 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 8/18/2004 0:00 | 1.005 | 176.332 |
| 8/19/2004 0:00 | 1.06 | 176.159 |
| 8/20/2004 0:00 | 1.059 | 176.332 |
| 8/21/2004 0:00 | 0.99 | 176.454 |
| 8/22/2004 0:00 | 0.972 | 176.978 |
| 8/23/2004 0:00 | 0.992 | 176.799 |
| 8/24/2004 0:00 | 0.99 | 177.245 |
| 8/25/2004 0:00 | 0.992 | 177.728 |
| 8/26/2004 0:00 | 1.024 | 177.547 |
| 8/27/2004 0:00 | 1.029 | 177.271 |
| 8/28/2004 0:00 | 1.03 | 176.625 |
| 8/29/2004 0:00 | 1.036 | 176.519 |
| 8/30/2004 0:00 | 1.081 | 177.385 |
| 8/31/2004 0:00 | 1.017 | 177.284 |
| 9/1/2004 0:00 | 1.283 | 177.398 |
| 9/2/2004 0:00 | 1.089 | 177.502 |
| 9/3/2004 0:00 | 1.056 | 177.377 |
| 9/4/2004 0:00 | 1.033 | 177.49 |
| 9/5/2004 0:00 | 0.978 | 177.856 |
| 9/6/2004 0:00 | 1.041 | 177.858 |
| 9/7/2004 0:00 | 0.991 | 178.084 |
| 9/8/2004 0:00 | 0.991 | 177.752 |
| 9/9/2004 0:00 | 0.991 | 178.02 |
| 9/10/2004 0:00 | 0.991 | 178.09 |
| 9/11/2004 0:00 | 0.991 | 178.283 |
| 9/12/2004 0:00 | 0.991 | 178.35 |
| 9/13/2004 0:00 | 0.991 | 178.677 |
| 9/14/2004 0:00 | 0.991 | 178.976 |
| 9/15/2004 0:00 | 0.991 | 178.792 |
| 9/16/2004 0:00 | 0.991 | 166.019 |
| 9/17/2004 0:00 | 1.18 | 179.504 |
| 9/18/2004 0:00 | 1.148 | 178.918 |
| 9/19/2004 0:00 | 1.107 | 178.561 |
| 9/20/2004 0:00 | 1.087 | 179.848 |
| 9/21/2004 0:00 | 1.065 | 179.491 |
| 9/22/2004 0:00 | 1.111 | 179.482 |
| 9/23/2004 0:00 | 1.09 | 178.981 |
| 9/24/2004 0:00 | 1.076 | 179.343 |
| 9/25/2004 0:00 | 1.062 | 178.417 |
| 9/26/2004 0:00 | 1.044 | 177.903 |
| 9/27/2004 0:00 | 1.071 | 178.944 |
| 9/28/2004 0:00 | 1.073 | 179.298 |
| 9/29/2004 0:00 | 1.006 | 178.267 |
| 9/30/2004 0:00 | 1 | 179.083 |
| 10/1/2004 0:00 | 1.042 | 179.808 |
| 10/2/2004 0:00 | 1.004 | 178.111 |
| 10/3/2004 0:00 | 1.014 | 178.165 |
| 10/4/2004 0:00 | 1.04 | 179.028 |
| 10/5/2004 0:00 | 1.079 | 179.589 |
| 10/6/2004 0:00 | 1.058 | 179.419 |
| 10/7/2004 0:00 | 1.128 | 180.397 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|-----------------|----------------|---------------------|
| 10/8/2004 0:00 | 1.077 | 179.566 |
| 10/9/2004 0:00 | 1.067 | 179.171 |
| 10/10/2004 0:00 | 1.017 | 178.905 |
| 10/11/2004 0:00 | 1.08 | 178.803 |
| 10/12/2004 0:00 | 0.584 | 180.482 |
| 10/13/2004 0:00 | 0 | |
| 10/14/2004 0:00 | 0 | 179.427 |
| 10/15/2004 0:00 | 0 | 180.108 |
| 10/16/2004 0:00 | 0 | 179.818 |
| 10/17/2004 0:00 | 0 | 180.116 |
| 10/18/2004 0:00 | 0 | 180.443 |
| 10/19/2004 0:00 | 0 | 180.634 |
| 10/20/2004 0:00 | 0 | 180.856 |
| 10/21/2004 0:00 | 0 | 180.836 |
| 10/22/2004 0:00 | 0 | 181.1 |
| 10/23/2004 0:00 | 0 | 180.885 |
| 10/24/2004 0:00 | 0 | 180.967 |
| 10/25/2004 0:00 | 0 | 180.918 |
| 10/26/2004 0:00 | 0 | 181.25 |
| 10/27/2004 0:00 | 0 | 181.761 |
| 10/28/2004 0:00 | 0 | 181.049 |
| 10/29/2004 0:00 | 0 | 181.437 |
| 10/30/2004 0:00 | 0 | 180.827 |
| 10/31/2004 0:00 | 0 | 181.313 |
| 11/1/2004 0:00 | 0 | 181.22 |
| 11/2/2004 0:00 | 0 | 181.52 |
| 11/3/2004 0:00 | 0 | 181.647 |
| 11/4/2004 0:00 | 0 | 181.696 |
| 11/5/2004 0:00 | 0 | 182.076 |
| 11/6/2004 0:00 | 0 | 181.405 |
| 11/7/2004 0:00 | 0 | 181.162 |
| 11/8/2004 0:00 | 0 | 182.304 |
| 11/9/2004 0:00 | 0 | 182.229 |
| 11/10/2004 0:00 | 0 | 182.317 |
| 11/11/2004 0:00 | 0 | 182.328 |
| 11/12/2004 0:00 | 0 | 182.349 |
| 11/13/2004 0:00 | 0 | 181.755 |
| 11/14/2004 0:00 | 0 | 181.686 |
| 11/15/2004 0:00 | 0 | 182.213 |
| 11/16/2004 0:00 | 0 | 181.919 |
| 11/17/2004 0:00 | 0 | 182.318 |
| 11/18/2004 0:00 | 0 | 182.77 |
| 11/19/2004 0:00 | 0 | 182.737 |
| 11/20/2004 0:00 | 0 | 182.039 |
| 11/21/2004 0:00 | 0 | 182.158 |
| 11/22/2004 0:00 | 0 | 182.998 |
| 11/23/2004 0:00 | 0 | 182.492 |
| 11/24/2004 0:00 | 0 | 182.355 |
| 11/25/2004 0:00 | 0 | 181.467 |
| 11/26/2004 0:00 | 0 | 181.736 |
| 11/27/2004 0:00 | 0 | 181.499 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|-----------------|----------------|---------------------|
| 11/28/2004 0:00 | 0 | 181.882 |
| 11/29/2004 0:00 | 0 | 166.426 |
| 11/30/2004 0:00 | 0 | |
| 12/1/2004 0:00 | 0 | |
| 12/2/2004 0:00 | 0 | |
| 12/3/2004 0:00 | 0 | |
| 12/4/2004 0:00 | 0 | |
| 12/5/2004 0:00 | 0 | |
| 12/6/2004 0:00 | 0 | |
| 12/7/2004 0:00 | 0 | |
| 12/8/2004 0:00 | 0 | |
| 12/9/2004 0:00 | 0 | |
| 12/10/2004 0:00 | 0 | |
| 12/11/2004 0:00 | 0 | |
| 12/12/2004 0:00 | 0 | |
| 12/13/2004 0:00 | 0 | |
| 12/14/2004 0:00 | 0 | |
| 12/15/2004 0:00 | 0 | |
| 12/16/2004 0:00 | 0 | |
| 12/17/2004 0:00 | 0 | |
| 12/18/2004 0:00 | 0 | |
| 12/19/2004 0:00 | 0 | |
| 12/20/2004 0:00 | 0 | |
| 12/21/2004 0:00 | 0 | |
| 12/22/2004 0:00 | 0 | |
| 12/23/2004 0:00 | 0 | |
| 12/24/2004 0:00 | 0 | |
| 12/25/2004 0:00 | 0 | |
| 12/26/2004 0:00 | 0 | |
| 12/27/2004 0:00 | 0 | |
| 12/28/2004 0:00 | 0 | |
| 12/29/2004 0:00 | 0 | |
| 12/30/2004 0:00 | 0 | |
| 12/31/2004 0:00 | 0 | |
| 1/1/2005 0:00 | 0 | |
| 1/2/2005 0:00 | 0 | |
| 1/3/2005 0:00 | 0 | |
| 1/4/2005 0:00 | 0 | |
| 1/5/2005 0:00 | 0 | |
| 1/6/2005 0:00 | 0 | |
| 1/7/2005 0:00 | 0 | |
| 1/8/2005 0:00 | 0 | |
| 1/9/2005 0:00 | 0 | |
| 1/10/2005 0:00 | 0 | |
| 1/11/2005 0:00 | 0 | |
| 1/12/2005 0:00 | 0 | |
| 1/13/2005 0:00 | 0 | |
| 1/14/2005 0:00 | 0 | |
| 1/15/2005 0:00 | 0 | |
| 1/16/2005 0:00 | 0 | |
| 1/17/2005 0:00 | 0 | |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 1/18/2005 0:00 | 0 | |
| 1/19/2005 0:00 | 0 | |
| 1/20/2005 0:00 | 0 | |
| 1/21/2005 0:00 | 0 | |
| 1/22/2005 0:00 | 0 | |
| 1/23/2005 0:00 | 0 | |
| 1/24/2005 0:00 | 0 | |
| 1/25/2005 0:00 | 0 | |
| 1/26/2005 0:00 | 0 | |
| 1/27/2005 0:00 | 0 | |
| 1/28/2005 0:00 | 0 | |
| 1/29/2005 0:00 | 0 | |
| 1/30/2005 0:00 | 0 | |
| 1/31/2005 0:00 | 0 | |
| 2/1/2005 0:00 | 0 | |
| 2/2/2005 0:00 | 0 | |
| 2/3/2005 0:00 | 0 | |
| 2/4/2005 0:00 | 0 | |
| 2/5/2005 0:00 | 0 | |
| 2/6/2005 0:00 | 0 | |
| 2/7/2005 0:00 | 0 | |
| 2/8/2005 0:00 | 0 | |
| 2/9/2005 0:00 | 0 | |
| 2/10/2005 0:00 | 0 | |
| 2/11/2005 0:00 | 0 | |
| 2/12/2005 0:00 | 0 | |
| 2/13/2005 0:00 | 0 | |
| 2/14/2005 0:00 | 0 | |
| 2/15/2005 0:00 | 0 | |
| 2/16/2005 0:00 | 0 | |
| 2/17/2005 0:00 | 0 | |
| 2/18/2005 0:00 | 0 | |
| 2/19/2005 0:00 | 0 | |
| 2/20/2005 0:00 | 0 | |
| 2/21/2005 0:00 | 0 | |
| 2/22/2005 0:00 | 0 | |
| 2/23/2005 0:00 | 0 | |
| 2/24/2005 0:00 | 0 | |
| 2/25/2005 0:00 | 0 | |
| 2/26/2005 0:00 | 0 | |
| 2/27/2005 0:00 | 0 | |
| 2/28/2005 0:00 | 0 | |
| 3/1/2005 0:00 | 0 | |
| 3/2/2005 0:00 | 0 | |
| 3/3/2005 0:00 | 0 | |
| 3/4/2005 0:00 | 0 | |
| 3/5/2005 0:00 | 0 | |
| 3/6/2005 0:00 | 0 | |
| 3/7/2005 0:00 | 0 | |
| 3/8/2005 0:00 | 0 | |
| 3/9/2005 0:00 | 0 | |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 3/10/2005 0:00 | 0 | |
| 3/11/2005 0:00 | 0 | |
| 3/12/2005 0:00 | 0 | |
| 3/13/2005 0:00 | 0 | |
| 3/14/2005 0:00 | 0 | |
| 3/15/2005 0:00 | 0 | |
| 3/16/2005 0:00 | 0 | |
| 3/17/2005 0:00 | 0 | |
| 3/18/2005 0:00 | 0 | |
| 3/19/2005 0:00 | 0 | |
| 3/20/2005 0:00 | 0 | |
| 3/21/2005 0:00 | 0 | |
| 3/22/2005 0:00 | 0 | |
| 3/23/2005 0:00 | 0 | |
| 3/24/2005 0:00 | 0 | |
| 3/25/2005 0:00 | 0 | |
| 3/26/2005 0:00 | 0 | |
| 3/27/2005 0:00 | 0 | |
| 3/28/2005 0:00 | 0 | |
| 3/29/2005 0:00 | 0 | |
| 3/30/2005 0:00 | 0 | |
| 3/31/2005 0:00 | 0 | |
| 4/1/2005 0:00 | 0 | |
| 4/2/2005 0:00 | 0 | |
| 4/3/2005 0:00 | 0 | |
| 4/4/2005 0:00 | 0 | |
| 4/5/2005 0:00 | 0 | |
| 4/6/2005 0:00 | 0 | |
| 4/7/2005 0:00 | 0 | |
| 4/8/2005 0:00 | 0 | |
| 4/9/2005 0:00 | 0 | |
| 4/10/2005 0:00 | 0 | |
| 4/11/2005 0:00 | 0 | |
| 4/12/2005 0:00 | 0 | |
| 4/13/2005 0:00 | 0 | |
| 4/14/2005 0:00 | 0 | |
| 4/15/2005 0:00 | 0 | |
| 4/16/2005 0:00 | 0 | |
| 4/17/2005 0:00 | 0 | |
| 4/18/2005 0:00 | 0 | |
| 4/19/2005 0:00 | 0 | |
| 4/20/2005 0:00 | 0 | |
| 4/21/2005 0:00 | 0 | |
| 4/22/2005 0:00 | 0 | |
| 4/23/2005 0:00 | 0 | |
| 4/24/2005 0:00 | 0 | |
| 4/25/2005 0:00 | 0 | |
| 4/26/2005 0:00 | 0 | |
| 4/27/2005 0:00 | 0 | |
| 4/28/2005 0:00 | 0 | |
| 4/29/2005 0:00 | 0 | |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 4/30/2005 0:00 | 0 | |
| 5/1/2005 0:00 | 0 | |
| 5/2/2005 0:00 | 0 | |
| 5/3/2005 0:00 | 0 | |
| 5/4/2005 0:00 | 0 | |
| 5/5/2005 0:00 | 0 | |
| 5/6/2005 0:00 | 0 | |
| 5/7/2005 0:00 | 0 | |
| 5/8/2005 0:00 | 0 | |
| 5/9/2005 0:00 | 0 | |
| 5/10/2005 0:00 | 0 | |
| 5/11/2005 0:00 | 0 | |
| 5/12/2005 0:00 | 0 | |
| 5/13/2005 0:00 | 0 | |
| 5/14/2005 0:00 | 0 | |
| 5/15/2005 0:00 | 0 | |
| 5/16/2005 0:00 | 0 | |
| 5/17/2005 0:00 | 0 | |
| 5/18/2005 0:00 | 0 | |
| 5/19/2005 0:00 | 0 | |
| 5/20/2005 0:00 | 0 | |
| 5/21/2005 0:00 | 0 | |
| 5/22/2005 0:00 | 0 | |
| 5/23/2005 0:00 | 0 | |
| 5/24/2005 0:00 | 0 | |
| 5/25/2005 0:00 | 0 | |
| 5/26/2005 0:00 | 0 | |
| 5/27/2005 0:00 | 0 | |
| 5/28/2005 0:00 | 0 | |
| 5/29/2005 0:00 | 0 | |
| 5/30/2005 0:00 | 0 | |
| 5/31/2005 0:00 | 0 | |
| 6/1/2005 0:00 | 0 | |
| 6/2/2005 0:00 | 0 | |
| 6/3/2005 0:00 | 0 | |
| 6/4/2005 0:00 | 0 | |
| 6/5/2005 0:00 | 0 | |
| 6/6/2005 0:00 | 0 | |
| 6/7/2005 0:00 | 0 | |
| 6/8/2005 0:00 | 0 | 178.778 |
| 6/9/2005 0:00 | 0 | 179.743 |
| 6/10/2005 0:00 | 0 | 179.731 |
| 6/11/2005 0:00 | 0 | 179.585 |
| 6/12/2005 0:00 | 0 | 179.552 |
| 6/13/2005 0:00 | 0 | 179.738 |
| 6/14/2005 0:00 | 0 | 179.71 |
| 6/15/2005 0:00 | 0 | 180.619 |
| 6/16/2005 0:00 | 0 | 180.673 |
| 6/17/2005 0:00 | 0 | 180.159 |
| 6/18/2005 0:00 | 0 | 180.443 |
| 6/19/2005 0:00 | 0 | 180.54 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 6/20/2005 0:00 | 0 | 184.007 |
| 6/21/2005 0:00 | 0 | 183.715 |
| 6/22/2005 0:00 | 0 | 183.694 |
| 6/23/2005 0:00 | 0 | 182.204 |
| 6/24/2005 0:00 | 0 | 179.489 |
| 6/25/2005 0:00 | 0 | 179.167 |
| 6/26/2005 0:00 | 0 | 179.359 |
| 6/27/2005 0:00 | 0 | 179.436 |
| 6/28/2005 0:00 | 0 | 179.393 |
| 6/29/2005 0:00 | 0 | 180.196 |
| 6/30/2005 0:00 | 0 | 179.392 |
| 7/1/2005 0:00 | 0 | 179.025 |
| 7/2/2005 0:00 | 0 | 178.21 |
| 7/3/2005 0:00 | 0 | 176.216 |
| 7/4/2005 0:00 | 0 | 176.991 |
| 7/5/2005 0:00 | 0 | 179.828 |
| 7/6/2005 0:00 | 0 | 178.701 |
| 7/7/2005 0:00 | 0 | 177.141 |
| 7/8/2005 0:00 | 0 | 176.871 |
| 7/9/2005 0:00 | 0 | 177.005 |
| 7/10/2005 0:00 | 0 | 177.516 |
| 7/11/2005 0:00 | 0 | 179.832 |
| 7/12/2005 0:00 | 0.437 | 179.18 |
| 7/13/2005 0:00 | 0.951 | 179.172 |
| 7/14/2005 0:00 | 0.95 | 179.186 |
| 7/15/2005 0:00 | 0.964 | 178.716 |
| 7/16/2005 0:00 | 0.959 | 178.191 |
| 7/17/2005 0:00 | 0.919 | 177.526 |
| 7/18/2005 0:00 | 0.906 | 179.276 |
| 7/19/2005 0:00 | 0.934 | 179.747 |
| 7/20/2005 0:00 | 0.903 | 171.863 |
| 7/21/2005 0:00 | 0.952 | 178.842 |
| 7/22/2005 0:00 | 0.967 | 178.547 |
| 7/23/2005 0:00 | 0.927 | 175.731 |
| 7/24/2005 0:00 | 0.912 | 175.446 |
| 7/25/2005 0:00 | 0.928 | 178.679 |
| 7/26/2005 0:00 | 0.947 | 178.626 |
| 7/27/2005 0:00 | 0.94 | 177.945 |
| 7/28/2005 0:00 | 0.928 | 176.61 |
| 7/29/2005 0:00 | 0.934 | 176.213 |
| 7/30/2005 0:00 | 0.947 | 174.174 |
| 7/31/2005 0:00 | 0.903 | 173.532 |
| 8/1/2005 0:00 | 0.91 | 176.486 |
| 8/2/2005 0:00 | 0.889 | 177.711 |
| 8/3/2005 0:00 | 0.905 | 176.298 |
| 8/4/2005 0:00 | 0.908 | 176.413 |
| 8/5/2005 0:00 | 0.923 | 176.74 |
| 8/6/2005 0:00 | 0.921 | 174.201 |
| 8/7/2005 0:00 | 0.919 | 174.525 |
| 8/8/2005 0:00 | 0.952 | 177.352 |
| 8/9/2005 0:00 | 0.922 | 177.524 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 8/10/2005 0:00 | 0.939 | 178.47 |
| 8/11/2005 0:00 | 0.947 | 178.147 |
| 8/12/2005 0:00 | 0.907 | 176.591 |
| 8/13/2005 0:00 | 0.937 | 175.812 |
| 8/14/2005 0:00 | 0.916 | 173.769 |
| 8/15/2005 0:00 | 0.875 | 174.934 |
| 8/16/2005 0:00 | 0.884 | 175.127 |
| 8/17/2005 0:00 | 0.908 | 176.467 |
| 8/18/2005 0:00 | 0.904 | 175.172 |
| 8/19/2005 0:00 | 0.911 | 175.499 |
| 8/20/2005 0:00 | 0.926 | 174.413 |
| 8/21/2005 0:00 | 0.924 | 174.483 |
| 8/22/2005 0:00 | 0.917 | 176.677 |
| 8/23/2005 0:00 | 0.908 | 176.175 |
| 8/24/2005 0:00 | 0.884 | 174.914 |
| 8/25/2005 0:00 | 0.885 | 175.422 |
| 8/26/2005 0:00 | 0.902 | 176.273 |
| 8/27/2005 0:00 | 0.925 | 174.463 |
| 8/28/2005 0:00 | 0.917 | 174.145 |
| 8/29/2005 0:00 | 0.958 | 175.93 |
| 8/30/2005 0:00 | 0.86 | 174.187 |
| 8/31/2005 0:00 | 0.884 | 175.645 |
| 9/1/2005 0:00 | 0.884 | 175.717 |
| 9/2/2005 0:00 | 0.904 | 175.61 |
| 9/3/2005 0:00 | 0.899 | 174.95 |
| 9/4/2005 0:00 | 0.861 | 174.534 |
| 9/5/2005 0:00 | 0.9 | 175.304 |
| 9/6/2005 0:00 | 0.903 | 175.901 |
| 9/7/2005 0:00 | 0.911 | 176.147 |
| 9/8/2005 0:00 | 0.905 | 176.166 |
| 9/9/2005 0:00 | 0.891 | 175.862 |
| 9/10/2005 0:00 | 0.948 | 175.743 |
| 9/11/2005 0:00 | 0.944 | 175.997 |
| 9/12/2005 0:00 | 0.921 | 176.633 |
| 9/13/2005 0:00 | 0.909 | 176.256 |
| 9/14/2005 0:00 | 0.918 | 176.407 |
| 9/15/2005 0:00 | 0.892 | 176.021 |
| 9/16/2005 0:00 | 0.88 | 175.432 |
| 9/17/2005 0:00 | 0.913 | 175.499 |
| 9/18/2005 0:00 | 0.927 | 175.991 |
| 9/19/2005 0:00 | 0.895 | 176.551 |
| 9/20/2005 0:00 | 0.867 | 175.64 |
| 9/21/2005 0:00 | 0.878 | 175.193 |
| 9/22/2005 0:00 | 0.868 | 175.261 |
| 9/23/2005 0:00 | 0.856 | 175.246 |
| 9/24/2005 0:00 | 0.893 | 175.013 |
| 9/25/2005 0:00 | 0.887 | 175.148 |
| 9/26/2005 0:00 | 0.859 | 175.513 |
| 9/27/2005 0:00 | 0.869 | 175.072 |
| 9/28/2005 0:00 | 0.864 | 174.8 |
| 9/29/2005 0:00 | 1.106 | 174.576 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|-----------------|----------------|---------------------|
| 9/30/2005 0:00 | 1.234 | 174.197 |
| 10/1/2005 0:00 | 1.273 | 174.007 |
| 10/2/2005 0:00 | 1.271 | 174.215 |
| 10/3/2005 0:00 | 1.27 | 174.357 |
| 10/4/2005 0:00 | 1.251 | 174.326 |
| 10/5/2005 0:00 | 1.269 | 174.419 |
| 10/6/2005 0:00 | 1.257 | 174.325 |
| 10/7/2005 0:00 | 1.234 | 174.242 |
| 10/8/2005 0:00 | 1.247 | 174.04 |
| 10/9/2005 0:00 | 1.254 | 173.99 |
| 10/10/2005 0:00 | 1.24 | 174.245 |
| 10/11/2005 0:00 | 1.22 | 174.483 |
| 10/12/2005 0:00 | 1.213 | 174.484 |
| 10/13/2005 0:00 | 1.215 | 174.386 |
| 10/14/2005 0:00 | 1.21 | 174.811 |
| 10/15/2005 0:00 | 1.35 | 174.804 |
| 10/16/2005 0:00 | 1.29 | 174.718 |
| 10/17/2005 0:00 | 1.222 | 175.237 |
| 10/18/2005 0:00 | 1.201 | 175.432 |
| 10/19/2005 0:00 | 1.22 | 176.173 |
| 10/20/2005 0:00 | 1.21 | 176.242 |
| 10/21/2005 0:00 | 1.207 | 176.491 |
| 10/22/2005 0:00 | 1.238 | 176.751 |
| 10/23/2005 0:00 | 1.251 | 176.914 |
| 10/24/2005 0:00 | 1.212 | 176.839 |
| 10/25/2005 0:00 | 1.252 | 176.918 |
| 10/26/2005 0:00 | 1.267 | 175.423 |
| 10/27/2005 0:00 | 0.709 | 174.367 |
| 10/28/2005 0:00 | 0.32 | 174.691 |
| 10/29/2005 0:00 | 0.458 | 174.674 |
| 10/30/2005 0:00 | 0.464 | 174.638 |
| 10/31/2005 0:00 | 0.345 | 174.866 |
| 11/1/2005 0:00 | 0.398 | 174.855 |
| 11/2/2005 0:00 | 0.435 | 174.934 |
| 11/3/2005 0:00 | 1.437 | 174.207 |
| 11/4/2005 0:00 | 1.124 | 174.356 |
| 11/5/2005 0:00 | 0.652 | 174.466 |
| 11/6/2005 0:00 | 0.872 | 174.743 |
| 11/7/2005 0:00 | 0.752 | 174.937 |
| 11/8/2005 0:00 | 0.348 | 175.146 |
| 11/9/2005 0:00 | 0.339 | 175.233 |
| 11/10/2005 0:00 | 0.228 | 175.208 |
| 11/11/2005 0:00 | 0.322 | 175.33 |
| 11/12/2005 0:00 | 0.297 | 175.343 |
| 11/13/2005 0:00 | 0.422 | 175.144 |
| 11/14/2005 0:00 | 0.548 | 175.552 |
| 11/15/2005 0:00 | 0.576 | 166.964 |
| 11/16/2005 0:00 | 0.647 | 165.286 |
| 11/17/2005 0:00 | 0.568 | 152.151 |
| 11/18/2005 0:00 | 0.54 | 143.553 |
| 11/19/2005 0:00 | 0.603 | 143.463 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|-----------------|----------------|---------------------|
| 11/20/2005 0:00 | 0.61 | 143.485 |
| 11/21/2005 0:00 | 0.533 | 145.071 |
| 11/22/2005 0:00 | 0.453 | 161.341 |
| 11/23/2005 0:00 | 0.224 | 173.361 |
| 11/24/2005 0:00 | 0.29 | 174.633 |
| 11/25/2005 0:00 | 0.224 | 174.952 |
| 11/26/2005 0:00 | 0.271 | 174.979 |
| 11/27/2005 0:00 | 0.292 | 175.034 |
| 11/28/2005 0:00 | 0.274 | 175.206 |
| 11/29/2005 0:00 | 0.287 | 175.02 |
| 11/30/2005 0:00 | 0.224 | 175.199 |
| 12/1/2005 0:00 | 0.211 | 175.305 |
| 12/2/2005 0:00 | 0.168 | 175.32 |
| 12/3/2005 0:00 | 0.268 | 175.377 |
| 12/4/2005 0:00 | 0.218 | 175.507 |
| 12/5/2005 0:00 | 0.151 | 175.514 |
| 12/6/2005 0:00 | 0.137 | 175.426 |
| 12/7/2005 0:00 | 0.14 | 175.637 |
| 12/8/2005 0:00 | 0.113 | 175.68 |
| 12/9/2005 0:00 | 0.062 | 175.691 |
| 12/10/2005 0:00 | 0.209 | 175.806 |
| 12/11/2005 0:00 | 0.275 | 175.661 |
| 12/12/2005 0:00 | 0.166 | 175.979 |
| 12/13/2005 0:00 | 0.169 | 175.318 |
| 12/14/2005 0:00 | 0.15 | 176.032 |
| 12/15/2005 0:00 | 0.098 | 176.009 |
| 12/16/2005 0:00 | 0.081 | 176.034 |
| 12/17/2005 0:00 | 0.223 | 176.036 |
| 12/18/2005 0:00 | 0.249 | 176.151 |
| 12/19/2005 0:00 | 0.16 | 176.236 |
| 12/20/2005 0:00 | 0.101 | 176.084 |
| 12/21/2005 0:00 | 0.082 | 177.485 |
| 12/22/2005 0:00 | 0.056 | 177.875 |
| 12/23/2005 0:00 | 0.076 | 178.366 |
| 12/24/2005 0:00 | 0.174 | 179.076 |
| 12/25/2005 0:00 | 0.063 | 180.414 |
| 12/26/2005 0:00 | 0.104 | 179.782 |
| 12/27/2005 0:00 | 0.056 | 178.803 |
| 12/28/2005 0:00 | 0.265 | 178.355 |
| 12/29/2005 0:00 | 0.393 | 177.788 |
| 12/30/2005 0:00 | 0.347 | 177.929 |
| 12/31/2005 0:00 | 0.432 | 178.072 |
| 1/1/2006 0:00 | 0.274 | 178.522 |
| 1/2/2006 0:00 | 0.475 | 178.845 |
| 1/3/2006 0:00 | 0.233 | 177.998 |
| 1/4/2006 0:00 | 0.239 | 178.147 |
| 1/5/2006 0:00 | 0.215 | 176.263 |
| 1/6/2006 0:00 | 0.207 | 176.093 |
| 1/7/2006 0:00 | 0.331 | 176.173 |
| 1/8/2006 0:00 | 0.345 | 176.251 |
| 1/9/2006 0:00 | 0.214 | 176.289 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 1/10/2006 0:00 | 0.241 | 176.242 |
| 1/11/2006 0:00 | 0.349 | 176.283 |
| 1/12/2006 0:00 | 0.255 | 176.245 |
| 1/13/2006 0:00 | 0.213 | 176.352 |
| 1/14/2006 0:00 | 0.376 | 176.299 |
| 1/15/2006 0:00 | 0.389 | 176.565 |
| 1/16/2006 0:00 | 0.466 | 176.546 |
| 1/17/2006 0:00 | 0.269 | 176.379 |
| 1/18/2006 0:00 | 0.246 | 176.315 |
| 1/19/2006 0:00 | 0.283 | 176.197 |
| 1/20/2006 0:00 | 0.215 | 176.202 |
| 1/21/2006 0:00 | 0.26 | 178.156 |
| 1/22/2006 0:00 | 0.288 | 178.68 |
| 1/23/2006 0:00 | 0.115 | 178.294 |
| 1/24/2006 0:00 | 0.202 | 176.093 |
| 1/25/2006 0:00 | 0.209 | 176.199 |
| 1/26/2006 0:00 | 0.206 | 176.128 |
| 1/27/2006 0:00 | 0.177 | 176.198 |
| 1/28/2006 0:00 | 0.297 | 176.14 |
| 1/29/2006 0:00 | 0.383 | 176.226 |
| 1/30/2006 0:00 | 0.247 | 176.36 |
| 1/31/2006 0:00 | 0.184 | 176.375 |
| 2/1/2006 0:00 | 0.202 | 176.144 |
| 2/2/2006 0:00 | 0.197 | 176.084 |
| 2/3/2006 0:00 | 0.149 | 176.154 |
| 2/4/2006 0:00 | 0.334 | 176.193 |
| 2/5/2006 0:00 | 0.358 | 176.156 |
| 2/6/2006 0:00 | 0.236 | 176.332 |
| 2/7/2006 0:00 | 0.215 | 176.122 |
| 2/8/2006 0:00 | 0.285 | 176.189 |
| 2/9/2006 0:00 | 0.257 | 176.182 |
| 2/10/2006 0:00 | 0.169 | 176.285 |
| 2/11/2006 0:00 | 0.303 | 176.21 |
| 2/12/2006 0:00 | 0.278 | 176.509 |
| 2/13/2006 0:00 | 0.309 | 176.668 |
| 2/14/2006 0:00 | 0.225 | 176.422 |
| 2/15/2006 0:00 | 0.267 | 176.428 |
| 2/16/2006 0:00 | 0.261 | 176.429 |
| 2/17/2006 0:00 | 0.245 | 176.58 |
| 2/18/2006 0:00 | 0.366 | 176.706 |
| 2/19/2006 0:00 | 0.348 | 176.766 |
| 2/20/2006 0:00 | 0.416 | 176.745 |
| 2/21/2006 0:00 | 0.285 | 176.767 |
| 2/22/2006 0:00 | 0.32 | 176.872 |
| 2/23/2006 0:00 | 0.261 | 176.638 |
| 2/24/2006 0:00 | 0.303 | 176.735 |
| 2/25/2006 0:00 | 0.334 | 176.749 |
| 2/26/2006 0:00 | 0.468 | 176.856 |
| 2/27/2006 0:00 | 0.301 | 176.801 |
| 2/28/2006 0:00 | 0.317 | 176.686 |
| 3/1/2006 0:00 | 0.357 | 176.801 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 3/2/2006 0:00 | 0.322 | 176.773 |
| 3/3/2006 0:00 | 0.338 | 176.865 |
| 3/4/2006 0:00 | 0.502 | 176.821 |
| 3/5/2006 0:00 | 0.502 | 176.649 |
| 3/6/2006 0:00 | 0.4 | 172.988 |
| 3/7/2006 0:00 | 0.44 | 176.71 |
| 3/8/2006 0:00 | 0.361 | 176.524 |
| 3/9/2006 0:00 | 0.391 | 176.46 |
| 3/10/2006 0:00 | 0.364 | 176.189 |
| 3/11/2006 0:00 | 0.499 | 176.233 |
| 3/12/2006 0:00 | 0.491 | 176.367 |
| 3/13/2006 0:00 | 0.446 | 176.323 |
| 3/14/2006 0:00 | 0.373 | 176.208 |
| 3/15/2006 0:00 | 0.381 | 176.365 |
| 3/16/2006 0:00 | 0.396 | 176.351 |
| 3/17/2006 0:00 | 0.347 | 176.203 |
| 3/18/2006 0:00 | 0.441 | 176.241 |
| 3/19/2006 0:00 | 0.609 | 176.313 |
| 3/20/2006 0:00 | 0.356 | 176.357 |
| 3/21/2006 0:00 | 0.325 | 176.18 |
| 3/22/2006 0:00 | 0.348 | 176.396 |
| 3/23/2006 0:00 | 0.371 | 176.341 |
| 3/24/2006 0:00 | 0.335 | 176.304 |
| 3/25/2006 0:00 | 0.489 | 176.441 |
| 3/26/2006 0:00 | 0.496 | 176.541 |
| 3/27/2006 0:00 | 0.438 | 176.401 |
| 3/28/2006 0:00 | 0.451 | 176.262 |
| 3/29/2006 0:00 | 0.386 | 176.098 |
| 3/30/2006 0:00 | 0.404 | 172.936 |
| 3/31/2006 0:00 | 0.527 | 176.511 |
| 4/1/2006 0:00 | 0.51 | 176.321 |
| 4/2/2006 0:00 | 0.595 | 176.199 |
| 4/3/2006 0:00 | 0.432 | 176.219 |
| 4/4/2006 0:00 | 0.41 | 176.159 |
| 4/5/2006 0:00 | 0.387 | 176.138 |
| 4/6/2006 0:00 | 0.504 | 176.178 |
| 4/7/2006 0:00 | 0.441 | 176.176 |
| 4/8/2006 0:00 | 0.65 | 176.207 |
| 4/9/2006 0:00 | 0.66 | 176.194 |
| 4/10/2006 0:00 | 0.408 | 176.202 |
| 4/11/2006 0:00 | 0.186 | 178.228 |
| 4/12/2006 0:00 | 0.02 | 182.513 |
| 4/13/2006 0:00 | 0 | |
| 4/14/2006 0:00 | 0 | |
| 4/15/2006 0:00 | 0 | |
| 4/16/2006 0:00 | 0 | |
| 4/17/2006 0:00 | 0 | |
| 4/18/2006 0:00 | 0 | |
| 4/19/2006 0:00 | 0 | |
| 4/20/2006 0:00 | 0 | |
| 4/21/2006 0:00 | 0 | |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 4/22/2006 0:00 | 0 | |
| 4/23/2006 0:00 | 0 | |
| 4/24/2006 0:00 | 0 | |
| 4/25/2006 0:00 | 0 | |
| 4/26/2006 0:00 | 0 | |
| 4/27/2006 0:00 | 0 | |
| 4/28/2006 0:00 | 0 | |
| 4/29/2006 0:00 | 0 | |
| 4/30/2006 0:00 | 0 | |
| 5/1/2006 0:00 | 0 | |
| 5/2/2006 0:00 | 0 | |
| 5/3/2006 0:00 | 0 | |
| 5/4/2006 0:00 | 0 | |
| 5/5/2006 0:00 | 0 | |
| 5/6/2006 0:00 | 0 | |
| 5/7/2006 0:00 | 0 | |
| 5/8/2006 0:00 | 0 | |
| 5/9/2006 0:00 | 0 | |
| 5/10/2006 0:00 | 0 | |
| 5/11/2006 0:00 | 0 | |
| 5/12/2006 0:00 | 0 | |
| 5/13/2006 0:00 | 0 | |
| 5/14/2006 0:00 | 0 | |
| 5/15/2006 0:00 | 0 | |
| 5/16/2006 0:00 | 0 | |
| 5/17/2006 0:00 | 0 | |
| 5/18/2006 0:00 | 0 | |
| 5/19/2006 0:00 | 0 | |
| 5/20/2006 0:00 | 0 | |
| 5/21/2006 0:00 | 0 | |
| 5/22/2006 0:00 | 0 | |
| 5/23/2006 0:00 | 0 | |
| 5/24/2006 0:00 | 0 | |
| 5/25/2006 0:00 | 0 | |
| 5/26/2006 0:00 | 0 | |
| 5/27/2006 0:00 | 0 | |
| 5/28/2006 0:00 | 0 | |
| 5/29/2006 0:00 | 0 | |
| 5/30/2006 0:00 | 0 | |
| 5/31/2006 0:00 | 0 | |
| 6/1/2006 0:00 | 0 | |
| 6/2/2006 0:00 | 0 | |
| 6/3/2006 0:00 | 0 | |
| 6/4/2006 0:00 | 0 | |
| 6/5/2006 0:00 | 0 | |
| 6/6/2006 0:00 | 0 | |
| 6/7/2006 0:00 | 0 | |
| 6/8/2006 0:00 | 0 | |
| 6/9/2006 0:00 | 0 | |
| 6/10/2006 0:00 | 0 | 179.307 |
| 6/11/2006 0:00 | 0 | 180.548 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|----------------|----------------|---------------------|
| 6/12/2006 0:00 | 0 | 180.373 |
| 6/13/2006 0:00 | 0 | 161.397 |
| 6/14/2006 0:00 | 0 | 181.393 |
| 6/15/2006 0:00 | 0 | 183.282 |
| 6/16/2006 0:00 | 0 | 182.698 |
| 6/17/2006 0:00 | 0 | 182.917 |
| 6/18/2006 0:00 | 0 | 182.987 |
| 6/19/2006 0:00 | 0 | 180.912 |
| 6/20/2006 0:00 | 0 | 181.422 |
| 6/21/2006 0:00 | 0 | 181.867 |
| 6/22/2006 0:00 | 0 | 182.414 |
| 6/23/2006 0:00 | 0 | 182.402 |
| 6/24/2006 0:00 | 0 | 183.475 |
| 6/25/2006 0:00 | 0 | 184.122 |
| 6/26/2006 0:00 | 0 | 180.388 |
| 6/27/2006 0:00 | 0 | 174.285 |
| 6/28/2006 0:00 | 0 | 197.152 |
| 6/29/2006 0:00 | 0 | 184.344 |
| 6/30/2006 0:00 | 0 | 177.105 |
| 7/1/2006 0:00 | 0 | 177.646 |
| 7/2/2006 0:00 | 0 | 177.383 |
| 7/3/2006 0:00 | 0 | 177.983 |
| 7/4/2006 0:00 | 0 | 177.526 |
| 7/5/2006 0:00 | 0 | 180.511 |
| 7/6/2006 0:00 | 0 | 179.699 |
| 7/7/2006 0:00 | 0 | 182.681 |
| 7/8/2006 0:00 | 0 | 182.513 |
| 7/9/2006 0:00 | 0 | 182.065 |
| 7/10/2006 0:00 | 0 | 182.907 |
| 7/11/2006 0:00 | 0 | 183.027 |
| 7/12/2006 0:00 | 0 | 156.681 |
| 7/13/2006 0:00 | 0 | 123.896 |
| 7/14/2006 0:00 | 0 | 181.623 |
| 7/15/2006 0:00 | 0 | 182.634 |
| 7/16/2006 0:00 | 0 | 182.863 |
| 7/17/2006 0:00 | 0 | 176.754 |
| 7/18/2006 0:00 | 0 | 184.419 |
| 7/19/2006 0:00 | 0 | 183.642 |
| 7/20/2006 0:00 | 0 | 183.437 |
| 7/21/2006 0:00 | 0 | 183.693 |
| 7/22/2006 0:00 | 0 | 181.864 |
| 7/23/2006 0:00 | 0 | 182.056 |
| 7/24/2006 0:00 | 0.321 | 181.855 |
| 7/25/2006 0:00 | 0.591 | 182.123 |
| 7/26/2006 0:00 | 0.605 | 182.035 |
| 7/27/2006 0:00 | 0.603 | 181.673 |
| 7/28/2006 0:00 | 0.587 | 181.791 |
| 7/29/2006 0:00 | 0.607 | 182.919 |
| 7/30/2006 0:00 | 0.608 | 182.999 |
| 7/31/2006 0:00 | 0.626 | 182.508 |
| 8/1/2006 0:00 | 0.625 | 182.061 |

Meter 91 Flows:

| Time | CH 1 High Flow | CH 2 Pressure (HGL) |
|---------------|----------------|---------------------|
| 8/2/2006 0:00 | 0.614 | 180.981 |


Appendix C

Stormwater Drainage System Analysis

NRCS Soil Survey Information

SOIL SURVEY OF MIDDLESEX COUNTY, MASSACHUSETTS

Assembly Square Full Build



MAP LEGEND

- Soil Map Units
- Cities
- Detailed Counties
- Detailed States
- Interstate Highways
- Roads
- Rails
- Water
- Hydrography
- Oceans
- Escarpment, bedrock
- Escarpment, non-bedrock
- Gulley
- Levee
- Slope

- Blowout
- Borrow Pit
- Clay Spot
- Depression, closed
- Eroded Spot
- Gravel Pit
- Gravelly Spot
- Gulley
- Lava Flow
- Landfill
- Marsh or Swamp
- Miscellaneous Water
- Rock Outcrop
- Saline Spot
- Sandy Spot
- Slide or Slip
- Sinkhole
- Sodic Spot
- Spoil Area
- Stony Spot
- Very Stony Spot
- Perennial Water
- Wet Spot

MAP INFORMATION

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>

Coordinate System: UTM Zone 19

Soil Survey Area: Middlesex County, Massachusetts
Spatial Version of Data: 3
Soil Map Compilation Scale: 1:25000

Map comprised of aerial images photographed on these dates:
4/3/1995

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.


Map Unit Legend Summary

Middlesex County, Massachusetts


| Map Unit Symbol | Map Unit Name | Acres in AOI | Percent of AOI |
|-----------------|----------------------------|--------------|----------------|
| 603 | Urban land, wet substratum | 72.0 | 94.8 |
| 655 | Udorthents, wet substratum | 3.9 | 5.2 |

72" Outfall As-Built Plan and Profile


\\VIB\PROJ\WAT-LD\08518.05\CAD\LD\PLANSET\DRAINAGE OUTFALL-CONST\08518.05-OUTFALL PLAN & PROFILE-AB
Saved Friday, March 03, 2012 2:16:54 PM RMAN\TNGS Plotted Friday, March 03, 2012 2:12:07 PM Mathews, Richard



**DRAINAGE OUTFALL
PLAN VIEW**



BEACH NOURISHMENT PLAN



DRAINAGE OUTFALL PROFILE

VHB
Vanasse Hangen Brustlin, Inc.
Transportation
Land Development
Environmental Services
101 Walnut Street, P.O. Box 9151
Watertown, Massachusetts 02471
617.924.1770 • FAX 617.924.2286

- Notes:**
1. UPLAND WORK ZONES, TEMPORARY STAGING AND STOCK PILE AREAS AND ACCESS ROUTES WITHIN THE DCR DRAW 7 PARK ARE SUBJECT TO DCR REVIEW AND APPROVAL AND MAY BE SUBJECT TO CHANGE BASED ON ACTUAL SITE AND CONSTRUCTION CONDITIONS.
 2. SUBJECT TO DCR REVIEW AND APPROVAL, THE CONTRACTOR SHALL COORDINATE CONSTRUCTION SEQUENCING TO PROVIDE SECURE AND SAFE PUBLIC ACCESS TO THE SOUTHERLY PART OF DRAW 7 PARK THROUGHOUT CONSTRUCTION.
 3. FINAL DESIGN OF THE FISHING PLATFORM IS SUBJECT TO DCR REVIEW AND APPROVAL.
 4. CONSTRUCTION DEWATERING SHALL BE DISCHARGED TO A DEWATERING FILTER BAG OR A DEWATERING HAYBALE BASIN PRIOR TO OVERLAND DISCHARGE. DISCHARGE FROM THESE DEWATERING BMPs SHALL BE LOCATED WITHIN THE TEMPORARY STAGING AND STOCKPILE AREA SEDIMENTATION AND EROSION CONTROLS.
 5. AT THE COMPLETION OF CONSTRUCTION, THE CONTRACTOR IS TO REE ALL COFFERDAM SHEETING THAT IS PERPENDICULAR TO THE SHORE LINE. THE COFFERDAM SHEETING THAT IS PARALLEL TO THE SHORE LINE IS TO BE CUT DOWN TO AN ELEVATION OF 1 FOOT BELOW OCEAN FLOOR AND LEFT IN PLACE IN THE GROUND.
 6. CONTRACTOR SHOULD NOTE THAT MBTA SIGNAL CABLES THAT CROSS THE RAILROAD RIGHT OF WAY TRANSVERSELY HAVE A MINIMUM COVER. THIS CONDITION IS NOT ANTICIPATED DIRECTLY AT THE STORM DRAIN CROSSING LOCATION, BUT IS NOTED IN CASE OF UNKNOWN CONDITIONS.

- Beach Nourishment Notes:**
1. ALL EXCAVATED SOILS FROM THE COFFERDAM AREA SHALL BE EXAMINED BY THE ENVIRONMENTAL MONITORING ENGINEER FOR BEACH NOURISHMENT SUITABILITY. SUITABLE SOILS WILL BE SANDS AND COARSE SANDS (SIMILAR TO EXISTING BEACH SOILS). UNSUITABLE SOILS WILL BE SILTS, CLAYS, ROCK AND OTHER DEBRIS.
 2. BOTH SUITABLE AND UNSUITABLE SOILS WILL BE STOCKPILED SEPARATELY WITH EROSION CONTROLS AND BE ALLOWED TO DEWATER.
 3. UNSUITABLE SOILS WILL BE REMOVED FROM THE SITE ONCE ADEQUATELY DEWATERED.
 4. SUITABLE SOILS WILL BE USED IN THE BEACH NOURISHMENT. THE BEACH NOURISHMENT SOIL WILL BE PLACED AT THE OUTFALL HEADWALL AND WORK AWAY IN BOTH DIRECTIONS. THE BEACH NOURISHMENT SOILS WILL BE SPREAD UNTIL THERE IS NO MORE SUITABLE SOIL. NO ADDITIONAL SOILS WILL BE REQUIRED. THE LIMITS ON THE PLAN SHOW THE MAXIMUM AREA OF BEACH NOURISHMENT.

| | | | |
|----------------|------------------------------|------------|--------------|
| 4 | AS-BUILT INFORMATION | 3-09-12 | RPW |
| 3 | JACKING REVISIONS (CONTACTS) | 10-28-11 | RPW |
| 2 | JACKING ALIGNMENT REVISIONS | 10-20-11 | RPW |
| 1 | MBTA COMMENTS | 6-22-11 | RPW |
| No. | Revision | Date | Appr. |
| Designed by | Drawn by | Checked by | |
| CAD checked by | Approved by | | |
| Scale | As Noted | Date | May 13, 2011 |
| Project Title | Assembly on the Mystic | | |

Assembly Square Drive
Somerville, Massachusetts

MBTA Review

Not Approved for Construction
Drawing Title

Plan and Profile

Drawing Number
C-2
Sheet 2 of 5
Project Number
08518.05

08518.05-OUTFALL PLAN & PROFILE-AB.DWG

Scenario: 10 Year with Tailwater
Current Time Step: 0.000Hr
Conduit FlexTable: Combined Pipe/Node Report

| Start Node | Stop Node | Length (Unified) (ft) | System CA (acres) | System Intensity (in/h) | System Rational Flow (ft ³ /s) | Capacity (Full Flow) (ft ³ /s) | Velocity (Average) (ft/s) | Invert (Upstream) (ft) | Invert (Downstream) (ft) | Slope (ft/ft) | Hydraulic Grade Line (In) (ft) | Hydraulic Grade Line (Out) (ft) |
|------------|-----------|-----------------------|-------------------|-------------------------|---|---|---------------------------|------------------------|--------------------------|---------------|--------------------------------|---------------------------------|
| CB-G6N | DMH-G6 | 14.0 | 0.118 | 5.300 | 0.63 | 5.04 | 4.37 | 7.50 | 7.22 | 0.020 | 7.83 | 7.46 |
| CB-G4E | DMH-G4 | 9.0 | 0.273 | 5.300 | 1.46 | 5.04 | 5.55 | 7.00 | 6.82 | 0.020 | 7.65 | 7.68 |
| DCB-G2E | DMH-G2 | 12.0 | 0.232 | 5.300 | 1.24 | 5.14 | 1.58 | 5.00 | 4.75 | 0.021 | 7.72 | 7.70 |
| CB-G1E | DMH-G1 | 43.0 | 0.179 | 5.300 | 0.96 | 3.56 | 1.22 | 4.00 | 3.57 | 0.010 | 7.74 | 7.71 |
| CB-G1NE | DMH-G1 | 56.0 | 0.098 | 5.300 | 0.52 | 3.56 | 0.67 | 4.00 | 3.44 | 0.010 | 7.73 | 7.71 |
| DMH-G1 | DMH-G2 | 45.0 | 0.277 | 5.062 | 1.41 | 77.20 | 0.11 | 2.90 | 2.77 | 0.003 | 7.70 | 7.70 |
| DMH-G2 | DMH-G3 | 42.0 | 0.509 | 3.929 | 2.02 | 79.91 | 0.16 | 2.77 | 2.64 | 0.003 | 7.68 | 7.68 |
| DMH-G3 | DMH-G4 | 155.0 | 0.509 | 3.438 | 1.76 | 79.09 | 0.14 | 2.64 | 2.17 | 0.003 | 7.68 | 7.68 |
| DMH-G4 | DMH-G5 | 203.0 | 0.782 | 2.435 | 1.92 | 62.14 | 0.15 | 2.17 | 1.79 | 0.002 | 7.65 | 7.65 |
| RG-G1 | DMH-G5 | 65.0 | 0.046 | 5.300 | 0.24 | 8.13 | 6.74 | 5.32 | 4.29 | 0.016 | 8.72 | 7.65 |
| DMH-G5 | DMH-G6 | 118.0 | 0.827 | 1.807 | 1.51 | 137.41 | 0.76 | 1.79 | 0.71 | 0.009 | 7.36 | 7.35 |
| DMH-G6 | DMH-G7 | 38.0 | 1.060 | 1.733 | 1.85 | 80.72 | 0.79 | -0.73 | -0.85 | 0.003 | 6.70 | 6.69 |
| DMH-G7 | DMH-G8 | 11.0 | 1.060 | 1.710 | 1.83 | 212.16 | 0.78 | -0.85 | -1.09 | 0.022 | 6.69 | 6.69 |
| DMH-G8 | DMH-G9 | 70.0 | 1.060 | 1.704 | 1.82 | 78.67 | 0.78 | -1.09 | -1.30 | 0.003 | 6.68 | 6.68 |
| CB-F7NE | DMH-F7 | 12.0 | 0.219 | 5.300 | 1.17 | 5.24 | 5.37 | 9.00 | 8.74 | 0.022 | 9.46 | 9.08 |
| CB-F7NW | DMH-F7 | 13.0 | 0.000 | 5.300 | 0.00 | 5.04 | 0.00 | 9.00 | 8.74 | 0.020 | 9.00 | 8.92 |
| CB-F6NE | DMH-F6 | 12.0 | 0.195 | 5.300 | 1.04 | 5.24 | 5.20 | 9.00 | 8.74 | 0.022 | 9.43 | 9.49 |
| CB-F6NW | DMH-F6 | 13.0 | 0.000 | 5.300 | 0.00 | 5.04 | 0.00 | 9.00 | 8.74 | 0.020 | 9.49 | 9.49 |
| CB-F5NW | DMH-F5 | 13.0 | 0.000 | 5.300 | 0.00 | 5.04 | 0.00 | 9.00 | 8.74 | 0.020 | 10.32 | 10.32 |
| CB-F5NE | DMH-F5 | 13.0 | 0.212 | 5.300 | 1.13 | 5.04 | 1.44 | 9.00 | 8.74 | 0.020 | 10.33 | 10.32 |
| CB-F4NW | DMH-F4 | 13.0 | 0.121 | 5.300 | 0.65 | 3.56 | 0.83 | 9.00 | 8.87 | 0.010 | 10.56 | 10.56 |
| CB-F4NE | DMH-F4 | 12.0 | 0.123 | 5.300 | 0.66 | 3.71 | 0.83 | 9.00 | 8.87 | 0.011 | 10.56 | 10.56 |
| CB-F3NE | DMH-F3 | 10.0 | 0.240 | 5.300 | 1.28 | 5.04 | 1.63 | 8.50 | 8.30 | 0.020 | 11.26 | 11.25 |
| CB-F1NE | DMH-F1 | 9.0 | 0.083 | 5.300 | 0.44 | 3.76 | 0.56 | 9.90 | 9.80 | 0.011 | 11.35 | 11.34 |
| DMH-F1 | DMH-F2 | 78.0 | 0.514 | 5.255 | 2.72 | 6.83 | 1.54 | 8.30 | 7.97 | 0.004 | 11.34 | 11.29 |
| DCB-F2E | DMH-F2 | 77.0 | 0.404 | 5.300 | 2.16 | 5.10 | 1.76 | 8.70 | 8.22 | 0.006 | 11.38 | 11.29 |
| DMH-F2 | DMH-F3 | 36.0 | 0.917 | 5.111 | 4.73 | 12.50 | 1.50 | 7.47 | 7.36 | 0.003 | 11.26 | 11.25 |
| DMH-F3 | DMH-C5 | 129.0 | 1.157 | 5.043 | 5.88 | 12.44 | 1.87 | 7.36 | 6.97 | 0.003 | 11.22 | 11.13 |
| CB-C4SW | DMH-C4 | 12.0 | 0.075 | 5.300 | 0.40 | 5.04 | 0.51 | 9.10 | 8.86 | 0.020 | 11.22 | 11.22 |
| CB-C4NW | DMH-C4 | 12.0 | 0.050 | 5.300 | 0.27 | 5.04 | 0.34 | 9.10 | 8.86 | 0.020 | 11.22 | 11.22 |
| CB-C3SW | DMH-C3 | 12.0 | 0.028 | 5.300 | 0.15 | 11.12 | 0.19 | 9.60 | 8.43 | 0.098 | 11.22 | 11.22 |
| CB-C3NW | DMH-C3 | 12.0 | 0.025 | 5.300 | 0.13 | 11.12 | 0.17 | 9.60 | 8.43 | 0.098 | 11.22 | 11.22 |
| DMH-C3 | DMH-C4 | 40.0 | 0.141 | 5.099 | 0.73 | 10.37 | 0.41 | 8.43 | 8.04 | 0.010 | 11.22 | 11.22 |
| DMH-C4 | DMH-C5 | 57.0 | 0.733 | 4.824 | 3.56 | 10.50 | 2.02 | 8.04 | 7.47 | 0.010 | 11.21 | 11.13 |
| DMH-C5 | DMH-C6 | 33.0 | 1.890 | 4.744 | 9.04 | 12.45 | 2.88 | 6.97 | 6.87 | 0.003 | 11.08 | 11.02 |
| CB-C7SE | DMH-C7 | 14.0 | 0.106 | 5.300 | 0.57 | 5.04 | 0.72 | 9.20 | 8.92 | 0.020 | 11.37 | 11.37 |
| CB-C7NE | DMH-C7 | 14.0 | 0.117 | 5.300 | 0.63 | 5.13 | 0.80 | 9.20 | 8.91 | 0.021 | 11.37 | 11.37 |
| CB-C8SE | DMH-C8 | 14.0 | 0.146 | 5.300 | 0.78 | 5.04 | 0.99 | 10.70 | 10.42 | 0.020 | 12.55 | 12.54 |
| CB-C8NE | DMH-C8 | 14.0 | 0.082 | 5.300 | 0.44 | 5.04 | 0.56 | 10.70 | 10.42 | 0.020 | 12.54 | 12.54 |
| DMH-C8 | DMH-C7 | 178.0 | 1.598 | 5.229 | 8.42 | 6.82 | 4.77 | 8.51 | 7.76 | 0.004 | 12.54 | 11.37 |
| DMH-C7 | DMH-C6 | 92.0 | 2.175 | 5.123 | 11.23 | 14.73 | 3.58 | 7.26 | 6.87 | 0.004 | 11.25 | 11.02 |
| DMH-C6 | DMH-F4 | 116.0 | 4.183 | 4.711 | 19.86 | 22.85 | 4.05 | 6.37 | 6.01 | 0.003 | 10.87 | 10.56 |
| DMH-F4 | DMH-F5 | 122.0 | 4.789 | 4.630 | 22.35 | 34.16 | 3.16 | 5.51 | 5.19 | 0.003 | 10.48 | 10.32 |
| DMH-F5 | DMH-D5 | 108.0 | 5.332 | 4.521 | 24.29 | 38.51 | 3.44 | 5.19 | 4.83 | 0.003 | 10.25 | 10.08 |
| CB-D4NW | DMH-D4 | 12.0 | 0.112 | 5.300 | 0.60 | 3.56 | 3.36 | 10.30 | 10.18 | 0.010 | 10.62 | 10.46 |
| CB-D4SW | DMH-D4 | 13.0 | 0.117 | 5.300 | 0.62 | 3.42 | 3.31 | 10.30 | 10.18 | 0.009 | 10.63 | 10.47 |
| DMH-D4 | DMH-D5 | 90.0 | 0.452 | 5.289 | 2.41 | 10.50 | 1.36 | 8.34 | 7.44 | 0.010 | 10.12 | 10.08 |
| DCB-D6S | DMH-D6 | 12.0 | 0.434 | 5.300 | 2.32 | 5.04 | 4.11 | 8.80 | 8.56 | 0.020 | 11.51 | 11.41 |
| CB-D7E | DMH-D7 | 54.0 | 0.133 | 5.300 | 0.71 | 5.18 | 0.91 | 8.83 | 7.69 | 0.021 | 11.59 | 11.57 |
| DMH-D7 | DMH-D6 | 53.0 | 0.995 | 5.131 | 5.15 | 7.90 | 2.91 | 7.69 | 7.39 | 0.006 | 11.54 | 11.41 |
| DMH-D6 | DMH-D5 | 179.0 | 1.428 | 5.080 | 7.31 | 8.08 | 4.65 | 7.39 | 6.33 | 0.006 | 11.23 | 10.08 |
| DMH-D5 | DMH-F6 | 123.0 | 7.212 | 4.432 | 32.22 | 36.58 | 4.69 | 4.83 | 4.46 | 0.003 | 9.86 | 9.49 |
| DMH-F6 | DMH-F7 | 122.0 | 7.870 | 4.357 | 34.57 | 36.73 | 5.02 | 4.46 | 4.09 | 0.003 | 9.35 | 8.92 |
| DMH-F7 | DMH-F8 | 23.0 | 8.089 | 4.288 | 34.97 | 43.98 | 5.08 | 4.09 | 3.99 | 0.004 | 8.15 | 8.07 |
| DMH-F8 | DMH-F9 | 10.0 | 8.089 | 4.275 | 34.86 | 94.32 | 5.06 | 3.99 | 3.79 | 0.020 | 7.92 | 7.89 |
| DMH-F9 | DMH-F10 | 79.0 | 8.089 | 4.270 | 34.82 | 36.76 | 5.05 | 3.79 | 3.55 | 0.003 | 7.74 | 7.45 |
| CB-E2SE | DMH-E2 | 8.0 | 0.195 | 5.300 | 1.04 | 5.19 | 5.16 | 7.80 | 7.63 | 0.021 | 8.23 | 8.14 |
| CB-E2NE | DMH-E2 | 49.0 | 0.154 | 5.300 | 0.82 | 3.56 | 3.69 | 7.80 | 7.31 | 0.010 | 8.18 | 8.14 |
| DMH-E2 | DMH-E1 | 33.0 | 0.348 | 5.262 | 1.85 | 3.56 | 4.58 | 7.31 | 6.98 | 0.010 | 8.08 | 8.03 |
| DMH-E1 | MH-68 | 9.0 | 0.348 | 5.242 | 1.84 | 3.36 | 2.34 | 5.56 | 5.48 | 0.009 | 8.03 | 8.01 |
| CB-21 | DMH-22 | 5.0 | 0.496 | 5.300 | 2.65 | 4.51 | 3.37 | 6.82 | 6.74 | 0.016 | 8.52 | 8.49 |
| CB-20 | DMH-22 | 49.0 | 0.428 | 5.300 | 2.29 | 3.53 | 2.91 | 6.82 | 6.34 | 0.010 | 8.70 | 8.49 |
| CB-18 | DMH-19 | 6.0 | 0.140 | 5.300 | 0.75 | 5.44 | 4.86 | 8.74 | 8.60 | 0.023 | 9.24 | 9.26 |
| CB-17 | DMH-19 | 49.0 | 0.141 | 5.300 | 0.75 | 3.60 | 3.62 | 8.74 | 8.24 | 0.010 | 9.26 | 9.26 |
| CB-11 | DMH-12 | 5.0 | 0.530 | 5.300 | 2.83 | 3.90 | 3.60 | 6.66 | 6.60 | 0.012 | 10.64 | 10.61 |
| CB-10 | DMH-12 | 49.0 | 0.419 | 5.300 | 2.24 | 3.56 | 2.85 | 6.66 | 6.17 | 0.010 | 10.80 | 10.61 |
| CB-A6SE | DMH-A6 | 14.0 | 0.367 | 5.300 | 1.96 | 3.56 | 2.49 | 8.08 | 7.94 | 0.010 | 11.44 | 11.40 |
| CB-A6N | DMH-A6 | 15.0 | 0.169 | 5.300 | 0.90 | 3.56 | 1.15 | 8.09 | 7.94 | 0.010 | 11.41 | 11.40 |
| DMH-A6 | DMH-A5 | 93.0 | 0.777 | 5.263 | 4.12 | 5.76 | 2.33 | 7.94 | 7.66 | 0.003 | 11.72 | 11.58 |
| DMH-A5 | DMH-A4 | 126.0 | 0.777 | 5.150 | 4.03 | 5.77 | 2.28 | 7.66 | 7.28 | 0.003 | 11.55 | 11.36 |
| CB-A4S | DMH-A4 | 14.0 | 0.041 | 5.300 | 0.22 | 5.04 | 0.28 | 10.00 | 9.72 | 0.020 | 11.36 | 11.36 |
| CB-A4N | DMH-A4 | 14.0 | 0.053 | 5.300 | 0.28 | 5.13 | 0.36 | 10.00 | 9.71 | 0.021 | 11.36 | 11.36 |
| DMH-A4 | DMH-A3 | 178.0 | 0.871 | 4.994 | 4.39 | 12.34 | 1.40 | 7.28 | 6.75 | 0.003 | 11.34 | 11.27 |
| DMH-A3 | DMH-A2 | 42.0 | 1.360 | 4.632 | 6.35 | 12.59 | 2.02 | 6.75 | 6.62 | 0.003 | 11.25 | 11.21 |
| CB-A1S | DMH-A2 | 15.0 | 0.159 | 5.300 | 0.85 | 4.69 | 1.08 | 7.50 | 7.24 | 0.017 | 11.22 | 11.21 |
| CB-A1N | DMH-A2 | 13.0 | 0.089 | 5.300 | 0.48 | 5.93 | 0.61 | 7.60 | 7.24 | 0.028 | 11.22 | 11.21 |
| DMH-A2 | DMH-A1 | 23.0 | 1.642 | 4.574 | 7.57 | 14.92 | 2.41 | 6.62 | 6.52 | 0.004 | 11.19 | 11.16 |
| DMH-A1 | DMH-8 | 93.0 | 1.642 | 4.546 | 7.53 | 12.19 | 2.40 | 6.49 | 6.22 | 0.003 | 11.12 | 11.01 |
| CB-8B | DMH-8 | 22.0 | 0.058 | 5.300 | 0.31 | 3.13 | 0.39 | 8.45 | 8.28 | 0.008 | 11.02 | 11.01 |
| CB-8C | DMH-8 | 61.0 | 0.151 | 5.300 | 0.80 | 3.41 | 1.02 | 8.20 | 7.64 | 0.009 | 11.05 | 11.01 |
| CB-8A | DMH-8 | 65.0 | 0.229 | 5.300 | 1.22 | 2.42 | 1.56 | 8.29 | 7.99 | 0.005 | 11.09 | 11.01 |
| DMH-8 | DMH-9 | 83.0 | 2.079 | 4.436 | 9.30 | 11.10 | 2.96 | 6.22 | 6.02 | 0.002 | 10.95 | 10.81 |
| DMH-9 | DMH-12 | 97.0 | 2.079 | 4.357 | 9.13 | 11.25 | 2.91 | 6.00 | 5.76 | 0.002 | 10.76 | 10.61 |
| DMH-12 | DMH-13 | 242.0 | 3.028 | 4.262 | 13.01 | 20.93 | 2.65 | 5.26 | 4.63 | 0.003 | 10.52 | 10.27 |
| CB-C1N | DMH-C1 | 24.0 | 0.064 | 5.300 | 0.34 | 5.04 | 0.44 | 10.00 | 9.52 | 0.020 | 11.30 | 11.30 |
| CB-C1SE | DMH-C1 | 17.0 | 0.056 | 5.300 | 0.30 | 4.96 | 0.38 | 10.00 | 9.67 | 0.019 | 11.30 | 11.30 |
| CB-C2NE | DMH-C2 | 23.0 | 0.071 | 5.300 | 0.38 | 5.04 | 0.48 | 8.80 | 8.34 | 0.020 | 11.86 | 11.86 |
| CB-C2SE | DMH-C2 | 13.0 | 0.073 | 5.300 | 0.39 | 5.04 | 0.50 | 8.90 | 8.64 | 0.020 | 11.86 | 11.86 |
| DMH-C2 | DMH-C1 | 77.0 | 1.629 | 5.165 | 8.48 | 10.50 | 4.80 | 7.63 | 6.86 | 0.010 | 11.80 | 11.30 |
| DMH-C1 | DMH-13 | 123.0 | 1.749 | 5.120 | 9.03 | 10.50 | 5.11 | 6.86 | 5.63 | 0.010 | 11.18 | 10.27 |
| DMH-13 | DMH-16 | 64.0 | 4.777 | 4.004 | 19.28 | 21.14 | 3.93 | 4.63 | 4.46 | 0.003 | 10.03 | 9.89 |
| CB-14 | DMH-16 | 49.0 | 0.081 | 5.300 | 0.43 | 3.60 | 3.09 | 9.21 | 8.71 | 0.010 | 9.89 | 9.89 |

| | | | | | | | | | | | | |
|-------------------|---------|-------|--------|-------|-------|--------|------|-------|-------|--------|-------|-------|
| CB-15 | DMH-16 | 12.0 | 0.078 | 5.300 | 0.42 | 2.30 | 2.22 | 9.19 | 9.14 | 0.004 | 9.89 | 9.89 |
| DMH-16 | DMH-19 | 240.0 | 4.936 | 3.958 | 19.69 | 20.85 | 4.01 | 4.46 | 3.84 | 0.003 | 9.82 | 9.26 |
| DMH-19 | DMH-D1 | 42.0 | 5.217 | 3.788 | 19.92 | 33.91 | 2.82 | 3.34 | 3.23 | 0.003 | 9.20 | 9.16 |
| DMH-D3 | DMH-D2 | 46.0 | 1.280 | 5.300 | 6.84 | 7.74 | 3.87 | 6.52 | 6.27 | 0.005 | 10.64 | 10.44 |
| CB-D2S | DMH-D2 | 29.0 | 0.214 | 5.300 | 1.14 | 3.17 | 2.95 | 7.00 | 6.77 | 0.008 | 10.56 | 10.44 |
| DMH-D2 | DMH-D1 | 104.0 | 1.808 | 5.266 | 9.60 | 11.52 | 6.09 | 5.77 | 4.52 | 0.012 | 10.25 | 9.16 |
| DMH-D1 | DMH-22 | 194.0 | 7.024 | 3.746 | 26.52 | 33.91 | 3.92 | 3.23 | 2.73 | 0.003 | 8.83 | 8.49 |
| DMH-22 | DMH-23 | 122.0 | 7.948 | 3.606 | 28.89 | 51.52 | 3.12 | 2.23 | 1.91 | 0.003 | 8.39 | 8.28 |
| DMH-23 | DMH-24 | 11.0 | 7.948 | 3.559 | 28.51 | 95.92 | 3.09 | 1.86 | 1.76 | 0.009 | 8.24 | 8.23 |
| DMH-24 | DMH-105 | 30.0 | 7.948 | 3.555 | 28.48 | 91.84 | 3.08 | 1.71 | 1.46 | 0.008 | 8.18 | 8.16 |
| CB-30 | DMH-31 | 47.0 | 0.320 | 5.300 | 1.71 | 3.52 | 2.18 | 7.41 | 6.95 | 0.010 | 9.11 | 9.00 |
| CB-32O | DMH-32M | 54.0 | 0.000 | 5.300 | 0.00 | 3.43 | 0.00 | 4.00 | 3.50 | 0.009 | 9.70 | 9.70 |
| CB-32R | DMH-32P | 37.0 | 0.386 | 5.300 | 2.06 | 3.31 | 2.63 | 7.64 | 7.32 | 0.009 | 10.04 | 9.92 |
| CB-32Q | DMH-32P | 22.0 | 0.288 | 5.300 | 1.54 | 2.94 | 1.96 | 7.48 | 7.33 | 0.007 | 9.96 | 9.92 |
| DMH-32P | DMH-32M | 53.0 | 1.266 | 5.260 | 6.71 | 10.99 | 3.80 | 3.02 | 2.44 | 0.011 | 9.92 | 9.70 |
| CB-32N | DMH-32M | 12.0 | 0.313 | 5.300 | 1.67 | 2.91 | 2.13 | 6.88 | 6.80 | 0.007 | 9.73 | 9.70 |
| CB-F15 | DMH-F13 | 17.0 | 0.146 | 5.300 | 0.78 | 5.04 | 0.99 | 7.10 | 6.76 | 0.020 | 11.06 | 11.05 |
| CB-F14 | DMH-F13 | 16.0 | 0.208 | 5.300 | 1.10 | 5.19 | 1.40 | 7.10 | 6.76 | 0.021 | 11.06 | 11.05 |
| CB-F13 | DMH-F12 | 10.0 | 0.151 | 5.300 | 0.81 | 5.04 | 1.03 | 9.30 | 9.10 | 0.020 | 11.45 | 11.44 |
| CB-F12 | DMH-F11 | 12.0 | 0.145 | 5.300 | 0.77 | 5.04 | 0.99 | 9.30 | 9.06 | 0.020 | 11.50 | 11.49 |
| DMH-F11 | DMH-F12 | 128.0 | 0.388 | 5.265 | 2.06 | 10.50 | 1.17 | 7.19 | 5.91 | 0.010 | 11.49 | 11.44 |
| DMH-F12 | DMH-F13 | 140.0 | 1.066 | 4.954 | 5.32 | 10.50 | 3.01 | 5.91 | 4.51 | 0.010 | 11.41 | 11.05 |
| DMH-F13 | DMH-32T | 76.0 | 1.418 | 4.823 | 6.89 | 10.29 | 3.90 | 4.51 | 3.78 | 0.010 | 10.99 | 10.66 |
| CB-32Z | DMH-32Y | 31.0 | 0.000 | 5.300 | 0.00 | 2.56 | 5.37 | 3.86 | 3.70 | 0.005 | 11.40 | 10.96 |
| DMH-32Y | DMH-32U | 47.0 | 0.000 | 5.284 | 0.00 | 6.85 | 2.39 | 3.69 | 3.49 | 0.004 | 10.75 | 10.67 |
| CB-32V | DMH-32U | 27.0 | 0.255 | 5.300 | 1.36 | 3.22 | 1.74 | 6.59 | 6.37 | 0.008 | 10.71 | 10.67 |
| CB-32W | DMH-32U | 18.0 | 0.212 | 5.300 | 1.13 | 3.03 | 1.45 | 6.39 | 6.26 | 0.007 | 10.69 | 10.67 |
| CB-32X | DMH-32U | 38.0 | 0.217 | 5.300 | 1.16 | 3.32 | 1.47 | 6.29 | 5.96 | 0.009 | 10.71 | 10.67 |
| DMH-32U | DMH-32T | 119.0 | 1.083 | 5.227 | 5.71 | 6.88 | 5.62 | 3.39 | 2.88 | 0.004 | 11.72 | 10.66 |
| DMH-32T | DMH-32S | 171.0 | 2.501 | 4.767 | 12.02 | 21.96 | 3.31 | 2.78 | 2.29 | 0.003 | 10.47 | 10.20 |
| DMH-32S | DMH-32M | 277.0 | 2.501 | 4.621 | 11.65 | 22.45 | 3.23 | 2.27 | 1.44 | 0.003 | 10.12 | 9.70 |
| DMH-32M | DMH-32L | 24.0 | 4.081 | 4.378 | 18.01 | 22.15 | 4.53 | 1.42 | 1.35 | 0.003 | 9.57 | 9.50 |
| DMH-32L | DMH-32K | 9.0 | 4.081 | 4.363 | 17.95 | 43.23 | 4.52 | 1.30 | 1.20 | 0.011 | 9.40 | 9.37 |
| DMH-32K | DMH-32 | 17.0 | 4.081 | 4.358 | 17.92 | 24.37 | 4.51 | 1.15 | 1.09 | 0.004 | 9.28 | 9.23 |
| CB-34N | CB-34M | 32.0 | 0.206 | 5.300 | 1.10 | 10.24 | 0.62 | 6.81 | 6.63 | 0.006 | 10.60 | 10.60 |
| CB-34M | CB-34L | 40.0 | 0.415 | 5.155 | 2.16 | 10.35 | 1.22 | 6.63 | 6.40 | 0.006 | 10.60 | 10.59 |
| CB-34L | CB-34K | 93.0 | 0.633 | 5.062 | 3.23 | 10.41 | 1.83 | 6.40 | 5.86 | 0.006 | 10.59 | 10.54 |
| CB-34K | CB-34J | 25.0 | 0.880 | 4.917 | 4.36 | 10.22 | 2.47 | 5.86 | 5.72 | 0.006 | 10.54 | 10.51 |
| CB-34J | CB-34I | 51.0 | 1.114 | 4.889 | 5.49 | 10.12 | 3.11 | 5.72 | 5.44 | 0.005 | 10.51 | 10.43 |
| CB-34I | CB-34H | 48.0 | 1.330 | 4.842 | 6.49 | 22.46 | 2.07 | 5.44 | 5.16 | 0.006 | 10.43 | 10.40 |
| CB-34H | CB-34G | 41.0 | 1.560 | 4.776 | 7.51 | 22.03 | 2.39 | 5.16 | 4.93 | 0.006 | 10.40 | 10.38 |
| CB-34G | CB-34F | 41.0 | 1.776 | 4.728 | 8.46 | 22.50 | 2.69 | 4.93 | 4.69 | 0.006 | 10.38 | 10.34 |
| CB-34F | CB-34E | 42.0 | 1.983 | 4.685 | 9.36 | 22.23 | 2.98 | 4.69 | 4.45 | 0.006 | 10.34 | 10.30 |
| CB-34E | CB-34D | 41.0 | 2.190 | 4.645 | 10.26 | 22.03 | 3.26 | 4.45 | 4.22 | 0.006 | 10.30 | 10.25 |
| CB-34D | CB-34C | 41.0 | 2.418 | 4.609 | 11.24 | 22.50 | 3.58 | 4.22 | 3.98 | 0.006 | 10.25 | 10.19 |
| CB-34C | DMH-34A | 18.0 | 2.641 | 4.577 | 12.18 | 19.61 | 3.88 | 3.98 | 3.90 | 0.004 | 10.19 | 10.16 |
| CB-34B | DMH-34A | 32.0 | 0.043 | 5.300 | 0.23 | 3.73 | 0.29 | 4.90 | 4.55 | 0.011 | 10.16 | 10.16 |
| DMH-34A | DMH-34 | 67.0 | 2.683 | 4.564 | 12.34 | 23.12 | 3.93 | 3.90 | 3.20 | 0.010 | 10.01 | 9.81 |
| CB-39D | CB-39C | 70.0 | 0.152 | 5.300 | 0.81 | 3.56 | 1.03 | 6.00 | 5.30 | 0.010 | 9.55 | 9.51 |
| CB-39C | DMH-39A | 23.0 | 0.152 | 5.108 | 0.78 | 5.75 | 0.99 | 5.30 | 4.70 | 0.026 | 9.51 | 9.50 |
| CB-39B | DMH-39A | 16.0 | 0.258 | 5.300 | 1.38 | 3.56 | 1.75 | 5.11 | 4.95 | 0.010 | 9.52 | 9.50 |
| DMH-39A | DMH-38 | 50.0 | 0.409 | 5.042 | 2.08 | 6.13 | 1.70 | 4.70 | 4.25 | 0.009 | 9.76 | 9.71 |
| CB-38A | DMH-38 | 35.0 | 0.000 | 5.300 | 0.00 | 7.94 | 2.33 | 3.40 | 3.20 | 0.006 | 9.76 | 9.71 |
| CB-40A | DMH-41 | 12.0 | 0.214 | 5.300 | 1.14 | 2.72 | 1.46 | 5.57 | 5.50 | 0.006 | 9.50 | 9.49 |
| CB-43 | DMH-44 | 26.0 | 0.161 | 5.300 | 0.86 | 1.56 | 1.09 | 6.16 | 6.11 | 0.002 | 9.66 | 9.65 |
| CB-42 | DMH-44 | 19.0 | 0.220 | 5.300 | 1.17 | 4.90 | 1.49 | 6.15 | 5.79 | 0.019 | 9.67 | 9.65 |
| CB-45A | DMH-45 | 35.0 | 0.164 | 5.300 | 0.88 | 3.56 | 1.12 | 7.12 | 6.77 | 0.010 | 10.32 | 10.29 |
| CB-46B | DMH-46A | 45.0 | 0.146 | 5.300 | 0.78 | 2.19 | 1.43 | 7.75 | 7.30 | 0.010 | 11.12 | 11.06 |
| CB-46E | DMH-46C | 7.0 | 0.439 | 5.300 | 2.34 | -2.50 | 6.72 | 10.60 | 10.90 | -0.043 | 12.78 | 12.52 |
| CB-46D | DMH-46C | 40.0 | 0.195 | 5.300 | 1.04 | -1.05 | 2.99 | 10.60 | 10.90 | -0.008 | 12.81 | 12.52 |
| CB-46H | DMH-46F | 8.0 | 0.481 | 5.300 | 2.57 | 1.35 | 7.37 | 14.30 | 14.20 | 0.013 | 15.22 | 14.85 |
| CB-46G | DMH-46F | 39.0 | 0.138 | 5.300 | 0.74 | -1.37 | 2.11 | 13.70 | 14.20 | -0.013 | 14.94 | 14.78 |
| CB-46M | CB-46L | 58.0 | 0.111 | 5.300 | 0.59 | 1.23 | 3.49 | 16.60 | 16.00 | 0.010 | 16.96 | 16.51 |
| CB-46L | DMH-46K | 46.0 | 0.216 | 5.253 | 1.15 | 1.26 | 4.09 | 16.00 | 15.50 | 0.011 | 16.51 | 16.00 |
| CB-46Q | DMH-46N | 7.0 | 0.086 | 5.300 | 0.46 | 4.86 | 3.89 | 17.20 | 17.07 | 0.019 | 17.53 | 17.56 |
| CB-46O | DMH-46N | 23.0 | 0.099 | 5.300 | 0.53 | 1.38 | 3.69 | 17.37 | 17.07 | 0.013 | 17.71 | 17.56 |
| DMH-46P | DMH-46N | 22.0 | 0.073 | 5.300 | 0.39 | 1.24 | 3.14 | 17.30 | 17.07 | 0.010 | 17.59 | 17.56 |
| DMH-46N | DMH-46K | 137.0 | 0.258 | 5.280 | 1.37 | 13.52 | 4.91 | 17.07 | 14.80 | 0.017 | 17.51 | 15.82 |
| DMH-46K | DMH-46J | 37.0 | 0.474 | 5.201 | 2.49 | 13.38 | 5.79 | 14.80 | 14.20 | 0.016 | 15.40 | 14.89 |
| DMH-46J | DMH-46I | 12.0 | 0.474 | 5.183 | 2.48 | 13.56 | 5.84 | 14.20 | 14.00 | 0.017 | 14.80 | 14.80 |
| DMH-46I | DMH-46F | 52.0 | 0.474 | 5.177 | 2.47 | 11.28 | 5.12 | 14.00 | 13.40 | 0.012 | 14.74 | 14.78 |
| DMH-46F | DMH-46C | 150.0 | 1.094 | 5.148 | 5.68 | 15.34 | 8.03 | 13.40 | 10.20 | 0.021 | 14.32 | 12.52 |
| DMH-46C | DMH-46A | 149.0 | 1.728 | 5.096 | 8.88 | 14.40 | 5.02 | 10.10 | 7.30 | 0.019 | 12.13 | 11.06 |
| DMH-46A | DMH-45 | 78.0 | 1.874 | 5.011 | 9.47 | 12.47 | 5.36 | 7.30 | 6.20 | 0.014 | 10.93 | 10.29 |
| CB-45B | DMH-45 | 8.0 | 0.169 | 5.300 | 0.90 | 3.31 | 2.59 | 6.80 | 6.20 | 0.075 | 10.34 | 10.29 |
| CB-45C | DMH-45 | 33.0 | 0.188 | 5.300 | 1.01 | -2.63 | 1.28 | 6.85 | 7.03 | -0.005 | 10.32 | 10.29 |
| DMH-45 | DMH-44 | 182.0 | 2.396 | 4.970 | 12.00 | 23.36 | 3.82 | 6.20 | 4.26 | 0.011 | 10.16 | 9.65 |
| DMH-44 | DMH-41 | 186.0 | 2.776 | 4.835 | 13.53 | 46.13 | 1.91 | 4.16 | 3.27 | 0.005 | 9.57 | 9.49 |
| CB-40 | DMH-41 | 3.0 | 0.120 | 5.300 | 0.64 | 5.44 | 0.81 | 5.48 | 5.41 | 0.023 | 9.49 | 9.49 |
| CB-39 | DMH-41 | 38.0 | 0.264 | 5.300 | 1.41 | 3.37 | 1.80 | 5.23 | 4.89 | 0.009 | 9.55 | 9.49 |
| DMH-41 | DMH-38 | 60.0 | 3.374 | 4.560 | 15.51 | 58.08 | 1.61 | 3.22 | 3.02 | 0.003 | 9.72 | 9.71 |
| DMH-38A(Partners) | DMH-38 | 123.0 | 6.562 | 5.300 | 35.06 | 55.92 | 3.64 | 3.40 | 3.02 | 0.003 | 9.86 | 9.71 |
| DMH-38 | DMH-37 | 431.0 | 10.345 | 4.454 | 46.45 | 74.52 | 4.02 | 3.02 | 1.86 | 0.003 | 10.53 | 10.00 |
| CB-36 | DMH-37 | 3.0 | 0.510 | 5.300 | 2.73 | 6.50 | 3.47 | 5.72 | 5.62 | 0.033 | 10.02 | 10.00 |
| CB-35 | DMH-37 | 36.0 | 0.438 | 5.300 | 2.34 | 3.51 | 2.98 | 5.80 | 5.45 | 0.010 | 10.16 | 10.00 |
| DMH-37 | DMH-34 | 101.0 | 11.294 | 4.151 | 47.25 | 74.26 | 4.09 | 1.84 | 1.57 | 0.003 | 9.94 | 9.81 |
| DMH-34 | DMH-33B | 71.0 | 13.977 | 4.081 | 57.50 | 78.12 | 4.90 | 1.56 | 1.35 | 0.003 | 9.64 | 9.51 |
| DMH-33B | DMH-33A | 12.0 | 13.977 | 4.040 | 56.92 | 131.12 | 4.86 | 1.30 | 1.20 | 0.008 | 9.40 | 9.38 |
| DMH-33A | DMH-32 | 24.0 | 13.977 | 4.033 | 56.82 | 77.57 | 4.85 | 1.15 | 1.08 | 0.003 | 9.27 | 9.23 |
| CB-32D | DMH-32B | 39.0 | 0.140 | 5.300 | 0.75 | 3.33 | 0.95 | 6.62 | 6.28 | 0.009 | 9.28 | 9.26 |
| CB-32C | DMH-32B | 21.0 | 0.134 | 5.300 | 0.72 | 3.21 | 0.91 | 6.90 | 6.73 | 0.008 | 9.27 | 9.26 |
| CB-32I | DMH-32H | 17.0 | 0.183 | 5.300 | 0.98 | 1.31 | 2.80 | 6.70 | 6.50 | 0.012 | 9.48 | 9.37 |
| CB-32J | DMH-32H | 48.0 | 0.171 | 5.300 | 0.91 | 1.23 | 2.61 | 6.40 | 5.90 | 0.010 | 9.65 | 9.37 |
| DMH-32H | DMH-32E | 119.0 | 0.353 | 5.248 | 1.87 | 22.14 | 0.60 | 5.90 | 4.76 | 0.010 | 9.31 | 9.30 |
| CB-32G | DMH-32E | 44.0 | 0.088 | 5.300 | 0.47 | 1.21 | 1.34 | 5.71 | 5.27 | 0.010 | | |

| | | | | | | | | | | | | |
|----------|---------|-------|--------|-------|--------|--------|------|--------|--------|--------|-------|-------|
| DMH-28 | DMH-28 | 165.0 | 20.097 | 3.578 | 72.48 | 180.57 | 2.86 | 0.65 | 0.35 | 0.002 | 8.80 | 8.74 |
| CB-27 | DMH-25 | 158.0 | 20.587 | 3.514 | 72.92 | 178.27 | 2.87 | 0.35 | 0.07 | 0.002 | 8.70 | 8.64 |
| CB-26 | DMH-25 | 5.0 | 0.262 | 5.300 | 1.40 | 2.76 | 3.53 | 8.42 | 8.39 | 0.006 | 8.92 | 8.89 |
| DMH-25 | DMH-25 | 48.0 | 0.205 | 5.300 | 1.09 | 3.53 | 3.96 | 8.41 | 7.94 | 0.010 | 8.85 | 8.64 |
| CB-24C | DMH-105 | 61.0 | 21.054 | 3.453 | 73.28 | 179.83 | 2.89 | 0.07 | -0.04 | 0.002 | 8.18 | 8.16 |
| CB-24G | DMH-24B | 34.0 | 0.050 | 5.300 | 0.27 | 3.56 | 0.34 | 5.23 | 4.89 | 0.010 | 8.33 | 8.33 |
| CB-24J | DMH-24E | 41.0 | 0.072 | 5.300 | 0.38 | 4.98 | 0.49 | 5.90 | 5.10 | 0.020 | 8.45 | 8.44 |
| CB-24K | DMH-24I | 9.0 | 0.156 | 5.300 | 0.83 | 1.45 | 2.39 | 5.80 | 5.67 | 0.014 | 9.01 | 8.97 |
| DMH-24I | DMH-24I | 54.0 | 0.183 | 5.300 | 0.98 | 1.87 | 2.80 | 6.70 | 5.41 | 0.024 | 9.32 | 8.97 |
| DMH-24H | DMH-24H | 173.0 | 0.339 | 5.245 | 1.79 | 3.61 | 2.28 | 5.41 | 3.63 | 0.010 | 8.96 | 8.52 |
| DMH-24H | DMH-24E | 23.0 | 0.339 | 5.030 | 1.72 | 5.04 | 2.19 | 3.53 | 3.07 | 0.020 | 8.50 | 8.44 |
| CB-24M | DMH-24L | 18.0 | 0.456 | 5.300 | 2.44 | 6.50 | 3.10 | 3.10 | 2.50 | 0.033 | 8.88 | 8.79 |
| CB-24P | DMH-24N | 23.0 | 0.675 | 5.300 | 3.61 | 5.25 | 4.59 | 4.60 | 4.10 | 0.022 | 8.86 | 8.62 |
| CB-24Q | DMH-24N | 21.0 | 0.548 | 5.300 | 2.93 | 7.38 | 3.73 | 5.00 | 4.10 | 0.043 | 8.76 | 8.62 |
| CB-24Q | DMH-24N | 154.0 | 0.071 | 5.300 | 0.38 | 3.63 | 0.48 | 5.60 | 4.00 | 0.010 | 8.64 | 8.62 |
| CB-24S | DMH-24R | 26.0 | 0.171 | 5.300 | 0.91 | 4.42 | 1.16 | 6.60 | 6.20 | 0.015 | 9.39 | 9.37 |
| CB-24T | DMH-24R | 11.0 | 0.775 | 5.300 | 4.14 | -11.77 | 5.27 | 5.40 | 6.60 | -0.109 | 9.52 | 9.37 |
| CB-24U | DMH-24R | 116.0 | 0.161 | 5.300 | 0.86 | 2.96 | 1.09 | 7.10 | 6.30 | 0.007 | 9.44 | 9.37 |
| DMH-24R | DMH-24N | 300.0 | 1.106 | 4.999 | 5.57 | 8.58 | 3.15 | 6.10 | 4.10 | 0.007 | 9.47 | 8.62 |
| DMH-24N | DMH-24L | 294.0 | 2.400 | 4.394 | 10.63 | 16.16 | 3.38 | 4.00 | 2.50 | 0.005 | 9.44 | 8.79 |
| DMH-24L | DMH-24E | 80.0 | 2.856 | 4.148 | 11.94 | 14.96 | 3.80 | 2.50 | 2.15 | 0.004 | 8.67 | 8.44 |
| CB-24F | DMH-24E | 15.0 | 0.136 | 5.300 | 0.73 | 3.05 | 0.93 | 5.73 | 5.62 | 0.007 | 8.45 | 8.44 |
| DMH-24E | DMH-24B | 37.0 | 3.403 | 4.089 | 14.02 | 75.96 | 1.98 | 1.35 | 0.87 | 0.013 | 8.34 | 8.33 |
| CB-24D | DMH-24B | 35.0 | 0.121 | 5.300 | 0.65 | 1.51 | 1.85 | 6.65 | 6.10 | 0.016 | 8.43 | 8.33 |
| DMH-24B | DMH-24A | 47.0 | 3.574 | 4.036 | 14.54 | 63.05 | 2.06 | 0.87 | 0.45 | 0.009 | 8.29 | 8.27 |
| DMH-24A | DMH-105 | 199.0 | 3.574 | 3.971 | 14.31 | 25.90 | 2.02 | 0.30 | 0.00 | 0.002 | 8.25 | 8.16 |
| DMH-105 | MH-68 | 43.0 | 32.577 | 3.429 | 112.61 | 266.27 | 4.32 | -0.04 | -0.21 | 0.004 | 8.05 | 8.01 |
| MH-68 | DMH-107 | 222.0 | 32.925 | 3.418 | 113.45 | 258.94 | 4.35 | -0.21 | -1.04 | 0.004 | 7.89 | 7.70 |
| DMH-107 | DMH-F10 | 172.0 | 34.723 | 3.362 | 117.66 | 256.30 | 4.50 | -1.04 | -1.67 | 0.004 | 7.61 | 7.45 |
| DMH-F10 | DMH-G9 | 374.0 | 42.812 | 3.319 | 143.24 | 267.30 | 5.43 | -1.67 | -3.16 | 0.004 | 7.17 | 6.68 |
| CB-G12SE | DMH-G12 | 13.0 | 0.075 | 5.300 | 0.40 | 5.13 | 3.90 | 8.00 | 7.73 | 0.021 | 8.26 | 7.92 |
| CB-G13SE | DMH-G13 | 13.0 | 0.107 | 5.300 | 0.57 | 5.04 | 4.25 | 7.50 | 7.24 | 0.020 | 8.08 | 8.09 |
| DMH-63B | DMH-G14 | 23.0 | 1.193 | 3.600 | 4.33 | 2.97 | 7.94 | 4.75 | 4.50 | 0.011 | 9.87 | 9.34 |
| CB-G15SE | DMH-G15 | 13.0 | 0.082 | 5.300 | 0.44 | 5.04 | 0.56 | 7.70 | 7.44 | 0.020 | 9.35 | 9.35 |
| MH-74 | DMH-G15 | 10.0 | 0.037 | 5.300 | 0.20 | 4.63 | 0.25 | 4.90 | 4.80 | 0.010 | 9.35 | 9.35 |
| DMH-G15 | DMH-G14 | 24.0 | 0.122 | 5.188 | 0.64 | 9.83 | 0.36 | 4.71 | 4.50 | 0.009 | 9.34 | 9.34 |
| CB-G14SW | DMH-G14 | 17.0 | 0.062 | 5.300 | 0.33 | 5.11 | 0.42 | 7.80 | 7.45 | 0.021 | 9.34 | 9.34 |
| DMH-G14 | DMH-G13 | 167.0 | 1.714 | 3.597 | 6.21 | 9.34 | 3.52 | 4.50 | 3.18 | 0.008 | 8.67 | 8.09 |
| CB-G13SW | DMH-G13 | 13.0 | 0.103 | 5.300 | 0.55 | 4.84 | 4.09 | 7.50 | 7.26 | 0.018 | 8.08 | 8.09 |
| DMH-G13 | DMH-G12 | 149.0 | 2.364 | 3.544 | 8.44 | 20.13 | 2.69 | 2.68 | 1.50 | 0.008 | 8.02 | 7.82 |
| CB-G12SW | DMH-G12 | 13.0 | 0.045 | 5.300 | 0.24 | 5.13 | 3.35 | 8.00 | 7.73 | 0.021 | 8.20 | 7.86 |
| DMH-G12 | DMH-G11 | 47.0 | 2.590 | 3.482 | 9.09 | 20.34 | 2.89 | 1.50 | 1.12 | 0.008 | 7.21 | 7.14 |
| CB-E6SW | DMH-E6 | 9.0 | 0.247 | 5.300 | 1.32 | 3.56 | 4.20 | 8.61 | 8.52 | 0.010 | 9.10 | 8.95 |
| CB-E6NW | DMH-E6 | 26.0 | 0.247 | 5.300 | 1.32 | 3.56 | 4.20 | 8.78 | 8.52 | 0.010 | 9.27 | 8.94 |
| CB-E3SW | DMH-E3 | 12.0 | 0.156 | 5.300 | 0.83 | 3.56 | 1.06 | 9.10 | 8.98 | 0.010 | 10.12 | 10.11 |
| CB-E3NW | DMH-E3 | 26.0 | 0.151 | 5.300 | 0.81 | 3.63 | 3.72 | 10.19 | 9.92 | 0.010 | 10.57 | 10.24 |
| DMH-E3 | DMH-E4 | 140.0 | 0.307 | 5.268 | 1.63 | 10.50 | 0.92 | 8.09 | 6.69 | 0.010 | 9.66 | 9.63 |
| CB-E4NW | DMH-E4 | 26.0 | 0.134 | 5.300 | 0.71 | 4.99 | 4.51 | 9.50 | 8.99 | 0.020 | 9.85 | 9.63 |
| CB-E4SW | DMH-E4 | 9.0 | 0.176 | 5.300 | 0.94 | 5.18 | 5.01 | 9.50 | 9.31 | 0.021 | 9.91 | 9.62 |
| DMH-E4 | DMH-E5 | 122.0 | 0.617 | 4.838 | 3.01 | 10.50 | 1.70 | 6.69 | 5.47 | 0.010 | 9.50 | 9.39 |
| DMH-E10 | DMH-E5 | 36.0 | 0.490 | 5.300 | 2.62 | 22.62 | 0.83 | 5.33 | 4.97 | 0.010 | 9.39 | 9.39 |
| CB-E8NE | DMH-E8 | 10.0 | 0.075 | 5.300 | 0.40 | 5.04 | 0.51 | 8.90 | 8.70 | 0.020 | 10.44 | 10.44 |
| DMH-E8 | DMH-E9 | 114.0 | 0.695 | 5.244 | 3.67 | 6.46 | 2.99 | 8.45 | 7.31 | 0.010 | 10.41 | 10.04 |
| CB-E9NE | DMH-E9 | 10.0 | 0.097 | 5.300 | 0.52 | 5.04 | 0.66 | 8.90 | 8.70 | 0.020 | 10.04 | 10.04 |
| DMH-E9 | DMH-E5 | 118.0 | 1.390 | 5.136 | 7.20 | 10.50 | 4.07 | 7.06 | 5.88 | 0.010 | 9.96 | 9.39 |
| DMH-E5 | DMH-E6 | 104.0 | 2.819 | 4.635 | 13.17 | 22.62 | 4.19 | 4.97 | 3.93 | 0.010 | 9.15 | 8.72 |
| DMH-E6 | DMH-E7 | 56.0 | 3.313 | 4.565 | 15.25 | 22.62 | 4.85 | 3.93 | 3.37 | 0.010 | 7.89 | 7.58 |
| DMH-E7 | DMH-G11 | 41.0 | 3.313 | 4.532 | 15.14 | 31.99 | 4.82 | 2.28 | 1.46 | 0.020 | 7.36 | 7.14 |
| DMH-G11 | DMH-G10 | 10.0 | 5.921 | 3.464 | 20.68 | 66.13 | 4.21 | 0.62 | 0.36 | 0.026 | 6.85 | 6.82 |
| DMH-G10 | DMH-G9 | 18.0 | 5.921 | 3.462 | 20.66 | 41.01 | 4.21 | 0.36 | 0.18 | 0.010 | 6.72 | 6.68 |
| DMH-G9 | MH-75 | 128.0 | 49.794 | 1.662 | 83.40 | 0.00 | 3.60 | -12.15 | -12.15 | 0.000 | 6.68 | 6.44 |
| MH-75 | DMH-110 | 82.0 | 49.794 | 1.645 | 82.56 | 405.01 | 3.57 | -3.16 | -3.91 | 0.009 | 6.25 | 6.10 |
| DMH-110 | DMH-111 | 211.0 | 49.794 | 1.634 | 82.02 | 260.76 | 3.55 | -3.91 | -4.71 | 0.004 | 5.88 | 5.50 |
| DMH-111 | O-1 | 67.0 | 49.794 | 1.606 | 80.61 | 258.68 | 3.50 | -4.71 | -4.96 | 0.004 | 5.32 | 5.20 |
| CB-2 | DMH-3 | 20.0 | 0.223 | 5.300 | 1.19 | 3.90 | 4.36 | 7.72 | 7.48 | 0.012 | 8.18 | 7.86 |
| CB-1 | DMH-3 | 72.0 | 0.203 | 5.300 | 1.09 | 3.09 | 3.58 | 7.55 | 7.01 | 0.008 | 7.99 | 7.79 |
| DMH-3 | DMH-4 | 57.0 | 0.426 | 5.243 | 2.25 | 10.13 | 4.61 | 6.91 | 6.38 | 0.009 | 7.48 | 7.05 |
| DMH-4 | O-2 | 218.0 | 0.426 | 5.208 | 2.24 | 10.98 | 4.88 | 6.38 | 4.00 | 0.011 | 6.94 | 4.85 |

C:\Users\rmathews\Documents\0851805 AmPUD 2014-May.stc

Scenario: 25-year with tailwater
Current Time Step: 0.000Hr
Conduit FlexTable: Combined Pipe/Node Report

| Start Node | Stop Node | Length (Unified) (ft) | System CA (acres) | System Intensity (in/h) | System Rational Flow (ft ³ /s) | Capacity (Full Flow) (ft ³ /s) | Velocity (Average) (ft/s) | Invert (Upstream) (ft) | Invert (Downstream) (ft) | Slope (ft/ft) | Hydraulic Grade Line (In) (ft) | Hydraulic Grade Line (Out) (ft) |
|------------|-----------|-----------------------|-------------------|-------------------------|---|---|---------------------------|------------------------|--------------------------|---------------|--------------------------------|---------------------------------|
| CB-G6N | DMH-G6 | 14.0 | 0.118 | 6.000 | 0.71 | 5.04 | 0.91 | 7.50 | 7.22 | 0.020 | 10.16 | 10.15 |
| CB-G4E | DMH-G4 | 9.0 | 0.273 | 6.000 | 1.65 | 5.04 | 2.10 | 7.00 | 6.82 | 0.020 | 10.17 | 10.15 |
| DCB-G2E | DMH-G2 | 12.0 | 0.232 | 6.000 | 1.40 | 5.14 | 1.78 | 5.00 | 4.75 | 0.021 | 9.52 | 9.50 |
| CB-G1E | DMH-G1 | 43.0 | 0.179 | 6.000 | 1.08 | 3.56 | 1.38 | 4.00 | 3.57 | 0.010 | 9.44 | 9.40 |
| CB-G1NE | DMH-G1 | 56.0 | 0.098 | 6.000 | 0.59 | 3.56 | 0.76 | 4.00 | 3.44 | 0.010 | 9.42 | 9.40 |
| DMH-G1 | DMH-G2 | 45.0 | 0.277 | 5.778 | 1.61 | 77.20 | 0.13 | 2.90 | 2.77 | 0.003 | 9.50 | 9.50 |
| DMH-G2 | DMH-G3 | 42.0 | 0.509 | 4.726 | 2.42 | 79.91 | 0.19 | 2.77 | 2.64 | 0.003 | 10.15 | 10.15 |
| DMH-G3 | DMH-G4 | 155.0 | 0.509 | 4.144 | 2.13 | 79.09 | 0.17 | 2.64 | 2.17 | 0.003 | 10.15 | 10.15 |
| DMH-G4 | DMH-G5 | 203.0 | 0.782 | 2.971 | 2.34 | 62.14 | 0.19 | 2.17 | 1.79 | 0.002 | 10.15 | 10.15 |
| RG-G1 | DMH-G5 | 65.0 | 0.000 | 6.000 | 0.00 | 8.13 | 7.08 | 5.32 | 4.29 | 0.016 | 11.34 | 10.16 |
| DMH-G5 | DMH-G6 | 118.0 | 0.782 | 2.426 | 1.91 | 137.41 | 0.84 | 1.79 | 0.71 | 0.009 | 10.15 | 10.14 |
| DMH-G6 | DMH-G7 | 38.0 | 1.015 | 2.356 | 2.41 | 80.72 | 0.88 | -0.73 | -0.85 | 0.003 | 10.14 | 10.14 |
| DMH-G7 | DMH-G8 | 11.0 | 1.015 | 2.334 | 2.39 | 212.16 | 0.88 | -0.85 | -1.09 | 0.022 | 9.53 | 9.53 |
| DMH-G8 | DMH-G9 | 70.0 | 1.015 | 2.328 | 2.38 | 78.67 | 0.88 | -1.09 | -1.30 | 0.003 | 9.53 | 9.52 |
| CB-F7NE | DMH-F7 | 12.0 | 0.219 | 6.000 | 1.32 | 5.24 | 1.69 | 9.00 | 8.74 | 0.022 | 10.65 | 10.63 |
| CB-F7NW | DMH-F7 | 13.0 | 0.000 | 6.000 | 0.00 | 5.04 | 0.00 | 9.00 | 8.74 | 0.020 | 10.64 | 10.64 |
| CB-F6NE | DMH-F6 | 12.0 | 0.195 | 6.000 | 1.18 | 5.24 | 1.50 | 9.00 | 8.74 | 0.022 | 11.17 | 11.16 |
| CB-F6NW | DMH-F6 | 13.0 | 0.000 | 6.000 | 0.00 | 5.04 | 0.00 | 9.00 | 8.74 | 0.020 | 11.17 | 11.17 |
| CB-F5NW | DMH-F5 | 13.0 | 0.000 | 6.000 | 0.00 | 5.04 | 0.00 | 9.00 | 8.74 | 0.020 | 11.59 | 11.59 |
| CB-F5NE | DMH-F5 | 13.0 | 0.212 | 6.000 | 1.28 | 5.04 | 1.63 | 9.00 | 8.74 | 0.020 | 11.60 | 11.58 |
| CB-F4NW | DMH-F4 | 13.0 | 0.121 | 6.000 | 0.73 | 3.56 | 0.93 | 9.00 | 8.87 | 0.010 | 11.76 | 11.75 |
| CB-F4NE | DMH-F4 | 12.0 | 0.123 | 6.000 | 0.74 | 3.71 | 0.94 | 9.00 | 8.87 | 0.011 | 11.76 | 11.75 |
| CB-F3NE | DMH-F3 | 10.0 | 0.240 | 6.000 | 1.45 | 5.04 | 1.85 | 8.50 | 8.30 | 0.020 | 12.48 | 12.46 |
| CB-F1NE | DMH-F1 | 9.0 | 0.083 | 6.000 | 0.50 | 3.76 | 0.64 | 9.90 | 9.80 | 0.011 | 12.56 | 12.56 |
| DMH-F1 | DMH-F2 | 78.0 | 0.514 | 5.958 | 3.08 | 6.83 | 1.75 | 8.30 | 7.97 | 0.004 | 12.51 | 12.44 |
| DCB-F2E | DMH-F2 | 77.0 | 0.404 | 6.000 | 2.44 | 5.10 | 1.99 | 8.70 | 8.22 | 0.006 | 12.60 | 12.49 |
| DMH-F2 | DMH-F3 | 36.0 | 0.917 | 5.824 | 5.38 | 12.50 | 1.71 | 7.47 | 7.36 | 0.003 | 12.42 | 12.40 |
| DMH-F3 | DMH-C5 | 129.0 | 1.157 | 5.761 | 6.72 | 12.44 | 2.14 | 7.36 | 6.97 | 0.003 | 12.39 | 12.28 |
| CB-C4SW | DMH-C4 | 12.0 | 0.075 | 6.000 | 0.46 | 5.04 | 0.58 | 9.10 | 8.86 | 0.020 | 12.41 | 12.40 |
| CB-C4NW | DMH-C4 | 12.0 | 0.050 | 6.000 | 0.30 | 5.04 | 0.39 | 9.10 | 8.86 | 0.020 | 12.41 | 12.41 |
| CB-C3SW | DMH-C3 | 12.0 | 0.028 | 6.000 | 0.17 | 11.12 | 0.22 | 9.60 | 8.43 | 0.098 | 12.32 | 12.32 |
| CB-C3NW | DMH-C3 | 12.0 | 0.025 | 6.000 | 0.15 | 11.12 | 0.19 | 9.60 | 8.43 | 0.098 | 12.32 | 12.32 |
| DMH-C3 | DMH-C4 | 40.0 | 0.141 | 5.812 | 0.83 | 10.37 | 0.47 | 8.43 | 8.04 | 0.010 | 12.32 | 12.32 |
| DMH-C4 | DMH-C5 | 57.0 | 0.733 | 5.566 | 4.10 | 10.50 | 2.32 | 8.04 | 7.47 | 0.010 | 12.30 | 12.21 |
| DMH-C5 | DMH-C6 | 33.0 | 1.890 | 5.483 | 10.45 | 12.45 | 3.33 | 6.97 | 6.87 | 0.003 | 12.15 | 12.08 |
| CB-C7SE | DMH-C7 | 14.0 | 0.106 | 6.000 | 0.64 | 5.04 | 0.81 | 9.20 | 8.92 | 0.020 | 12.68 | 12.67 |
| CB-C7NE | DMH-C7 | 14.0 | 0.117 | 6.000 | 0.71 | 5.13 | 0.90 | 9.20 | 8.91 | 0.021 | 12.68 | 12.68 |
| CB-C8SE | DMH-C8 | 14.0 | 0.146 | 6.000 | 0.88 | 5.04 | 1.12 | 10.70 | 10.42 | 0.020 | 13.61 | 13.60 |
| CB-C8NE | DMH-C8 | 14.0 | 0.082 | 6.000 | 0.50 | 5.04 | 0.63 | 10.70 | 10.42 | 0.020 | 13.60 | 13.60 |
| DMH-C8 | DMH-C7 | 178.0 | 1.598 | 5.934 | 9.56 | 6.82 | 5.41 | 8.51 | 7.76 | 0.004 | 13.93 | 12.46 |
| DMH-C7 | DMH-C6 | 92.0 | 2.175 | 5.835 | 12.79 | 14.73 | 4.07 | 7.26 | 6.87 | 0.004 | 12.41 | 12.12 |
| DMH-C6 | DMH-F4 | 116.0 | 4.183 | 5.453 | 22.99 | 22.85 | 4.68 | 6.37 | 6.01 | 0.003 | 11.93 | 11.57 |
| DMH-F4 | DMH-F5 | 122.0 | 4.789 | 5.379 | 25.97 | 34.16 | 3.67 | 5.51 | 5.19 | 0.003 | 11.55 | 11.36 |
| DMH-F5 | DMH-D5 | 108.0 | 5.332 | 5.279 | 28.37 | 38.51 | 4.01 | 5.19 | 4.83 | 0.003 | 11.34 | 11.14 |
| CB-D4NW | DMH-D4 | 12.0 | 0.112 | 6.000 | 0.68 | 3.56 | 0.86 | 10.30 | 10.18 | 0.010 | 11.73 | 11.73 |
| CB-D4SW | DMH-D4 | 13.0 | 0.117 | 6.000 | 0.71 | 3.42 | 0.90 | 10.30 | 10.18 | 0.009 | 11.73 | 11.73 |
| DMH-D4 | DMH-D5 | 90.0 | 0.452 | 5.957 | 2.71 | 10.50 | 1.54 | 8.34 | 7.44 | 0.010 | 11.69 | 11.63 |
| DCB-D6S | DMH-D6 | 12.0 | 0.434 | 6.000 | 2.62 | 5.04 | 4.73 | 8.80 | 8.56 | 0.020 | 13.23 | 13.10 |
| CB-D7E | DMH-D7 | 54.0 | 0.133 | 6.000 | 0.81 | 5.18 | 1.03 | 8.83 | 7.69 | 0.021 | 13.43 | 13.40 |
| DMH-D7 | DMH-D6 | 53.0 | 0.995 | 5.842 | 5.86 | 7.90 | 3.31 | 7.69 | 7.39 | 0.006 | 13.26 | 13.10 |
| DMH-D6 | DMH-D5 | 179.0 | 1.428 | 5.794 | 8.34 | 8.08 | 5.34 | 7.39 | 6.33 | 0.006 | 13.07 | 11.63 |
| DMH-D5 | DMH-F6 | 123.0 | 7.212 | 5.198 | 37.79 | 36.58 | 5.50 | 4.83 | 4.46 | 0.003 | 11.09 | 10.67 |
| DMH-F6 | DMH-F7 | 122.0 | 7.870 | 5.131 | 40.71 | 36.73 | 5.91 | 4.46 | 4.09 | 0.003 | 10.62 | 10.14 |
| DMH-F7 | DMH-F8 | 23.0 | 8.089 | 5.069 | 41.33 | 43.98 | 6.00 | 4.09 | 3.99 | 0.004 | 10.08 | 9.99 |
| DMH-F8 | DMH-F9 | 10.0 | 8.089 | 5.058 | 41.24 | 94.32 | 5.99 | 3.99 | 3.79 | 0.020 | 9.17 | 9.13 |
| DMH-F9 | DMH-F10 | 79.0 | 8.089 | 5.053 | 41.20 | 36.76 | 5.98 | 3.79 | 3.55 | 0.003 | 9.07 | 8.75 |
| CB-E2SE | DMH-E2 | 8.0 | 0.195 | 6.000 | 1.18 | 5.19 | 1.50 | 7.80 | 7.63 | 0.021 | 9.43 | 9.42 |
| CB-E2NE | DMH-E2 | 49.0 | 0.154 | 6.000 | 0.93 | 3.56 | 1.18 | 7.80 | 7.31 | 0.010 | 9.44 | 9.41 |
| DMH-E2 | DMH-E1 | 33.0 | 0.348 | 5.876 | 2.06 | 3.56 | 2.63 | 7.31 | 6.98 | 0.010 | 9.33 | 9.22 |
| DMH-E1 | MH-68 | 9.0 | 0.348 | 5.838 | 2.05 | 3.36 | 2.61 | 5.56 | 5.48 | 0.009 | 9.07 | 9.04 |
| CB-21 | DMH-22 | 5.0 | 0.496 | 6.000 | 3.00 | 4.51 | 3.82 | 6.82 | 6.74 | 0.016 | 10.17 | 10.14 |
| CB-20 | DMH-22 | 49.0 | 0.428 | 6.000 | 2.59 | 3.53 | 3.30 | 6.82 | 6.34 | 0.010 | 10.47 | 10.21 |
| CB-18 | DMH-19 | 6.0 | 0.140 | 6.000 | 0.85 | 5.44 | 1.08 | 8.74 | 8.60 | 0.023 | 10.70 | 10.69 |
| CB-17 | DMH-19 | 49.0 | 0.141 | 6.000 | 0.85 | 3.60 | 1.08 | 8.74 | 8.24 | 0.010 | 10.82 | 10.79 |
| CB-11 | DMH-12 | 5.0 | 0.530 | 6.000 | 3.20 | 3.90 | 4.08 | 6.66 | 6.60 | 0.012 | 10.96 | 10.92 |
| CB-10 | DMH-12 | 49.0 | 0.419 | 6.000 | 2.53 | 3.56 | 3.23 | 6.66 | 6.17 | 0.010 | 11.17 | 10.92 |
| CB-A6SE | DMH-A6 | 14.0 | 0.367 | 6.000 | 2.22 | 3.56 | 2.82 | 8.08 | 7.94 | 0.010 | 11.45 | 11.40 |
| CB-A6N | DMH-A6 | 15.0 | 0.169 | 6.000 | 1.02 | 3.56 | 1.30 | 8.09 | 7.94 | 0.010 | 11.41 | 11.40 |
| DMH-A6 | DMH-A5 | 93.0 | 0.777 | 5.965 | 4.67 | 5.76 | 2.64 | 7.94 | 7.66 | 0.003 | 12.40 | 12.22 |
| DMH-A5 | DMH-A4 | 126.0 | 0.777 | 5.860 | 4.59 | 5.77 | 2.60 | 7.66 | 7.28 | 0.003 | 12.16 | 11.92 |
| CB-A4S | DMH-A4 | 14.0 | 0.041 | 6.000 | 0.25 | 5.04 | 0.32 | 10.00 | 9.72 | 0.020 | 11.94 | 11.94 |
| CB-A4N | DMH-A4 | 14.0 | 0.053 | 6.000 | 0.32 | 5.13 | 0.41 | 10.00 | 9.71 | 0.021 | 11.95 | 11.95 |
| DMH-A4 | DMH-A3 | 178.0 | 0.871 | 5.714 | 5.02 | 12.34 | 1.60 | 7.28 | 6.75 | 0.003 | 11.91 | 11.82 |
| DMH-A3 | DMH-A2 | 42.0 | 1.360 | 5.380 | 7.38 | 12.59 | 2.35 | 6.75 | 6.62 | 0.003 | 11.74 | 11.70 |
| CB-A1S | DMH-A2 | 15.0 | 0.159 | 6.000 | 0.96 | 4.69 | 1.22 | 7.50 | 7.24 | 0.017 | 11.71 | 11.70 |
| CB-A1N | DMH-A2 | 13.0 | 0.089 | 6.000 | 0.54 | 5.93 | 0.69 | 7.60 | 7.24 | 0.028 | 11.70 | 11.70 |
| DMH-A2 | DMH-A1 | 23.0 | 1.642 | 5.326 | 8.82 | 14.92 | 2.81 | 6.62 | 6.52 | 0.004 | 11.83 | 11.80 |
| DMH-A1 | DMH-8 | 93.0 | 1.642 | 5.302 | 8.78 | 12.19 | 2.79 | 6.49 | 6.22 | 0.003 | 11.78 | 11.64 |
| CB-8B | DMH-8 | 22.0 | 0.058 | 6.000 | 0.35 | 3.13 | 0.44 | 8.45 | 8.28 | 0.008 | 11.59 | 11.58 |
| CB-8C | DMH-8 | 61.0 | 0.151 | 6.000 | 0.91 | 3.41 | 1.16 | 8.20 | 7.64 | 0.009 | 11.68 | 11.64 |
| CB-8A | DMH-8 | 65.0 | 0.229 | 6.000 | 1.38 | 2.42 | 1.76 | 8.29 | 7.99 | 0.005 | 11.68 | 11.58 |
| DMH-8 | DMH-9 | 83.0 | 2.079 | 5.202 | 10.90 | 11.10 | 3.47 | 6.22 | 6.02 | 0.002 | 11.39 | 11.19 |
| DMH-9 | DMH-12 | 97.0 | 2.079 | 5.130 | 10.75 | 11.25 | 3.42 | 6.00 | 5.76 | 0.002 | 11.14 | 10.92 |
| DMH-12 | DMH-13 | 242.0 | 3.028 | 5.045 | 15.40 | 20.93 | 3.14 | 5.26 | 4.63 | 0.003 | 12.08 | 11.74 |
| CB-C1N | DMH-C1 | 24.0 | 0.064 | 6.000 | 0.39 | 5.04 | 0.49 | 10.00 | 9.52 | 0.020 | 13.30 | 13.30 |
| CB-C1SE | DMH-C1 | 17.0 | 0.056 | 6.000 | 0.34 | 4.96 | 0.43 | 10.00 | 9.67 | 0.019 | 13.30 | 13.30 |
| CB-C2NE | DMH-C2 | 23.0 | 0.071 | 6.000 | 0.43 | 5.04 | 0.55 | 8.80 | 8.34 | 0.020 | 13.20 | 13.20 |
| CB-C2SE | DMH-C2 | 13.0 | 0.073 | 6.000 | 0.44 | 5.04 | 0.57 | 8.90 | 8.64 | 0.020 | 13.20 | 13.20 |
| DMH-C2 | DMH-C1 | 77.0 | 1.629 | 5.874 | 9.65 | 10.50 | 5.46 | 7.63 | 6.86 | 0.010 | 13.95 | 13.30 |
| DMH-C1 | DMH-13 | 123.0 | 1.749 | 5.832 | 10.28 | 10.50 | 5.82 | 6.86 | 5.63 | 0.010 | 13.35 | 12.17 |
| DMH-13 | DMH-16 | 64.0 | 4.777 | 4.814 | 23.18 | 21.14 | 4.72 | 4.63 | 4.46 | 0.003 | 11.67 | 11.47 |
| CB-14 | DMH-16 | 49.0 | 0.081 | 6.000 | 0.49 | 3.60 | 0.62 | 9.21 | 8.71 | 0.010 | 11.92 | 11.92 |

| | | | | | | | | | | | | |
|-------------------|---------|-------|--------|-------|-------|--------|------|-------|-------|--------|-------|-------|
| CB-15 | DMH-16 | 12.0 | 0.078 | 6.000 | 0.47 | 2.30 | 0.60 | 9.19 | 9.14 | 0.004 | 11.80 | 11.80 |
| DMH-16 | DMH-19 | 240.0 | 4.936 | 4.773 | 23.75 | 20.85 | 4.84 | 4.46 | 3.84 | 0.003 | 11.40 | 10.59 |
| DMH-19 | DMH-D1 | 42.0 | 5.217 | 4.624 | 24.32 | 33.91 | 3.44 | 3.34 | 3.23 | 0.003 | 10.57 | 10.51 |
| DMH-D3 | DMH-D2 | 46.0 | 1.280 | 6.000 | 7.74 | 7.74 | 4.38 | 6.52 | 6.27 | 0.005 | 12.05 | 11.80 |
| CB-D2S | DMH-D2 | 29.0 | 0.214 | 6.000 | 1.30 | 3.17 | 3.46 | 7.00 | 6.77 | 0.008 | 11.97 | 11.80 |
| DMH-D2 | DMH-D1 | 104.0 | 1.808 | 5.968 | 10.88 | 11.52 | 6.96 | 5.77 | 4.52 | 0.012 | 12.33 | 10.91 |
| DMH-D1 | DMH-22 | 194.0 | 7.024 | 4.588 | 32.48 | 33.91 | 4.80 | 3.23 | 2.73 | 0.003 | 10.47 | 9.96 |
| DMH-22 | DMH-23 | 122.0 | 7.948 | 4.466 | 35.78 | 51.52 | 3.87 | 2.23 | 1.91 | 0.003 | 9.94 | 9.77 |
| DMH-23 | DMH-24 | 11.0 | 7.948 | 4.372 | 35.02 | 95.92 | 3.79 | 1.86 | 1.76 | 0.009 | 9.26 | 9.25 |
| DMH-24 | DMH-105 | 30.0 | 7.948 | 4.363 | 34.96 | 91.84 | 3.78 | 1.71 | 1.46 | 0.008 | 9.22 | 9.18 |
| CB-30 | DMH-31 | 47.0 | 0.320 | 6.000 | 1.94 | 3.52 | 2.47 | 7.41 | 6.95 | 0.010 | 9.59 | 9.45 |
| CB-32O | DMH-32M | 54.0 | 0.000 | 6.000 | 0.00 | 3.43 | 0.00 | 4.00 | 3.50 | 0.009 | 11.09 | 11.09 |
| CB-32R | DMH-32P | 37.0 | 0.386 | 6.000 | 2.34 | 3.31 | 2.97 | 7.64 | 7.32 | 0.009 | 11.85 | 11.69 |
| CB-32Q | DMH-32P | 22.0 | 0.288 | 6.000 | 1.74 | 2.94 | 2.22 | 7.48 | 7.33 | 0.007 | 11.71 | 11.66 |
| DMH-32P | DMH-32M | 53.0 | 1.266 | 5.963 | 7.61 | 10.99 | 4.31 | 3.02 | 2.44 | 0.011 | 11.37 | 11.09 |
| CB-32N | DMH-32M | 12.0 | 0.313 | 6.000 | 1.89 | 2.91 | 2.41 | 6.88 | 6.80 | 0.007 | 11.12 | 11.09 |
| CB-F15 | DMH-F13 | 17.0 | 0.146 | 6.000 | 0.88 | 5.04 | 1.12 | 7.10 | 6.76 | 0.020 | 11.31 | 11.30 |
| CB-F14 | DMH-F13 | 16.0 | 0.206 | 6.000 | 1.25 | 5.19 | 1.59 | 7.10 | 6.76 | 0.021 | 11.32 | 11.30 |
| CB-F13 | DMH-F12 | 10.0 | 0.000 | 6.000 | 0.00 | 5.04 | 0.00 | 9.30 | 9.10 | 0.020 | 12.12 | 12.12 |
| CB-F12 | DMH-F11 | 12.0 | 0.145 | 6.000 | 0.88 | 5.04 | 1.12 | 9.30 | 9.06 | 0.020 | 11.64 | 11.63 |
| DMH-F11 | DMH-F12 | 128.0 | 0.145 | 5.968 | 0.87 | 10.50 | 0.49 | 7.19 | 5.91 | 0.010 | 11.63 | 11.62 |
| DMH-F12 | DMH-F13 | 140.0 | 0.915 | 5.189 | 4.79 | 10.50 | 2.71 | 5.91 | 4.51 | 0.010 | 11.59 | 11.30 |
| DMH-F13 | DMH-32T | 76.0 | 1.267 | 5.034 | 6.43 | 10.29 | 3.64 | 4.51 | 3.78 | 0.010 | 11.67 | 11.39 |
| CB-32Z | DMH-32Y | 31.0 | 0.000 | 6.000 | 0.00 | 2.56 | 5.87 | 3.86 | 3.70 | 0.005 | 11.62 | 11.10 |
| DMH-32Y | DMH-32U | 47.0 | 0.000 | 5.984 | 0.00 | 6.85 | 2.61 | 3.69 | 3.49 | 0.004 | 10.76 | 10.67 |
| CB-32V | DMH-32U | 27.0 | 0.255 | 6.000 | 1.54 | 3.22 | 1.97 | 6.59 | 6.37 | 0.008 | 10.72 | 10.67 |
| CB-32W | DMH-32U | 18.0 | 0.212 | 6.000 | 1.28 | 3.03 | 1.64 | 6.39 | 6.26 | 0.007 | 10.69 | 10.67 |
| CB-32X | DMH-32U | 38.0 | 0.217 | 6.000 | 1.31 | 3.32 | 1.67 | 6.29 | 5.96 | 0.009 | 10.72 | 10.67 |
| DMH-32U | DMH-32T | 119.0 | 1.083 | 5.930 | 6.47 | 6.88 | 6.27 | 3.39 | 2.88 | 0.004 | 12.62 | 11.29 |
| DMH-32T | DMH-32S | 171.0 | 2.350 | 4.971 | 11.78 | 21.96 | 3.34 | 2.78 | 2.29 | 0.003 | 11.11 | 10.84 |
| DMH-32S | DMH-32M | 277.0 | 2.350 | 4.818 | 11.41 | 22.45 | 3.26 | 2.27 | 1.44 | 0.003 | 10.66 | 10.24 |
| DMH-32M | DMH-32L | 24.0 | 3.930 | 4.563 | 18.07 | 22.15 | 4.62 | 1.42 | 1.35 | 0.003 | 10.04 | 9.97 |
| DMH-32L | DMH-32K | 9.0 | 3.930 | 4.547 | 18.01 | 43.23 | 4.61 | 1.30 | 1.20 | 0.011 | 9.55 | 9.52 |
| DMH-32K | DMH-32 | 17.0 | 3.930 | 4.542 | 17.99 | 24.37 | 4.60 | 1.15 | 1.09 | 0.004 | 9.46 | 9.40 |
| CB-34N | CB-34M | 32.0 | 0.206 | 6.000 | 1.25 | 10.24 | 0.71 | 6.81 | 6.63 | 0.006 | 10.76 | 10.75 |
| CB-34M | CB-34L | 40.0 | 0.415 | 5.864 | 2.45 | 10.35 | 1.39 | 6.63 | 6.40 | 0.006 | 10.75 | 10.74 |
| CB-34L | CB-34K | 93.0 | 0.633 | 5.777 | 3.69 | 10.41 | 2.09 | 6.40 | 5.86 | 0.006 | 10.74 | 10.67 |
| CB-34K | CB-34J | 25.0 | 0.880 | 5.644 | 5.01 | 10.22 | 2.83 | 5.86 | 5.72 | 0.006 | 10.67 | 10.64 |
| CB-34J | CB-34I | 51.0 | 1.114 | 5.617 | 6.31 | 10.12 | 3.57 | 5.72 | 5.44 | 0.005 | 10.64 | 10.53 |
| CB-34I | CB-34H | 48.0 | 1.330 | 5.574 | 7.47 | 22.46 | 2.38 | 5.44 | 5.16 | 0.006 | 10.53 | 10.50 |
| CB-34H | CB-34G | 41.0 | 1.560 | 5.514 | 8.67 | 22.03 | 2.76 | 5.16 | 4.93 | 0.006 | 10.54 | 10.50 |
| CB-34G | CB-34F | 41.0 | 1.776 | 5.469 | 9.79 | 22.50 | 3.12 | 4.93 | 4.69 | 0.006 | 10.95 | 10.91 |
| CB-34F | CB-34E | 42.0 | 1.983 | 5.430 | 10.85 | 22.23 | 3.45 | 4.69 | 4.45 | 0.006 | 10.91 | 10.85 |
| CB-34E | CB-34D | 41.0 | 2.190 | 5.393 | 11.91 | 22.03 | 3.79 | 4.45 | 4.22 | 0.006 | 10.85 | 10.78 |
| CB-34D | CB-34C | 41.0 | 2.418 | 5.361 | 13.07 | 22.50 | 4.16 | 4.22 | 3.98 | 0.006 | 10.78 | 10.70 |
| CB-34C | DMH-34A | 18.0 | 2.641 | 5.331 | 14.19 | 19.61 | 4.52 | 3.98 | 3.90 | 0.004 | 10.71 | 10.67 |
| CB-34B | DMH-34A | 32.0 | 0.043 | 6.000 | 0.26 | 3.73 | 0.33 | 4.90 | 4.55 | 0.011 | 10.67 | 10.67 |
| DMH-34A | DMH-34 | 67.0 | 2.683 | 5.319 | 14.39 | 23.12 | 4.58 | 3.90 | 3.20 | 0.010 | 10.83 | 10.56 |
| CB-39D | CB-39C | 70.0 | 0.152 | 6.000 | 0.92 | 3.56 | 1.17 | 6.00 | 5.30 | 0.010 | 9.56 | 9.51 |
| CB-39C | DMH-39A | 23.0 | 0.152 | 5.820 | 0.89 | 5.75 | 1.13 | 5.30 | 4.70 | 0.026 | 9.51 | 9.50 |
| CB-39B | DMH-39A | 16.0 | 0.258 | 6.000 | 1.56 | 3.56 | 1.98 | 5.11 | 4.95 | 0.010 | 9.53 | 9.50 |
| DMH-39A | DMH-38 | 50.0 | 0.409 | 5.759 | 2.38 | 6.13 | 1.94 | 4.70 | 4.25 | 0.009 | 9.78 | 9.71 |
| CB-38A | DMH-38 | 35.0 | 0.000 | 4.030 | 0.00 | 7.94 | 8.65 | 3.40 | 3.20 | 0.006 | 10.45 | 9.71 |
| CB-40A | DMH-41 | 12.0 | 0.214 | 6.000 | 1.30 | 2.72 | 1.65 | 5.57 | 5.50 | 0.006 | 9.51 | 9.49 |
| CB-43 | DMH-44 | 26.0 | 0.124 | 6.000 | 0.75 | 1.56 | 0.95 | 6.16 | 6.11 | 0.002 | 9.65 | 9.64 |
| CB-42 | DMH-44 | 19.0 | 0.220 | 6.000 | 1.33 | 4.90 | 1.69 | 6.15 | 5.79 | 0.019 | 9.69 | 9.67 |
| CB-45A | DMH-45 | 35.0 | 0.185 | 6.000 | 1.12 | 3.56 | 1.43 | 7.12 | 6.77 | 0.010 | 10.67 | 10.64 |
| CB-46B | DMH-46A | 45.0 | 0.146 | 6.000 | 0.88 | 2.19 | 1.62 | 7.75 | 7.30 | 0.010 | 11.38 | 11.31 |
| CB-46E | DMH-46C | 7.0 | 0.439 | 6.000 | 2.65 | -2.50 | 7.60 | 10.60 | 10.90 | -0.043 | 13.52 | 13.19 |
| CB-46D | DMH-46C | 40.0 | 0.168 | 6.000 | 1.01 | -1.05 | 2.90 | 10.60 | 10.90 | -0.008 | 13.46 | 13.18 |
| CB-46H | DMH-46F | 8.0 | 0.481 | 6.000 | 2.91 | 1.35 | 8.34 | 14.30 | 14.20 | 0.013 | 15.33 | 14.86 |
| CB-46G | DMH-46F | 39.0 | 0.138 | 6.000 | 0.84 | -1.37 | 2.39 | 13.70 | 14.20 | -0.013 | 14.92 | 14.65 |
| CB-46M | CB-46L | 58.0 | 0.111 | 6.000 | 0.67 | 1.23 | 3.60 | 16.60 | 16.00 | 0.010 | 16.99 | 16.57 |
| CB-46L | DMH-46K | 46.0 | 0.216 | 5.952 | 1.30 | 1.26 | 4.10 | 16.00 | 15.50 | 0.011 | 16.57 | 16.04 |
| CB-46Q | DMH-46N | 7.0 | 0.086 | 6.000 | 0.52 | 4.86 | 4.03 | 17.20 | 17.07 | 0.019 | 17.53 | 17.57 |
| CB-46O | DMH-46N | 23.0 | 0.099 | 6.000 | 0.80 | 1.38 | 3.82 | 17.37 | 17.07 | 0.013 | 17.73 | 17.56 |
| CB-46P | DMH-46N | 22.0 | 0.073 | 6.000 | 0.44 | 1.24 | 3.24 | 17.30 | 17.07 | 0.010 | 17.61 | 17.56 |
| DMH-46N | DMH-46K | 137.0 | 0.258 | 5.980 | 1.55 | 13.52 | 5.09 | 17.07 | 14.80 | 0.017 | 17.54 | 15.47 |
| DMH-46K | DMH-46J | 37.0 | 0.474 | 5.899 | 2.82 | 13.38 | 6.00 | 14.80 | 14.20 | 0.016 | 15.44 | 14.94 |
| DMH-46J | DMH-46I | 12.0 | 0.474 | 5.880 | 2.81 | 13.56 | 6.05 | 14.20 | 14.00 | 0.017 | 14.84 | 14.73 |
| DMH-46I | DMH-46F | 52.0 | 0.474 | 5.875 | 2.81 | 11.28 | 5.30 | 14.00 | 13.40 | 0.012 | 14.64 | 14.43 |
| DMH-46F | DMH-46C | 150.0 | 1.094 | 5.845 | 6.44 | 15.34 | 8.30 | 13.40 | 10.20 | 0.021 | 14.38 | 12.77 |
| DMH-46C | DMH-46A | 149.0 | 1.700 | 5.791 | 9.92 | 14.40 | 5.62 | 10.10 | 7.30 | 0.019 | 12.66 | 11.33 |
| DMH-46A | DMH-45 | 78.0 | 1.846 | 5.711 | 10.63 | 12.47 | 6.01 | 7.30 | 6.20 | 0.014 | 11.16 | 10.37 |
| CB-45B | DMH-45 | 8.0 | 0.169 | 6.000 | 1.02 | 3.31 | 2.93 | 6.80 | 6.20 | 0.005 | 10.44 | 10.38 |
| CB-45C | DMH-45 | 33.0 | 0.188 | 6.000 | 1.14 | -2.63 | 1.45 | 6.85 | 7.03 | -0.005 | 10.67 | 10.64 |
| DMH-45 | DMH-44 | 182.0 | 2.389 | 5.672 | 13.66 | 23.36 | 4.35 | 6.20 | 4.26 | 0.011 | 10.29 | 9.63 |
| DMH-44 | DMH-41 | 186.0 | 2.732 | 5.547 | 15.28 | 46.13 | 2.16 | 4.16 | 3.27 | 0.005 | 9.59 | 9.49 |
| CB-40 | DMH-41 | 3.0 | 0.120 | 6.000 | 0.72 | 5.44 | 0.92 | 5.48 | 5.41 | 0.023 | 9.49 | 9.49 |
| CB-39 | DMH-41 | 38.0 | 0.264 | 6.000 | 1.60 | 3.37 | 2.04 | 5.23 | 4.89 | 0.009 | 9.57 | 9.49 |
| DMH-41 | DMH-38 | 60.0 | 3.330 | 5.289 | 17.75 | 58.08 | 1.85 | 3.22 | 3.02 | 0.003 | 9.73 | 9.71 |
| DMH-38A(Partners) | DMH-38 | 123.0 | 6.562 | 6.000 | 39.69 | 55.92 | 4.12 | 3.40 | 3.02 | 0.003 | 9.90 | 9.71 |
| DMH-38 | DMH-37 | 431.0 | 10.302 | 4.024 | 41.79 | 74.52 | 4.54 | 3.02 | 1.86 | 0.003 | 10.68 | 10.00 |
| CB-36 | DMH-37 | 3.0 | 0.510 | 6.000 | 3.09 | 6.50 | 3.93 | 5.72 | 5.62 | 0.033 | 10.02 | 10.00 |
| CB-35 | DMH-37 | 36.0 | 0.438 | 6.000 | 2.65 | 3.51 | 3.38 | 5.80 | 5.45 | 0.010 | 10.20 | 10.00 |
| DMH-37 | DMH-34 | 101.0 | 11.250 | 3.898 | 44.20 | 74.26 | 4.73 | 1.84 | 1.57 | 0.003 | 10.48 | 10.30 |
| DMH-34 | DMH-33B | 71.0 | 13.934 | 3.869 | 54.35 | 78.12 | 5.54 | 1.56 | 1.35 | 0.003 | 10.23 | 10.07 |
| DMH-33B | DMH-33A | 12.0 | 13.934 | 3.852 | 54.11 | 131.12 | 5.52 | 1.30 | 1.20 | 0.008 | 9.56 | 9.53 |
| DMH-33A | DMH-32 | 24.0 | 13.934 | 3.850 | 54.07 | 77.57 | 5.52 | 1.15 | 1.08 | 0.003 | 9.49 | 9.43 |
| CB-32D | DMH-32B | 39.0 | 0.140 | 6.000 | 0.85 | 3.33 | 1.08 | 6.62 | 6.28 | 0.009 | 9.79 | 9.77 |
| CB-32C | DMH-32B | 21.0 | 0.134 | 6.000 | 0.81 | 3.21 | 1.03 | 6.90 | 6.73 | 0.008 | 9.74 | 9.73 |
| CB-32I | DMH-32H | 17.0 | 0.183 | 6.000 | 1.11 | 1.31 | 3.17 | 6.70 | 6.50 | 0.012 | 9.67 | 9.53 |
| CB-32J | DMH-32H | 48.0 | 0.171 | 6.000 | 1.03 | 1.23 | 2.96 | 6.40 | 5.90 | 0.010 | 9.88 | 9.53 |
| DMH-32H | DMH-32E | 119.0 | 0.353 | 5.951 | 2.12 | 22.14 | 0.67 | 5.90 | 4.76 | 0.010 | 9.52 | 9.51 |
| CB-32G | DMH-32E | 44.0 | 0.088 | 6.000 | 0.53 | 1.21 | 1.52 | 5 | | | | |

| | | | | | | | | | | | | |
|----------|---------|-------|--------|-------|--------|--------|------|--------|--------|--------|-------|-------|
| DMH-28 | DMH-28 | 165.0 | 19.902 | 3.745 | 75.13 | 180.57 | 3.36 | 0.65 | 0.35 | 0.002 | 9.21 | 9.12 |
| CB-27 | DMH-25 | 158.0 | 20.393 | 3.680 | 75.64 | 178.27 | 3.38 | 0.35 | 0.07 | 0.002 | 9.11 | 9.03 |
| CB-26 | DMH-25 | 5.0 | 0.262 | 6.000 | 1.59 | 2.76 | 3.64 | 8.42 | 8.39 | 0.006 | 9.19 | 9.18 |
| DMH-25 | DMH-25 | 48.0 | 0.205 | 6.000 | 1.24 | 3.53 | 4.09 | 8.41 | 7.94 | 0.010 | 9.22 | 9.18 |
| CB-24C | DMH-105 | 61.0 | 20.860 | 3.617 | 76.06 | 179.83 | 3.39 | 0.07 | -0.04 | 0.002 | 9.02 | 8.99 |
| CB-24G | DMH-24B | 34.0 | 0.050 | 6.000 | 0.30 | 3.56 | 0.39 | 5.23 | 4.89 | 0.010 | 9.22 | 9.22 |
| CB-24J | DMH-24E | 41.0 | 0.072 | 6.000 | 0.43 | 4.98 | 0.55 | 5.90 | 5.10 | 0.020 | 9.26 | 9.25 |
| CB-24K | DMH-24I | 9.0 | 0.156 | 6.000 | 0.94 | 1.45 | 2.70 | 5.80 | 5.67 | 0.014 | 9.02 | 8.97 |
| DMH-24I | DMH-24I | 54.0 | 0.183 | 6.000 | 1.10 | 1.87 | 3.16 | 6.70 | 5.41 | 0.024 | 9.42 | 8.97 |
| DMH-24H | DMH-24H | 173.0 | 0.339 | 5.949 | 2.03 | 3.61 | 2.58 | 5.41 | 3.63 | 0.010 | 9.83 | 9.26 |
| DMH-24H | DMH-24E | 23.0 | 0.339 | 5.748 | 1.96 | 5.04 | 2.50 | 3.53 | 3.07 | 0.020 | 9.22 | 9.15 |
| CB-24M | DMH-24L | 18.0 | 0.456 | 6.000 | 2.76 | 6.50 | 3.51 | 3.10 | 2.50 | 0.033 | 9.16 | 9.05 |
| CB-24P | DMH-24N | 23.0 | 0.675 | 6.000 | 4.08 | 5.25 | 5.20 | 4.60 | 4.10 | 0.022 | 8.92 | 8.62 |
| CB-24O | DMH-24N | 21.0 | 0.548 | 6.000 | 3.31 | 7.38 | 4.22 | 5.00 | 4.10 | 0.043 | 8.80 | 8.62 |
| CB-24Q | DMH-24N | 154.0 | 0.071 | 6.000 | 0.43 | 3.63 | 0.55 | 5.60 | 4.00 | 0.010 | 8.64 | 8.62 |
| CB-24S | DMH-24R | 26.0 | 0.171 | 6.000 | 1.03 | 4.42 | 1.31 | 6.60 | 6.20 | 0.015 | 9.39 | 9.37 |
| CB-24T | DMH-24R | 11.0 | 0.775 | 6.000 | 4.69 | -11.77 | 5.97 | 5.40 | 6.60 | -0.109 | 9.56 | 9.37 |
| CB-24U | DMH-24R | 116.0 | 0.161 | 6.000 | 0.97 | 2.96 | 1.24 | 7.10 | 6.30 | 0.007 | 9.46 | 9.37 |
| DMH-24R | DMH-24N | 300.0 | 1.106 | 5.719 | 6.38 | 8.58 | 3.61 | 6.10 | 4.10 | 0.007 | 9.73 | 8.62 |
| DMH-24L | DMH-24L | 294.0 | 2.400 | 5.153 | 12.47 | 16.16 | 3.97 | 4.00 | 2.50 | 0.005 | 9.94 | 9.05 |
| DMH-24L | DMH-24E | 80.0 | 2.856 | 4.931 | 14.20 | 14.96 | 4.52 | 2.50 | 2.15 | 0.004 | 9.54 | 9.23 |
| CB-24F | DMH-24E | 15.0 | 0.136 | 6.000 | 0.82 | 3.05 | 1.05 | 5.73 | 5.62 | 0.007 | 9.26 | 9.25 |
| DMH-24E | DMH-24B | 37.0 | 3.403 | 4.878 | 16.73 | 75.96 | 2.37 | 1.35 | 0.87 | 0.013 | 9.14 | 9.12 |
| CB-24D | DMH-24B | 35.0 | 0.121 | 6.000 | 0.73 | 1.51 | 2.09 | 6.65 | 6.10 | 0.016 | 9.36 | 9.23 |
| DMH-24B | DMH-24A | 47.0 | 3.574 | 4.831 | 17.40 | 63.05 | 2.46 | 0.87 | 0.45 | 0.009 | 9.10 | 9.07 |
| DMH-24A | DMH-105 | 199.0 | 3.574 | 4.773 | 17.20 | 25.90 | 2.43 | 0.30 | 0.00 | 0.002 | 9.05 | 8.92 |
| DMH-105 | MH-68 | 43.0 | 32.382 | 3.593 | 117.29 | 266.27 | 4.90 | -0.04 | -0.21 | 0.004 | 8.82 | 8.77 |
| MH-68 | DMH-107 | 222.0 | 32.731 | 3.581 | 118.16 | 258.94 | 4.93 | -0.21 | -1.04 | 0.004 | 8.72 | 8.48 |
| DMH-107 | DMH-F10 | 172.0 | 34.528 | 3.521 | 122.56 | 256.30 | 5.09 | -1.04 | -1.67 | 0.004 | 8.43 | 8.23 |
| DMH-F10 | DMH-G9 | 374.0 | 42.617 | 3.476 | 149.34 | 267.30 | 6.07 | -1.67 | -3.16 | 0.004 | 8.16 | 7.54 |
| CB-G12SE | DMH-G12 | 13.0 | 0.075 | 6.000 | 0.46 | 5.13 | 0.58 | 8.00 | 7.73 | 0.021 | 12.20 | 12.20 |
| CB-G13SE | DMH-G13 | 13.0 | 0.107 | 6.000 | 0.65 | 5.04 | 0.82 | 7.50 | 7.24 | 0.020 | 11.80 | 11.80 |
| DMH-63B | DMH-G14 | 23.0 | 0.241 | 6.000 | 1.46 | 2.97 | 2.68 | 4.75 | 4.50 | 0.011 | 12.16 | 12.10 |
| CB-G15SE | DMH-G15 | 13.0 | 0.082 | 6.000 | 0.49 | 5.04 | 0.63 | 7.70 | 7.44 | 0.020 | 11.80 | 11.80 |
| MH-74 | DMH-G15 | 10.0 | 1.029 | 4.200 | 4.36 | 4.63 | 0.55 | 4.90 | 4.80 | 0.010 | 11.89 | 11.80 |
| DMH-G15 | DMH-G14 | 24.0 | 1.113 | 4.198 | 4.71 | 9.83 | 2.67 | 4.71 | 4.50 | 0.009 | 12.15 | 12.10 |
| CB-G14SW | DMH-G14 | 17.0 | 0.062 | 6.000 | 0.38 | 5.11 | 0.48 | 7.80 | 7.45 | 0.021 | 12.10 | 12.10 |
| DMH-G14 | DMH-G13 | 167.0 | 1.754 | 4.186 | 7.40 | 9.34 | 4.19 | 4.50 | 3.18 | 0.008 | 12.63 | 11.80 |
| CB-G13SW | DMH-G13 | 13.0 | 0.103 | 6.000 | 0.62 | 4.84 | 0.79 | 7.50 | 7.26 | 0.018 | 11.80 | 11.80 |
| DMH-G13 | DMH-G12 | 149.0 | 2.399 | 4.132 | 9.99 | 20.13 | 3.18 | 2.68 | 1.50 | 0.008 | 12.49 | 12.20 |
| CB-G12SW | DMH-G12 | 13.0 | 0.045 | 6.000 | 0.27 | 5.13 | 0.35 | 8.00 | 7.73 | 0.021 | 12.20 | 12.20 |
| DMH-G12 | DMH-G11 | 47.0 | 2.639 | 4.070 | 10.83 | 20.34 | 3.45 | 1.50 | 1.12 | 0.008 | 13.01 | 12.90 |
| CB-E6SW | DMH-E6 | 9.0 | 0.247 | 6.000 | 1.49 | 3.56 | 1.90 | 8.61 | 8.52 | 0.010 | 12.12 | 12.10 |
| CB-E6NW | DMH-E6 | 26.0 | 0.247 | 6.000 | 1.49 | 3.56 | 1.90 | 8.78 | 8.52 | 0.010 | 12.15 | 12.10 |
| CB-E3SW | DMH-E3 | 12.0 | 0.156 | 6.000 | 0.94 | 3.56 | 1.20 | 9.10 | 8.98 | 0.010 | 13.21 | 13.20 |
| CB-E3NW | DMH-E3 | 26.0 | 0.151 | 6.000 | 0.91 | 3.63 | 1.16 | 10.19 | 9.92 | 0.010 | 13.22 | 13.20 |
| DMH-E3 | DMH-E4 | 140.0 | 0.307 | 5.933 | 1.84 | 10.50 | 1.04 | 8.09 | 6.69 | 0.010 | 13.25 | 13.21 |
| CB-E4NW | DMH-E4 | 26.0 | 0.134 | 6.000 | 0.81 | 4.99 | 1.03 | 9.50 | 8.99 | 0.020 | 13.52 | 13.51 |
| CB-E4SW | DMH-E4 | 9.0 | 0.176 | 6.000 | 1.07 | 5.18 | 1.36 | 9.50 | 9.31 | 0.021 | 13.45 | 13.44 |
| DMH-E4 | DMH-E5 | 122.0 | 0.617 | 5.529 | 3.44 | 10.50 | 1.95 | 6.69 | 5.47 | 0.010 | 13.19 | 13.06 |
| DMH-E10 | DMH-E5 | 36.0 | 0.963 | 6.000 | 5.83 | 22.62 | 1.85 | 5.33 | 4.97 | 0.010 | 12.83 | 12.80 |
| CB-E8NE | DMH-E8 | 10.0 | 0.075 | 6.000 | 0.45 | 5.04 | 0.58 | 8.90 | 8.70 | 0.020 | 13.00 | 13.00 |
| DMH-E8 | DMH-E9 | 114.0 | 0.695 | 5.948 | 4.17 | 6.46 | 3.39 | 8.45 | 7.31 | 0.010 | 13.57 | 13.10 |
| CB-E9NE | DMH-E9 | 10.0 | 0.097 | 6.000 | 0.59 | 5.04 | 0.75 | 8.90 | 8.70 | 0.020 | 13.10 | 13.10 |
| DMH-E9 | DMH-E5 | 118.0 | 1.390 | 5.847 | 8.19 | 10.50 | 4.64 | 7.06 | 5.88 | 0.010 | 14.12 | 13.40 |
| DMH-E5 | DMH-E6 | 104.0 | 2.971 | 5.341 | 15.99 | 22.62 | 5.09 | 4.97 | 3.93 | 0.010 | 12.62 | 12.10 |
| DMH-E6 | DMH-E7 | 56.0 | 3.464 | 5.279 | 18.44 | 22.62 | 5.87 | 3.93 | 3.37 | 0.010 | 13.07 | 12.70 |
| DMH-E7 | DMH-G11 | 41.0 | 3.464 | 5.251 | 18.34 | 31.99 | 5.84 | 2.28 | 1.46 | 0.020 | 13.17 | 12.90 |
| DMH-G11 | DMH-G10 | 10.0 | 6.122 | 4.052 | 25.00 | 66.13 | 5.09 | 0.62 | 0.36 | 0.026 | 12.84 | 12.80 |
| DMH-G10 | DMH-G9 | 18.0 | 6.122 | 4.049 | 24.99 | 41.01 | 5.09 | 0.36 | 0.18 | 0.010 | 12.87 | 12.80 |
| DMH-G9 | MH-75 | 128.0 | 49.754 | 2.288 | 114.77 | 0.00 | 5.16 | -12.15 | -12.15 | 0.000 | 7.38 | 7.23 |
| MH-75 | DMH-110 | 82.0 | 49.754 | 2.276 | 114.15 | 405.01 | 5.14 | -3.16 | -3.91 | 0.009 | 7.23 | 7.13 |
| DMH-110 | DMH-111 | 211.0 | 49.754 | 2.268 | 113.75 | 260.76 | 5.12 | -3.91 | -4.71 | 0.004 | 7.02 | 6.78 |
| DMH-111 | O-1 | 67.0 | 49.754 | 2.247 | 112.71 | 258.68 | 5.09 | -4.71 | -4.96 | 0.004 | 5.28 | 5.20 |
| CB-2 | DMH-3 | 20.0 | 0.223 | 6.000 | 1.35 | 3.90 | 4.51 | 7.72 | 7.48 | 0.012 | 8.21 | 7.89 |
| CB-1 | DMH-3 | 72.0 | 0.203 | 6.000 | 1.23 | 3.09 | 3.70 | 7.55 | 7.01 | 0.008 | 8.02 | 7.58 |
| DMH-3 | DMH-4 | 57.0 | 0.426 | 5.942 | 2.55 | 10.13 | 4.77 | 6.91 | 6.38 | 0.009 | 7.52 | 7.09 |
| DMH-4 | O-2 | 218.0 | 0.426 | 5.906 | 2.54 | 10.98 | 5.05 | 6.38 | 4.00 | 0.011 | 6.98 | 4.85 |

C:\Users\rmathews\Documents\0851805 AmPUD 2014-May.stc

Scenario: 100 Year with tailwater
Current Time Step: 0.000Hr
Conduit FlexTable: Combined Pipe/Node Report

| Start Node | Stop Node | Length (Unified) (ft) | System CA (acres) | System Intensity (in/h) | System Rational Flow (ft ³ /s) | Capacity (Full Flow) (ft ³ /s) | Velocity (Average) (ft/s) | Invert (Upstream) (ft) | Invert (Downstream) (ft) | Slope (ft/ft) | Hydraulic Grade Line (In) (ft) | Hydraulic Grade Line (Out) (ft) |
|------------|-----------|-----------------------------|-------------------------|-------------------------------|--|--|---------------------------------|------------------------------|--------------------------------|------------------|---|--|
| CB-G6N | DMH-G6 | 14.0 | 0.118 | 7.400 | 0.88 | 5.04 | 1.12 | 7.50 | 7.22 | 0.020 | 12.01 | 12.00 |
| CB-G4E | DMH-G4 | 9.0 | 0.273 | 7.400 | 2.03 | 5.04 | 2.59 | 7.00 | 6.82 | 0.020 | 11.63 | 11.60 |
| DCB-G2E | DMH-G2 | 12.0 | 0.232 | 7.400 | 1.73 | 5.14 | 2.20 | 5.00 | 4.75 | 0.021 | 9.53 | 9.50 |
| CB-G1E | DMH-G1 | 43.0 | 0.179 | 7.400 | 1.34 | 3.56 | 1.70 | 4.00 | 3.57 | 0.010 | 9.46 | 9.40 |
| CB-G1NE | DMH-G1 | 56.0 | 0.098 | 7.400 | 0.73 | 3.56 | 0.93 | 4.00 | 3.44 | 0.010 | 9.42 | 9.40 |
| DMH-G1 | DMH-G2 | 45.0 | 0.277 | 7.190 | 2.01 | 77.20 | 0.16 | 2.90 | 2.77 | 0.003 | 9.50 | 9.50 |
| DMH-G2 | DMH-G3 | 42.0 | 0.509 | 6.204 | 3.18 | 79.91 | 0.25 | 2.77 | 2.64 | 0.003 | 10.30 | 10.30 |
| DMH-G3 | DMH-G4 | 155.0 | 0.509 | 5.624 | 2.88 | 79.09 | 0.23 | 2.64 | 2.17 | 0.003 | 11.60 | 11.60 |
| DMH-G4 | DMH-G5 | 203.0 | 0.782 | 4.394 | 3.46 | 62.14 | 0.28 | 2.17 | 1.79 | 0.002 | 12.01 | 12.01 |
| RG-G1 | DMH-G5 | 65.0 | 0.000 | 7.400 | 0.00 | 8.13 | 7.72 | 5.32 | 4.29 | 0.016 | 13.42 | 12.02 |
| DMH-G5 | DMH-G6 | 118.0 | 0.782 | 3.620 | 2.85 | 137.41 | 0.98 | 1.79 | 0.71 | 0.009 | 12.01 | 12.00 |
| DMH-G6 | DMH-G7 | 38.0 | 1.015 | 3.540 | 3.62 | 80.72 | 1.04 | -0.73 | -0.85 | 0.003 | 12.30 | 12.30 |
| DMH-G7 | DMH-G8 | 11.0 | 1.015 | 3.516 | 3.60 | 212.16 | 1.04 | -0.85 | -1.09 | 0.022 | 12.40 | 12.40 |
| DMH-G8 | DMH-G9 | 70.0 | 1.015 | 3.509 | 3.59 | 78.67 | 1.04 | -1.09 | -1.30 | 0.003 | 12.81 | 12.80 |
| CB-F7NE | DMH-F7 | 12.0 | 0.219 | 7.400 | 1.63 | 5.24 | 2.08 | 9.00 | 8.74 | 0.022 | 13.23 | 13.20 |
| CB-F7NW | DMH-F7 | 13.0 | 0.000 | 7.400 | 0.00 | 5.04 | 0.00 | 9.00 | 8.74 | 0.020 | 13.20 | 13.20 |
| CB-F6NE | DMH-F6 | 12.0 | 0.195 | 7.400 | 1.46 | 5.24 | 1.85 | 9.00 | 8.74 | 0.022 | 13.22 | 13.20 |
| CB-F6NW | DMH-F6 | 13.0 | 0.000 | 7.400 | 0.00 | 5.04 | 0.00 | 9.00 | 8.74 | 0.020 | 13.20 | 13.20 |
| CB-F5NW | DMH-F5 | 13.0 | 0.000 | 7.400 | 0.00 | 5.04 | 0.00 | 9.00 | 8.74 | 0.020 | 13.10 | 13.10 |
| CB-F5NE | DMH-F5 | 13.0 | 0.212 | 7.400 | 1.58 | 5.04 | 2.01 | 9.00 | 8.74 | 0.020 | 13.13 | 13.10 |
| CB-F4NW | DMH-F4 | 13.0 | 0.121 | 7.400 | 0.91 | 3.56 | 1.15 | 9.00 | 8.87 | 0.010 | 13.21 | 13.20 |
| CB-F4NE | DMH-F4 | 12.0 | 0.123 | 7.400 | 0.92 | 3.71 | 1.17 | 9.00 | 8.87 | 0.011 | 13.21 | 13.20 |
| CB-F3NE | DMH-F3 | 10.0 | 0.240 | 7.400 | 1.79 | 5.04 | 2.28 | 8.50 | 8.30 | 0.020 | 12.93 | 12.90 |
| CB-F1NE | DMH-F1 | 9.0 | 0.083 | 7.400 | 0.62 | 3.76 | 0.79 | 9.90 | 9.80 | 0.011 | 12.90 | 12.90 |
| DMH-F1 | DMH-F2 | 78.0 | 0.514 | 7.360 | 3.81 | 6.83 | 2.16 | 8.30 | 7.97 | 0.004 | 13.06 | 12.95 |
| DCB-F2E | DMH-F2 | 77.0 | 0.404 | 7.400 | 3.01 | 5.10 | 2.45 | 8.70 | 8.22 | 0.006 | 13.17 | 13.00 |
| DMH-F2 | DMH-F3 | 36.0 | 0.917 | 7.233 | 6.69 | 12.50 | 2.13 | 7.47 | 7.36 | 0.003 | 12.93 | 12.90 |
| DMH-F3 | DMH-C5 | 129.0 | 1.157 | 7.174 | 8.37 | 12.44 | 2.66 | 7.36 | 6.97 | 0.003 | 13.98 | 13.80 |
| CB-C4SW | DMH-C4 | 12.0 | 0.075 | 7.400 | 0.56 | 5.04 | 0.72 | 9.10 | 8.86 | 0.020 | 13.40 | 13.40 |
| CB-C4NW | DMH-C4 | 12.0 | 0.050 | 7.400 | 0.37 | 5.04 | 0.48 | 9.10 | 8.86 | 0.020 | 13.40 | 13.40 |
| CB-C3SW | DMH-C3 | 12.0 | 0.028 | 7.400 | 0.21 | 11.12 | 0.27 | 9.60 | 8.43 | 0.098 | 13.40 | 13.40 |
| CB-C3NW | DMH-C3 | 12.0 | 0.025 | 7.400 | 0.19 | 11.12 | 0.24 | 9.60 | 8.43 | 0.098 | 13.40 | 13.40 |
| DMH-C3 | DMH-C4 | 40.0 | 0.141 | 7.222 | 1.03 | 10.37 | 0.58 | 8.43 | 8.04 | 0.010 | 13.40 | 13.40 |
| DMH-C4 | DMH-C5 | 57.0 | 0.733 | 6.982 | 5.16 | 10.50 | 2.92 | 8.04 | 7.47 | 0.010 | 13.94 | 13.80 |
| DMH-C5 | DMH-C6 | 33.0 | 1.890 | 6.914 | 13.17 | 12.45 | 4.19 | 6.97 | 6.87 | 0.003 | 14.18 | 14.07 |
| CB-C7SE | DMH-C7 | 14.0 | 0.106 | 7.400 | 0.79 | 5.04 | 1.00 | 9.20 | 8.92 | 0.020 | 13.41 | 13.40 |
| CB-C7NE | DMH-C7 | 14.0 | 0.117 | 7.400 | 0.87 | 5.13 | 1.11 | 9.20 | 8.91 | 0.021 | 13.41 | 13.40 |
| CB-C8SE | DMH-C8 | 14.0 | 0.146 | 7.400 | 1.09 | 5.04 | 1.38 | 10.70 | 10.42 | 0.020 | 13.61 | 13.60 |
| CB-C8NE | DMH-C8 | 14.0 | 0.082 | 7.400 | 0.61 | 5.04 | 0.78 | 10.70 | 10.42 | 0.020 | 13.60 | 13.60 |
| DMH-C8 | DMH-C7 | 178.0 | 1.598 | 7.337 | 11.82 | 6.82 | 6.69 | 8.51 | 7.76 | 0.004 | 15.65 | 13.40 |
| DMH-C7 | DMH-C6 | 92.0 | 2.175 | 7.244 | 15.88 | 14.73 | 5.06 | 7.26 | 6.87 | 0.004 | 14.58 | 14.13 |
| DMH-C6 | DMH-F4 | 116.0 | 4.183 | 6.886 | 29.03 | 22.85 | 5.91 | 6.37 | 6.01 | 0.003 | 13.78 | 13.20 |
| DMH-F4 | DMH-F5 | 122.0 | 4.789 | 6.817 | 32.91 | 34.16 | 4.66 | 5.51 | 5.19 | 0.003 | 13.40 | 13.10 |
| DMH-F5 | DMH-D5 | 108.0 | 5.332 | 6.726 | 36.15 | 38.51 | 5.11 | 5.19 | 4.83 | 0.003 | 14.22 | 13.90 |
| CB-D4NW | DMH-D4 | 12.0 | 0.112 | 7.400 | 0.83 | 3.56 | 1.06 | 10.30 | 10.18 | 0.010 | 13.41 | 13.40 |
| CB-D4SW | DMH-D4 | 13.0 | 0.117 | 7.400 | 0.87 | 3.42 | 1.11 | 10.30 | 10.18 | 0.009 | 13.41 | 13.40 |
| DMH-D4 | DMH-D5 | 90.0 | 0.452 | 7.359 | 3.35 | 10.50 | 1.90 | 8.34 | 7.44 | 0.010 | 13.99 | 13.90 |
| DCB-D6S | DMH-D6 | 12.0 | 0.434 | 7.400 | 3.24 | 5.04 | 5.80 | 8.80 | 8.56 | 0.020 | 13.30 | 13.10 |
| CB-D7E | DMH-D7 | 54.0 | 0.133 | 7.400 | 0.99 | 5.18 | 1.27 | 8.83 | 7.69 | 0.021 | 13.44 | 13.40 |
| DMH-D7 | DMH-D6 | 53.0 | 0.995 | 7.251 | 7.27 | 7.90 | 4.11 | 7.69 | 7.39 | 0.006 | 13.35 | 13.10 |
| DMH-D6 | DMH-D5 | 179.0 | 1.428 | 7.206 | 10.38 | 8.08 | 6.62 | 7.39 | 6.33 | 0.006 | 16.12 | 13.90 |
| DMH-D5 | DMH-F6 | 123.0 | 7.212 | 6.652 | 48.36 | 36.58 | 7.03 | 4.83 | 4.46 | 0.003 | 13.88 | 13.20 |
| DMH-F6 | DMH-F7 | 122.0 | 7.870 | 6.591 | 52.28 | 36.73 | 7.58 | 4.46 | 4.09 | 0.003 | 13.99 | 13.20 |
| DMH-F7 | DMH-F8 | 23.0 | 8.089 | 6.534 | 53.28 | 43.98 | 7.72 | 4.09 | 3.99 | 0.004 | 13.39 | 13.24 |
| DMH-F8 | DMH-F9 | 10.0 | 8.089 | 6.524 | 53.20 | 94.32 | 7.71 | 3.99 | 3.79 | 0.020 | 12.42 | 12.35 |
| DMH-F9 | DMH-F10 | 79.0 | 8.089 | 6.519 | 53.16 | 36.76 | 7.71 | 3.79 | 3.55 | 0.003 | 12.22 | 11.69 |
| CB-E2SE | DMH-E2 | 8.0 | 0.195 | 7.400 | 1.45 | 5.19 | 1.85 | 7.80 | 7.63 | 0.021 | 12.01 | 12.00 |
| CB-E2NE | DMH-E2 | 49.0 | 0.154 | 7.400 | 1.15 | 3.56 | 1.46 | 7.80 | 7.31 | 0.010 | 12.05 | 12.00 |
| DMH-E2 | DMH-E1 | 33.0 | 0.348 | 7.283 | 2.56 | 3.56 | 3.26 | 7.31 | 6.98 | 0.010 | 12.67 | 12.50 |
| DMH-E1 | DMH-E1 | 9.0 | 0.348 | 7.247 | 2.54 | 3.36 | 3.24 | 5.56 | 5.48 | 0.009 | 12.25 | 12.21 |
| CB-21 | DMH-22 | 5.0 | 0.496 | 7.400 | 3.70 | 4.51 | 4.71 | 6.82 | 6.74 | 0.016 | 11.13 | 11.08 |
| CB-20 | DMH-22 | 49.0 | 0.428 | 7.400 | 3.20 | 3.53 | 4.07 | 6.82 | 6.34 | 0.010 | 11.47 | 11.08 |
| CB-18 | DMH-19 | 6.0 | 0.140 | 7.400 | 1.04 | 5.44 | 1.33 | 8.74 | 8.60 | 0.023 | 12.40 | 12.40 |
| CB-17 | DMH-19 | 49.0 | 0.141 | 7.400 | 1.05 | 3.60 | 1.34 | 8.74 | 8.24 | 0.010 | 12.64 | 12.60 |
| CB-11 | DMH-12 | 5.0 | 0.530 | 7.400 | 3.95 | 3.90 | 5.03 | 6.66 | 6.60 | 0.012 | 10.98 | 10.92 |
| CB-10 | DMH-12 | 49.0 | 0.419 | 7.400 | 3.13 | 3.56 | 3.98 | 6.66 | 6.17 | 0.010 | 11.30 | 10.92 |
| CB-A6SE | DMH-A6 | 14.0 | 0.367 | 7.400 | 2.73 | 3.56 | 3.48 | 8.08 | 7.94 | 0.010 | 11.48 | 11.40 |
| CB-A6N | DMH-A6 | 15.0 | 0.169 | 7.400 | 1.26 | 3.56 | 1.60 | 8.09 | 7.94 | 0.010 | 11.42 | 11.40 |
| DMH-A6 | DMH-A5 | 93.0 | 0.777 | 7.367 | 5.77 | 5.76 | 3.27 | 7.94 | 7.66 | 0.003 | 12.78 | 12.50 |
| DMH-A5 | DMH-A4 | 126.0 | 0.777 | 7.268 | 5.69 | 5.77 | 3.22 | 7.66 | 7.28 | 0.003 | 12.42 | 12.05 |
| CB-A4S | DMH-A4 | 14.0 | 0.041 | 7.400 | 0.31 | 5.04 | 0.39 | 10.00 | 9.72 | 0.020 | 12.08 | 12.08 |
| CB-A4N | DMH-A4 | 14.0 | 0.053 | 7.400 | 0.39 | 5.13 | 0.50 | 10.00 | 9.71 | 0.021 | 12.10 | 12.10 |
| DMH-A4 | DMH-A3 | 178.0 | 0.871 | 7.131 | 6.26 | 12.34 | 1.99 | 7.28 | 6.75 | 0.003 | 12.03 | 11.89 |
| DMH-A3 | DMH-A2 | 42.0 | 1.360 | 6.818 | 9.35 | 12.59 | 2.98 | 6.75 | 6.62 | 0.003 | 11.77 | 11.70 |
| CB-A1S | DMH-A2 | 15.0 | 0.159 | 7.400 | 1.18 | 4.69 | 1.51 | 7.50 | 7.24 | 0.017 | 11.72 | 11.70 |
| CB-A1N | DMH-A2 | 13.0 | 0.089 | 7.400 | 0.67 | 5.93 | 0.85 | 7.60 | 7.24 | 0.028 | 11.70 | 11.70 |
| DMH-A2 | DMH-A1 | 23.0 | 1.642 | 6.769 | 11.20 | 14.92 | 3.57 | 6.62 | 6.52 | 0.004 | 11.86 | 11.80 |
| DMH-A1 | DMH-8 | 93.0 | 1.642 | 6.746 | 11.17 | 12.19 | 3.55 | 6.49 | 6.22 | 0.003 | 12.34 | 12.11 |
| CB-8B | DMH-8 | 22.0 | 0.058 | 7.400 | 0.43 | 3.13 | 0.55 | 8.45 | 8.28 | 0.008 | 12.03 | 12.02 |
| CB-8C | DMH-8 | 61.0 | 0.151 | 7.400 | 1.12 | 3.41 | 1.43 | 8.20 | 7.64 | 0.009 | 12.17 | 12.11 |
| CB-8A | DMH-8 | 65.0 | 0.229 | 7.400 | 1.71 | 2.42 | 2.17 | 8.29 | 7.99 | 0.005 | 12.17 | 12.02 |
| DMH-8 | DMH-9 | 83.0 | 2.079 | 6.655 | 13.95 | 11.10 | 4.44 | 6.22 | 6.02 | 0.002 | 11.69 | 11.37 |
| DMH-9 | DMH-12 | 97.0 | 2.079 | 6.589 | 13.81 | 11.25 | 4.40 | 6.00 | 5.76 | 0.002 | 11.28 | 10.92 |
| DMH-12 | DMH-13 | 242.0 | 3.028 | 6.512 | 19.88 | 20.93 | 4.05 | 5.26 | 4.63 | 0.003 | 13.47 | 12.90 |
| CB-C1N | DMH-C1 | 24.0 | 0.064 | 7.400 | 0.48 | 5.04 | 0.61 | 10.00 | 9.52 | 0.020 | 13.30 | 13.30 |
| CB-C1SE | DMH-C1 | 17.0 | 0.056 | 7.400 | 0.42 | 4.96 | 0.53 | 10.00 | 9.67 | 0.019 | 13.30 | 13.30 |
| CB-C2NE | DMH-C2 | 23.0 | 0.071 | 7.400 | 0.53 | 5.04 | 0.68 | 8.80 | 8.34 | 0.020 | 13.21 | 13.20 |
| CB-C2SE | DMH-C2 | 13.0 | 0.073 | 7.400 | 0.55 | 5.04 | 0.70 | 8.90 | 8.64 | 0.020 | 13.20 | 13.20 |
| DMH-C2 | DMH-C1 | 77.0 | 1.629 | 7.281 | 11.96 | 10.50 | 6.77 | 7.63 | 6.86 | 0.010 | 14.30 | 13.30 |
| DMH-C1 | DMH-13 | 123.0 | 1.749 | 7.241 | 12.77 | 10.50 | 7.23 | 6.86 | 5.63 | 0.010 | 14.72 | 12.90 |
| DMH-13 | DMH-16 | 64.0 | 4.777 | 6.303 | 30.35 | 21.14 | 6.18 | 4.63 | 4.46 | 0.003 | 13.79 | 13.44 |
| CB-14 | DMH-16 | 49.0 | 0.081 | 7.400 | 0.61 | 3.60 | 0.77 | 9.21 | 8.71 | 0.010 | 13.45 | 13.44 |

| | | | | | | | | | | | | |
|-------------------|---------|-------|--------|-------|-------|--------|-------|-------|-------|--------|-------|-------|
| CB-15 | DMH-16 | 12.0 | 0.078 | 7.400 | 0.58 | 2.30 | 0.74 | 9.19 | 9.14 | 0.004 | 13.44 | 13.44 |
| DMH-16 | DMH-19 | 240.0 | 4.936 | 6.267 | 31.18 | 20.85 | 6.35 | 4.46 | 3.84 | 0.003 | 13.59 | 12.20 |
| DMH-19 | DMH-D1 | 42.0 | 5.217 | 6.134 | 32.26 | 33.91 | 4.56 | 3.34 | 3.23 | 0.003 | 12.15 | 12.05 |
| DMH-D3 | DMH-D2 | 46.0 | 1.280 | 7.400 | 9.55 | 7.74 | 5.40 | 6.52 | 6.27 | 0.005 | 12.18 | 11.80 |
| CB-D2S | DMH-D2 | 29.0 | 0.214 | 7.400 | 1.60 | 3.17 | 4.22 | 7.00 | 6.77 | 0.008 | 12.05 | 11.80 |
| DMH-D2 | DMH-D1 | 104.0 | 1.808 | 7.370 | 13.43 | 11.52 | 8.57 | 5.77 | 4.52 | 0.012 | 14.85 | 12.69 |
| DMH-D1 | DMH-22 | 194.0 | 7.024 | 6.102 | 43.21 | 33.91 | 6.36 | 3.23 | 2.73 | 0.003 | 11.96 | 11.08 |
| DMH-22 | DMH-23 | 122.0 | 7.948 | 5.995 | 48.03 | 51.52 | 5.17 | 2.23 | 1.91 | 0.003 | 12.25 | 11.95 |
| DMH-23 | DMH-24 | 11.0 | 7.948 | 5.913 | 47.37 | 95.92 | 5.10 | 1.86 | 1.76 | 0.009 | 12.08 | 12.05 |
| DMH-24 | DMH-105 | 30.0 | 7.948 | 5.905 | 47.31 | 91.84 | 5.10 | 1.71 | 1.46 | 0.008 | 12.39 | 12.32 |
| CB-30 | DMH-31 | 47.0 | 0.320 | 7.400 | 2.39 | 3.52 | 3.04 | 7.41 | 6.95 | 0.010 | 12.19 | 11.98 |
| CB-32O | DMH-32M | 54.0 | 0.000 | 7.400 | 0.00 | 3.43 | 0.00 | 4.00 | 3.50 | 0.009 | 11.09 | 11.09 |
| CB-32R | DMH-32P | 37.0 | 0.386 | 7.400 | 2.88 | 3.31 | 3.67 | 7.64 | 7.32 | 0.009 | 11.93 | 11.69 |
| CB-32Q | DMH-32P | 22.0 | 0.288 | 7.400 | 2.15 | 2.94 | 2.73 | 7.48 | 7.33 | 0.007 | 11.77 | 11.69 |
| DMH-32P | DMH-32M | 53.0 | 1.266 | 7.385 | 9.40 | 10.99 | 5.32 | 3.02 | 2.44 | 0.011 | 11.51 | 11.09 |
| CB-32N | DMH-32M | 12.0 | 0.313 | 7.400 | 2.33 | 2.91 | 2.97 | 6.88 | 6.80 | 0.007 | 11.14 | 11.09 |
| CB-F15 | DMH-F13 | 17.0 | 0.146 | 7.400 | 1.09 | 5.04 | 1.38 | 7.10 | 6.76 | 0.020 | 11.32 | 11.30 |
| CB-F14 | DMH-F13 | 16.0 | 0.206 | 7.400 | 1.54 | 5.19 | 1.96 | 7.10 | 6.76 | 0.021 | 11.33 | 11.30 |
| CB-F13 | DMH-F12 | 10.0 | 0.000 | 7.400 | 0.00 | 5.04 | 0.00 | 9.30 | 9.10 | 0.020 | 12.65 | 12.65 |
| CB-F12 | DMH-F11 | 12.0 | 0.145 | 7.400 | 1.08 | 5.04 | 1.38 | 9.30 | 9.06 | 0.020 | 11.86 | 11.85 |
| DMH-F11 | DMH-F12 | 128.0 | 0.145 | 7.369 | 1.08 | 10.50 | 0.61 | 7.19 | 5.91 | 0.010 | 11.84 | 11.83 |
| DMH-F12 | DMH-F13 | 140.0 | 0.915 | 6.634 | 6.12 | 10.50 | 3.46 | 5.91 | 4.51 | 0.010 | 11.78 | 11.30 |
| DMH-F13 | DMH-32T | 76.0 | 1.267 | 6.492 | 8.29 | 10.29 | 4.69 | 4.51 | 3.78 | 0.010 | 11.86 | 11.39 |
| CB-32Z | DMH-32Y | 31.0 | 0.000 | 7.400 | 0.00 | 2.56 | 7.92 | 3.86 | 3.70 | 0.005 | 12.04 | 11.10 |
| DMH-32Y | DMH-32U | 47.0 | 0.000 | 7.386 | 0.00 | 6.85 | 3.52 | 3.69 | 3.49 | 0.004 | 10.83 | 10.67 |
| CB-32V | DMH-32U | 27.0 | 0.255 | 7.400 | 1.90 | 3.22 | 2.42 | 6.59 | 6.37 | 0.008 | 10.75 | 10.67 |
| CB-32W | DMH-32U | 18.0 | 0.212 | 7.400 | 1.58 | 3.03 | 2.02 | 6.39 | 6.26 | 0.007 | 10.71 | 10.67 |
| CB-32X | DMH-32U | 38.0 | 0.217 | 7.400 | 1.62 | 3.32 | 2.06 | 6.29 | 5.96 | 0.009 | 10.75 | 10.67 |
| DMH-32U | DMH-32T | 119.0 | 1.083 | 7.335 | 8.01 | 6.88 | 8.05 | 3.39 | 2.88 | 0.004 | 13.57 | 11.39 |
| DMH-32T | DMH-32S | 171.0 | 2.350 | 6.436 | 15.25 | 21.96 | 4.37 | 2.78 | 2.29 | 0.003 | 12.41 | 11.94 |
| DMH-32S | DMH-32M | 277.0 | 2.350 | 6.299 | 14.92 | 22.45 | 4.31 | 2.27 | 1.44 | 0.003 | 11.83 | 11.09 |
| DMH-32M | DMH-32L | 24.0 | 3.930 | 6.074 | 24.06 | 22.15 | 6.17 | 1.42 | 1.35 | 0.003 | 11.50 | 11.37 |
| DMH-32L | DMH-32K | 9.0 | 3.930 | 6.060 | 24.00 | 43.23 | 6.16 | 1.30 | 1.20 | 0.011 | 11.54 | 11.49 |
| DMH-32K | DMH-32 | 17.0 | 3.930 | 6.055 | 23.98 | 24.37 | 6.15 | 1.15 | 1.09 | 0.004 | 11.71 | 11.62 |
| CB-34N | CB-34M | 32.0 | 0.206 | 7.400 | 1.54 | 10.24 | 0.87 | 6.81 | 6.63 | 0.006 | 10.90 | 10.90 |
| CB-34M | CB-34L | 40.0 | 0.415 | 7.271 | 3.04 | 10.35 | 1.72 | 6.63 | 6.40 | 0.006 | 10.90 | 10.88 |
| CB-34L | CB-34K | 93.0 | 0.633 | 7.190 | 4.59 | 10.41 | 2.60 | 6.40 | 5.88 | 0.006 | 10.88 | 10.77 |
| CB-34K | CB-34J | 25.0 | 0.880 | 7.065 | 6.27 | 10.22 | 3.55 | 5.86 | 5.72 | 0.006 | 10.77 | 10.72 |
| CB-34J | CB-34I | 51.0 | 1.114 | 7.040 | 7.90 | 10.12 | 4.47 | 5.72 | 5.44 | 0.005 | 10.72 | 10.55 |
| CB-34I | CB-34H | 48.0 | 1.330 | 7.000 | 9.38 | 22.46 | 2.99 | 5.44 | 5.16 | 0.006 | 10.55 | 10.50 |
| CB-34H | CB-34G | 41.0 | 1.560 | 6.944 | 10.92 | 22.03 | 3.48 | 5.16 | 4.93 | 0.006 | 10.56 | 10.50 |
| CB-34G | CB-34F | 41.0 | 1.776 | 6.902 | 12.35 | 22.50 | 3.93 | 4.93 | 4.69 | 0.006 | 11.10 | 11.03 |
| CB-34F | CB-34E | 42.0 | 1.983 | 6.866 | 13.72 | 22.23 | 4.37 | 4.69 | 4.45 | 0.006 | 11.03 | 10.94 |
| CB-34E | CB-34D | 41.0 | 2.190 | 6.832 | 15.09 | 22.03 | 4.80 | 4.45 | 4.22 | 0.006 | 10.94 | 10.83 |
| CB-34D | CB-34C | 41.0 | 2.418 | 6.802 | 16.58 | 22.50 | 5.28 | 4.22 | 3.98 | 0.006 | 10.83 | 10.70 |
| CB-34C | DMH-34A | 18.0 | 2.641 | 6.775 | 18.03 | 19.61 | 5.74 | 3.98 | 3.90 | 0.004 | 10.74 | 10.67 |
| CB-34B | DMH-34A | 32.0 | 0.043 | 7.400 | 0.32 | 3.73 | 0.41 | 4.90 | 4.55 | 0.011 | 10.67 | 10.67 |
| DMH-34A | DMH-34 | 67.0 | 2.683 | 6.764 | 18.30 | 23.12 | 5.82 | 3.90 | 3.20 | 0.010 | 11.00 | 10.86 |
| CB-39D | CB-39C | 70.0 | 0.152 | 7.400 | 1.13 | 3.56 | 1.44 | 6.00 | 5.30 | 0.010 | 9.59 | 9.52 |
| CB-39C | DMH-39A | 23.0 | 0.152 | 7.230 | 1.10 | 5.75 | 1.41 | 5.30 | 4.70 | 0.026 | 9.52 | 9.50 |
| CB-39B | DMH-39A | 16.0 | 0.258 | 7.400 | 1.92 | 3.56 | 2.45 | 5.11 | 4.95 | 0.010 | 9.55 | 9.50 |
| DMH-39A | DMH-38 | 50.0 | 0.409 | 7.173 | 2.96 | 6.13 | 2.41 | 4.70 | 4.25 | 0.009 | 9.81 | 9.71 |
| CB-38A | DMH-38 | 35.0 | 0.000 | 5.387 | 0.00 | 7.94 | 11.58 | 3.40 | 3.20 | 0.006 | 11.04 | 9.71 |
| CB-40A | DMH-41 | 12.0 | 0.214 | 7.400 | 1.60 | 2.72 | 2.03 | 5.57 | 5.50 | 0.006 | 9.51 | 9.49 |
| CB-43 | DMH-44 | 26.0 | 0.124 | 7.400 | 0.92 | 1.56 | 1.18 | 6.16 | 6.11 | 0.002 | 9.75 | 9.73 |
| CB-42 | DMH-44 | 19.0 | 0.220 | 7.400 | 1.64 | 4.90 | 2.09 | 6.15 | 5.79 | 0.019 | 9.81 | 9.77 |
| CB-45A | DMH-45 | 35.0 | 0.165 | 7.400 | 1.38 | 3.56 | 1.76 | 7.12 | 6.77 | 0.010 | 11.35 | 11.30 |
| CB-46B | DMH-46A | 45.0 | 0.146 | 7.400 | 1.09 | 2.19 | 1.99 | 7.75 | 7.30 | 0.010 | 12.01 | 11.90 |
| CB-46E | DMH-46C | 7.0 | 0.439 | 7.400 | 3.27 | -2.50 | 9.38 | 10.80 | 10.90 | -0.043 | 14.53 | 14.02 |
| CB-46D | DMH-46C | 40.0 | 0.168 | 7.400 | 1.25 | -1.05 | 3.58 | 10.60 | 10.90 | -0.008 | 14.45 | 14.02 |
| CB-46H | DMH-46F | 8.0 | 0.481 | 7.400 | 3.59 | 1.35 | 10.29 | 14.30 | 14.20 | 0.013 | 15.80 | 15.09 |
| CB-46G | DMH-46F | 39.0 | 0.138 | 7.400 | 1.03 | -1.37 | 2.95 | 13.70 | 14.20 | -0.013 | 15.42 | 15.14 |
| CB-46M | CB-46L | 58.0 | 0.111 | 7.400 | 0.83 | 1.23 | 3.78 | 16.60 | 16.00 | 0.010 | 17.19 | 16.93 |
| CB-46L | DMH-46K | 46.0 | 0.216 | 7.346 | 1.60 | 1.26 | 4.59 | 16.00 | 15.50 | 0.011 | 16.93 | 16.09 |
| CB-46Q | DMH-46N | 7.0 | 0.086 | 7.400 | 0.64 | 4.86 | 4.28 | 17.20 | 17.07 | 0.019 | 17.60 | 17.63 |
| CB-46O | DMH-46N | 23.0 | 0.099 | 7.400 | 0.74 | 1.38 | 4.02 | 17.37 | 17.07 | 0.013 | 17.78 | 17.62 |
| CB-46P | DMH-46N | 22.0 | 0.073 | 7.400 | 0.54 | 1.24 | 3.43 | 17.30 | 17.07 | 0.010 | 17.65 | 17.61 |
| DMH-46N | DMH-46K | 137.0 | 0.258 | 7.378 | 1.92 | 13.52 | 5.41 | 17.07 | 14.80 | 0.017 | 17.59 | 15.55 |
| DMH-46K | DMH-46J | 37.0 | 0.474 | 7.289 | 3.48 | 13.38 | 6.36 | 14.80 | 14.20 | 0.016 | 15.51 | 15.03 |
| DMH-46J | DMH-46I | 12.0 | 0.474 | 7.269 | 3.47 | 13.56 | 6.42 | 14.20 | 14.00 | 0.017 | 14.91 | 14.98 |
| DMH-46I | DMH-46F | 52.0 | 0.474 | 7.262 | 3.47 | 11.28 | 5.62 | 14.00 | 13.40 | 0.012 | 14.90 | 14.93 |
| DMH-46F | DMH-46C | 150.0 | 1.094 | 7.230 | 7.97 | 15.34 | 8.77 | 13.40 | 10.20 | 0.021 | 14.88 | 14.02 |
| DMH-46C | DMH-46A | 149.0 | 1.700 | 7.170 | 12.29 | 14.40 | 6.95 | 10.10 | 7.30 | 0.019 | 13.94 | 11.90 |
| DMH-46A | DMH-45 | 78.0 | 1.846 | 7.095 | 13.20 | 12.47 | 7.47 | 7.30 | 6.20 | 0.014 | 12.09 | 10.86 |
| CB-45B | DMH-45 | 8.0 | 0.169 | 7.400 | 1.26 | 3.31 | 3.61 | 6.80 | 6.20 | 0.075 | 10.97 | 10.88 |
| CB-45C | DMH-45 | 33.0 | 0.188 | 7.400 | 1.41 | -2.63 | 1.79 | 6.85 | 7.03 | -0.005 | 11.36 | 11.31 |
| DMH-45 | DMH-44 | 182.0 | 2.389 | 7.058 | 17.00 | 23.36 | 5.41 | 6.20 | 4.26 | 0.011 | 10.73 | 9.70 |
| DMH-44 | DMH-41 | 186.0 | 2.732 | 6.940 | 19.12 | 46.13 | 2.70 | 4.16 | 3.27 | 0.005 | 9.64 | 9.49 |
| CB-40 | DMH-41 | 3.0 | 0.120 | 7.400 | 0.89 | 5.44 | 1.14 | 5.48 | 5.41 | 0.023 | 9.49 | 9.49 |
| CB-39 | DMH-41 | 38.0 | 0.264 | 7.400 | 1.97 | 3.37 | 2.51 | 5.23 | 4.89 | 0.009 | 9.61 | 9.49 |
| DMH-41 | DMH-38 | 60.0 | 3.330 | 6.700 | 22.49 | 58.08 | 2.34 | 3.22 | 3.02 | 0.003 | 9.74 | 9.71 |
| DMH-38A(Partners) | DMH-38 | 123.0 | 6.562 | 7.400 | 48.95 | 55.92 | 5.09 | 3.40 | 3.02 | 0.003 | 10.00 | 9.71 |
| DMH-38 | DMH-37 | 431.0 | 10.302 | 5.376 | 55.82 | 74.52 | 6.07 | 3.02 | 1.86 | 0.003 | 11.22 | 10.00 |
| CB-36 | DMH-37 | 3.0 | 0.510 | 7.400 | 3.81 | 6.50 | 4.85 | 5.72 | 5.62 | 0.033 | 10.03 | 10.00 |
| CB-35 | DMH-37 | 36.0 | 0.438 | 7.400 | 3.27 | 3.51 | 4.16 | 5.80 | 5.45 | 0.010 | 10.30 | 10.00 |
| DMH-37 | DMH-34 | 101.0 | 11.250 | 5.223 | 59.24 | 74.26 | 6.34 | 1.84 | 1.57 | 0.003 | 10.87 | 10.56 |
| DMH-34 | DMH-33B | 71.0 | 13.934 | 5.199 | 73.02 | 78.12 | 7.44 | 1.56 | 1.35 | 0.003 | 11.56 | 11.26 |
| DMH-33B | DMH-33A | 12.0 | 13.934 | 5.184 | 72.81 | 131.12 | 7.42 | 1.30 | 1.20 | 0.008 | 11.43 | 11.38 |
| DMH-33A | DMH-32 | 24.0 | 13.934 | 5.181 | 72.77 | 77.57 | 7.42 | 1.15 | 1.08 | 0.003 | 11.72 | 11.62 |
| CB-32D | DMH-32B | 39.0 | 0.140 | 7.400 | 1.04 | 3.33 | 1.33 | 6.62 | 6.28 | 0.009 | 10.47 | 10.44 |
| CB-32C | DMH-32B | 21.0 | 0.134 | 7.400 | 1.00 | 3.21 | 1.28 | 6.90 | 6.73 | 0.008 | 10.41 | 10.39 |
| CB-32I | DMH-32H | 17.0 | 0.183 | 7.400 | 1.36 | 1.31 | 3.91 | 6.70 | 6.50 | 0.012 | 10.04 | 9.83 |
| CB-32J | DMH-32H | 48.0 | 0.171 | 7.400 | 1.27 | 1.23 | 3.65 | 6.40 | 5.90 | 0.010 | 10.36 | 9.83 |
| DMH-32H | DMH-32E | 119.0 | 0.353 | 7.354 | 2.62 | 22.14 | 0.83 | 5.90 | 4.76 | 0.010 | 9.82 | 9.80 |
| CB-32G | DMH-32E | 44.0 | 0.088 | 7.400 | | | | | | | | |

| | | | | | | | | | | | | |
|----------|---------|-------|--------|-------|--------|--------|------|--------|--------|--------|-------|-------|
| DMH-28 | DMH-28 | 165.0 | 19.902 | 5.091 | 102.12 | 180.57 | 4.56 | 0.65 | 0.35 | 0.002 | 12.50 | 12.35 |
| CB-27 | DMH-25 | 158.0 | 20.393 | 5.034 | 103.49 | 178.27 | 4.60 | 0.35 | 0.07 | 0.002 | 12.32 | 12.17 |
| CB-26 | DMH-25 | 5.0 | 0.262 | 7.400 | 1.96 | 2.76 | 2.49 | 8.42 | 8.39 | 0.006 | 12.52 | 12.51 |
| DMH-25 | DMH-25 | 48.0 | 0.205 | 7.400 | 1.53 | 3.53 | 1.95 | 8.41 | 7.94 | 0.010 | 12.59 | 12.51 |
| CB-24C | DMH-105 | 61.0 | 20.860 | 4.981 | 104.73 | 179.83 | 4.65 | 0.07 | -0.04 | 0.002 | 12.14 | 12.08 |
| CB-24G | DMH-24B | 34.0 | 0.050 | 7.400 | 0.37 | 3.56 | 0.48 | 5.23 | 4.89 | 0.010 | 10.42 | 10.42 |
| CB-24J | DMH-24E | 41.0 | 0.072 | 7.400 | 0.54 | 4.98 | 0.68 | 5.90 | 5.10 | 0.020 | 10.09 | 10.08 |
| CB-24K | DMH-24I | 9.0 | 0.156 | 7.400 | 1.16 | 1.45 | 3.33 | 5.80 | 5.67 | 0.014 | 9.05 | 8.97 |
| DMH-24I | DMH-24I | 54.0 | 0.183 | 7.400 | 1.36 | 1.87 | 3.90 | 6.70 | 5.41 | 0.024 | 9.66 | 8.97 |
| DMH-24H | DMH-24H | 173.0 | 0.339 | 7.352 | 2.51 | 3.61 | 3.19 | 5.41 | 3.63 | 0.010 | 10.76 | 9.90 |
| CB-24M | DMH-24E | 23.0 | 0.339 | 7.162 | 2.44 | 5.04 | 3.11 | 3.53 | 3.07 | 0.020 | 10.19 | 10.08 |
| CB-24P | DMH-24L | 18.0 | 0.456 | 7.400 | 3.40 | 6.50 | 4.33 | 3.10 | 2.50 | 0.033 | 9.21 | 9.05 |
| CB-24O | DMH-24N | 23.0 | 0.675 | 7.400 | 5.04 | 5.25 | 6.41 | 4.60 | 4.10 | 0.022 | 9.08 | 8.62 |
| CB-24Q | DMH-24N | 21.0 | 0.548 | 7.400 | 4.09 | 7.38 | 5.20 | 5.00 | 4.10 | 0.043 | 8.90 | 8.62 |
| CB-24S | DMH-24N | 154.0 | 0.071 | 7.400 | 0.53 | 3.63 | 0.67 | 5.60 | 4.00 | 0.010 | 8.65 | 8.62 |
| CB-24T | DMH-24R | 26.0 | 0.171 | 7.400 | 1.27 | 4.42 | 1.62 | 6.60 | 6.20 | 0.015 | 9.40 | 9.37 |
| CB-24U | DMH-24R | 11.0 | 0.775 | 7.400 | 5.78 | -11.77 | 7.36 | 5.40 | 6.60 | -0.109 | 9.66 | 9.37 |
| DMH-24R | DMH-24R | 116.0 | 0.161 | 7.400 | 1.20 | 2.96 | 1.53 | 7.10 | 6.30 | 0.007 | 9.50 | 9.37 |
| DMH-24N | DMH-24N | 300.0 | 1.106 | 7.134 | 7.96 | 8.58 | 4.50 | 6.10 | 4.10 | 0.007 | 10.34 | 8.62 |
| DMH-24L | DMH-24L | 294.0 | 2.400 | 6.599 | 15.97 | 16.16 | 5.08 | 4.00 | 2.50 | 0.005 | 10.51 | 9.05 |
| DMH-24L | DMH-24E | 80.0 | 2.856 | 6.396 | 18.42 | 14.96 | 5.86 | 2.50 | 2.15 | 0.004 | 10.61 | 10.08 |
| CB-24F | DMH-24E | 15.0 | 0.136 | 7.400 | 1.02 | 3.05 | 1.29 | 5.73 | 5.62 | 0.007 | 10.09 | 10.08 |
| DMH-24E | DMH-24B | 37.0 | 3.403 | 6.348 | 21.78 | 75.96 | 3.08 | 1.35 | 0.87 | 0.013 | 10.46 | 10.42 |
| CB-24D | DMH-24B | 35.0 | 0.121 | 7.400 | 0.90 | 1.51 | 2.58 | 6.65 | 6.10 | 0.016 | 10.61 | 10.42 |
| DMH-24B | DMH-24A | 47.0 | 3.574 | 6.306 | 22.72 | 63.05 | 3.21 | 0.87 | 0.45 | 0.009 | 10.89 | 10.84 |
| DMH-24A | DMH-105 | 199.0 | 3.574 | 6.255 | 22.54 | 25.90 | 3.19 | 0.30 | 0.00 | 0.002 | 12.17 | 11.94 |
| DMH-105 | MH-68 | 43.0 | 32.382 | 4.961 | 161.92 | 266.27 | 6.73 | -0.04 | -0.21 | 0.004 | 11.71 | 11.62 |
| MH-68 | DMH-107 | 222.0 | 32.731 | 4.951 | 163.33 | 258.94 | 6.78 | -0.21 | -1.04 | 0.004 | 11.51 | 11.05 |
| DMH-107 | DMH-F10 | 172.0 | 34.528 | 4.900 | 170.53 | 256.30 | 7.04 | -1.04 | -1.67 | 0.004 | 10.94 | 10.56 |
| DMH-F10 | DMH-G9 | 374.0 | 42.617 | 4.862 | 208.85 | 267.30 | 8.44 | -1.67 | -3.16 | 0.004 | 10.40 | 9.21 |
| CB-G12SE | DMH-G12 | 13.0 | 0.075 | 7.400 | 0.56 | 5.13 | 0.72 | 8.00 | 7.73 | 0.021 | 12.20 | 12.20 |
| CB-G13SE | DMH-G13 | 13.0 | 0.107 | 7.400 | 0.80 | 5.04 | 1.01 | 7.50 | 7.24 | 0.020 | 11.81 | 11.80 |
| DMH-63B | DMH-G14 | 23.0 | 0.241 | 7.400 | 1.80 | 2.97 | 3.30 | 4.75 | 4.50 | 0.011 | 12.19 | 12.10 |
| CB-G15SE | DMH-G15 | 13.0 | 0.082 | 7.400 | 0.61 | 5.04 | 0.78 | 7.70 | 7.44 | 0.020 | 11.80 | 11.80 |
| MH-74 | DMH-G15 | 10.0 | 1.029 | 5.300 | 5.50 | 4.63 | 7.00 | 4.90 | 4.80 | 0.010 | 11.94 | 11.80 |
| DMH-G15 | DMH-G14 | 24.0 | 1.113 | 5.298 | 5.95 | 9.83 | 3.36 | 4.71 | 4.50 | 0.009 | 12.18 | 12.10 |
| CB-G14SW | DMH-G14 | 17.0 | 0.062 | 7.400 | 0.46 | 5.11 | 0.59 | 7.80 | 7.45 | 0.021 | 12.10 | 12.10 |
| DMH-G14 | DMH-G13 | 167.0 | 1.754 | 5.287 | 9.35 | 9.34 | 5.29 | 4.50 | 3.18 | 0.008 | 13.12 | 11.80 |
| CB-G13SW | DMH-G13 | 13.0 | 0.103 | 7.400 | 0.77 | 4.84 | 0.98 | 7.50 | 7.26 | 0.018 | 11.81 | 11.80 |
| DMH-G13 | DMH-G12 | 149.0 | 2.399 | 5.238 | 12.67 | 20.13 | 4.03 | 2.68 | 1.50 | 0.008 | 12.67 | 12.20 |
| CB-G12SW | DMH-G12 | 13.0 | 0.045 | 7.400 | 0.34 | 5.13 | 0.43 | 8.00 | 7.73 | 0.021 | 12.20 | 12.20 |
| DMH-G12 | DMH-G11 | 47.0 | 2.639 | 5.180 | 13.78 | 20.34 | 4.39 | 1.50 | 1.12 | 0.008 | 13.07 | 12.90 |
| CB-E6SW | DMH-E6 | 9.0 | 0.247 | 7.400 | 1.84 | 3.56 | 2.34 | 8.61 | 8.52 | 0.010 | 12.12 | 12.10 |
| CB-E6NW | DMH-E6 | 26.0 | 0.247 | 7.400 | 1.84 | 3.56 | 2.35 | 8.78 | 8.52 | 0.010 | 12.17 | 12.10 |
| CB-E3SW | DMH-E3 | 12.0 | 0.156 | 7.400 | 1.16 | 3.56 | 1.48 | 9.10 | 8.98 | 0.010 | 13.21 | 13.20 |
| CB-E3NW | DMH-E3 | 26.0 | 0.151 | 7.400 | 1.13 | 3.63 | 1.43 | 10.19 | 9.92 | 0.010 | 13.23 | 13.20 |
| DMH-E3 | DMH-E4 | 140.0 | 0.307 | 7.337 | 2.27 | 10.50 | 1.28 | 8.09 | 6.69 | 0.010 | 13.70 | 13.63 |
| CB-E4NW | DMH-E4 | 26.0 | 0.134 | 7.400 | 1.00 | 4.99 | 1.27 | 9.50 | 8.99 | 0.020 | 13.72 | 13.70 |
| CB-E4SW | DMH-E4 | 9.0 | 0.176 | 7.400 | 1.32 | 5.18 | 1.68 | 9.50 | 9.31 | 0.021 | 13.71 | 13.70 |
| DMH-E4 | DMH-E5 | 122.0 | 0.617 | 6.955 | 4.33 | 10.50 | 2.45 | 6.69 | 5.47 | 0.010 | 13.61 | 13.40 |
| DMH-E10 | DMH-E5 | 36.0 | 0.963 | 7.400 | 7.19 | 22.62 | 2.29 | 5.33 | 4.97 | 0.010 | 13.26 | 13.23 |
| CB-E8NE | DMH-E8 | 10.0 | 0.075 | 7.400 | 0.56 | 5.04 | 0.71 | 8.90 | 8.70 | 0.020 | 13.00 | 13.00 |
| DMH-E8 | DMH-E9 | 114.0 | 0.695 | 7.351 | 5.15 | 6.46 | 4.19 | 8.45 | 7.31 | 0.010 | 13.82 | 13.10 |
| CB-E9NE | DMH-E9 | 10.0 | 0.097 | 7.400 | 0.73 | 5.04 | 0.93 | 8.90 | 8.70 | 0.020 | 13.10 | 13.10 |
| DMH-E9 | DMH-E5 | 118.0 | 1.390 | 7.256 | 10.17 | 10.50 | 5.75 | 7.06 | 5.88 | 0.010 | 14.51 | 13.40 |
| DMH-E5 | DMH-E6 | 104.0 | 2.971 | 6.781 | 20.30 | 22.62 | 6.46 | 4.97 | 3.93 | 0.010 | 12.94 | 12.10 |
| DMH-E6 | DMH-E7 | 56.0 | 3.464 | 6.724 | 23.48 | 22.62 | 7.47 | 3.93 | 3.37 | 0.010 | 13.30 | 12.70 |
| DMH-E7 | DMH-G11 | 41.0 | 3.464 | 6.698 | 23.39 | 31.99 | 7.45 | 2.28 | 1.46 | 0.020 | 13.34 | 12.90 |
| DMH-G11 | DMH-G10 | 10.0 | 6.122 | 5.163 | 31.87 | 66.13 | 6.49 | 0.62 | 0.36 | 0.026 | 12.86 | 12.80 |
| DMH-G10 | DMH-G9 | 18.0 | 6.122 | 5.161 | 31.85 | 41.01 | 6.49 | 0.36 | 0.18 | 0.010 | 12.91 | 12.80 |
| DMH-G9 | MH-75 | 128.0 | 49.754 | 3.464 | 173.72 | 0.00 | 7.53 | -12.15 | -12.15 | 0.000 | 8.86 | 8.54 |
| MH-75 | DMH-110 | 82.0 | 49.754 | 3.453 | 173.15 | 405.01 | 7.51 | -3.16 | -3.91 | 0.009 | 8.54 | 8.33 |
| DMH-110 | DMH-111 | 211.0 | 49.754 | 3.445 | 172.79 | 260.76 | 7.50 | -3.91 | -4.71 | 0.004 | 8.10 | 7.57 |
| DMH-111 | O-1 | 67.0 | 49.754 | 3.427 | 171.85 | 258.68 | 7.46 | -4.71 | -4.96 | 0.004 | 5.37 | 5.20 |
| CB-2 | DMH-3 | 20.0 | 0.223 | 7.400 | 1.66 | 3.90 | 4.77 | 7.72 | 7.48 | 0.012 | 8.27 | 7.94 |
| CB-1 | DMH-3 | 72.0 | 0.203 | 7.400 | 1.52 | 3.09 | 3.91 | 7.55 | 7.01 | 0.008 | 8.07 | 7.67 |
| DMH-3 | DMH-4 | 57.0 | 0.426 | 7.336 | 3.15 | 10.13 | 5.06 | 6.91 | 6.38 | 0.009 | 7.59 | 7.18 |
| DMH-4 | O-2 | 218.0 | 0.426 | 7.296 | 3.13 | 10.98 | 5.36 | 6.38 | 4.00 | 0.011 | 7.05 | 4.85 |

C:\Users\rmathews\Documents\0851805 AmPUD 2014-May.stc

Long Term Best Management Practices Checklist

Assembly Square PUD, Somerville, MA

Long Term Best Management Practices – Maintenance/ Evaluation Checklist


| Best Management Practice | Inspection Frequency | Date Inspected | Inspector | Minimum Maintenance and Key Items to Check | Cleaning/Repair Needed <input type="checkbox"/> yes <input type="checkbox"/> no (List Items) | Date of Cleaning/Repair | Performed by |
|---|---|----------------|-----------|---|---|-------------------------|--------------|
| Pavement Sweeping | Minimum four times per year | | | | <input type="checkbox"/> yes <input type="checkbox"/> no | | |
| Catch Basins with Deep Sumps & Oil/Debris Traps | Minimum four times per year | | | Sediment (if more than six inches deep) and/or floatable pollutants shall be pumped from the basin and disposed of at an approved offsite facility in accordance with all applicable regulations. Any structural damage or other indication of malfunction will be reported to the site manager and repaired as necessary. During colder periods, the catch basin grates must be kept free of snow and ice. During warmer periods, the catch basin grates must be kept free of leaves, litter, sand, and debris. | <input type="checkbox"/> yes <input type="checkbox"/> no | | |
| Subsurface Detention System | Monthly for first 3 months then annually | | | All subsurface detention systems shall be inspected at least once each year. If sediment is more than six inches deep, it must be suspended via flushing with clean water and removed using a vactor truck. System will be observed after rainfalls to see if it is properly draining. | <input type="checkbox"/> yes <input type="checkbox"/> no | | |
| Structural Water Quality Devices | Monthly for first 3 months then a minimum four times per year | | | Cleaned a minimum of at least once per year or when sediment depth reaches within six inches of the dry weather water surface elevation. Follow manufacturer instructions for inspection and cleaning and contact manufacturer if system is malfunctioning. | <input type="checkbox"/> yes <input type="checkbox"/> no | | |
| Bioretention Area and Sediment Forebay | 2 times in the first year then annually | | | Invasive plants, weeds, erosion, litter, mulch depth and condition. Weeds and invasive plant species shall be removed by hand. Leaf litter and other detritus shall be removed twice per year. If needed to maintain aesthetic appearance, perennial plantings may be trimmed at the end of the growing season. | <input type="checkbox"/> yes <input type="checkbox"/> no | | |
| Green Roofs | Annually | | | Plant health, replace as necessary. Drains should be examined annually to ensure that they have not become clogged with sediment or organic debris. | <input type="checkbox"/> yes <input type="checkbox"/> no | | |
| Roof Drain Leaders | Quarterly | | | Keep roofs clean and free of debris. Keep roof drainage systems clear. Keep roof access limited to authorized personnel. Clean inlets draining to the subsurface bed twice per year as necessary. | <input type="checkbox"/> yes <input type="checkbox"/> no | | |
| Vegetated Areas | Bi-annually | | | Inspect planted areas on a semi-annual basis and remove any litter. Maintain planted areas adjacent to pavement to prevent soil washout. Immediately clean any soil deposited on pavement. Re-seed bare areas; install appropriate erosion control measures when native soil is exposed or erosion channels are forming. Plant alternative mixture of grass species in the event of unsuccessful establishment. The grass vegetation should not be cut to a height less than four inches. No pesticides are to be used unless a single spot treatment is required for a specific control application. Fertilizer usage should be avoided. If deemed necessary, slow release fertilizer should be used. Fertilizer may be used to begin the establishment of vegetation in bare or damaged areas, but should not be applied on a regular basis unless necessary. | <input type="checkbox"/> yes <input type="checkbox"/> no | | |
| Permeable Pavers | Monthly for first 3 months then annually | | | Vacuum sweeping or pressure wash. Inspect once per year and clean as necessary. Shovel snow off permeable pavers as necessary. Do not apply abrasives such as sand or grit on or adjacent to permeable pavers. Avoid plowing of areas with permeable pavers. | <input type="checkbox"/> yes <input type="checkbox"/> no | | |
| Tide Gate/Stormwater Outfall | Monthly for first 3 months then annually | | | Follow manufacturer instructions for inspection and cleaning and contact manufacturer if system is malfunctioning. Ensure proper functioning and correct any areas that have settled or experienced washouts. | <input type="checkbox"/> yes <input type="checkbox"/> no | | |

Stormwater Control Manager _____



Appendix D

Grading, Drainage, and Utility Plans May 2014 (1 thru 5)



MATCH LINE

[illegible]

| | | | |
|---------------------|--------------------------|-----------------------|-------|
| No. | Revision | Date | Appvd |
| Designed by | Drawn by <i>TAH</i> | Checked by <i>RPM</i> | |
| CAD checked by | Approved by <i>HGH</i> | | |
| Scale 1"=50' | Date May 15, 2014 | | |
| Project Title | | | |

Submission of Amended Preliminary Master Plan

Not Approved for Construction

Grading, Drainage and Utility Plan 1

Drawing Number

C-11

Sheet 11 of 19

Project Number
08518.05



101 Walnut Street, P.O. Box 9151
Watertown, Massachusetts 02471
617.924.1770 • FAX 617.924.228

MATCH LINE



| | | | |
|---------------------|------------------------|-----------------------|----------|
| No. | Revision | Date | Approved |
| Designed by | Drawn by <i>TAH</i> | Checked by <i>RPM</i> | |
| CAD checked by | Approved by <i>HGH</i> | | |
| Scale 1"=50' | Date | May 15, 2014 | |
| Project Title | | | |

Planned Unit Development
Grand Union Boulevard
Somerville, Massachusetts

Issued for
Submission of Amended
Preliminary Master Plan

Not Approved for Construction


Grading, Drainage and Utility Plan 2

Drawing Number


C-12

Sheet 12 of 19

Project Number
08518.05



MATCH LINE

[illegible]

| | | | | |
|---------------------|----------|--------------------------|-----------------------|-------|
| o. | Revision | | Date | Appvd |
| Designed by | | Drawn by <i>TAH</i> | Checked by <i>RPM</i> | |
| AD checked by | | Approved by <i>HGH</i> | | |
| Scale 1"=50' | | Date May 15, 2014 | | |
| Project Title | | | | |

Planned Unit Development
Grand Union Boulevard
Somerville, Massachusetts

Submission of Amended Preliminary Master Plan

Not Approved for Construction

Grading, Drainage
and Utility Plan 3

Drawing Number

C-13

13 of 19

Subject Number
518.05



| | | | |
|---------------|---------------------|------------------------|-------|
| Revision | | Date | Appvd |
| Designed by | Drawn by <i>TAH</i> | Checked by <i>RPM</i> | |
| AD checked by | | Approved by <i>HGH</i> | |
| Scale 1"=50' | | Date May 15, 2014 | |
| Project Title | | | |

Grading, Drainage and Utility Plan 5



Memorandum

To: Rachel Kelly
Somerville Conservation
Commission
Somerville City Hall
93 Highland Avenue
Somerville, MA 02143

Date: February 22, 2017

Project #: 08518.05

From: Dan Meegan, EIT

Re: Block 5B, Notice of Intent
Assembly Row at Assembly Square
Somerville, Massachusetts
Supplemental Memo

This memorandum summarizes the stormwater management system for the proposed Block 5B of the proposed redevelopment of the Assembly Square area in Somerville, Massachusetts, originally presented in the Assembly on the Mystic Proposed 72-inch Storm Drain and Outfall Notice of Intent (NOI) dated November 21, 2008 and issued an Order of Conditions on May 8, 2009. The stormwater management system design remains generally consistent with the stormwater management plan outlined in the previous site plan filings with the City of Somerville Planning Board and Conservation Commission.

As shown on the attached site plans titled "Block 5B" dated February 22, 2017, the proposed building, landscape areas, sidewalks and utility associated infrastructure are in the area of Block 5 and contain less impervious areas than the approved master plan. The drainage patterns Block 5B are essentially unchanged from the August 11, 2011 Roadway NOI submission. As Described in the Roadway NOI, the overall site plan was modified to address design developments since the issuance of the Order of Conditions while maintaining the originally proposed redevelopment program. The modifications included alterations to the site circulation, minor amenity area reconfiguration, and site grading which had direct benefits to the stormwater management system design and function.

With the proposed interim parking lots and associated drainage system additions, the overall stormwater management system for the entire PUD area will continue to maintain peak flows at or below those described in the November 2008 NOI while providing 1-inch water quality treatment in accordance with the Massachusetts Stormwater Handbook as described in the original Outfall NOI Report. Drainage area maps for proposed conditions, Water Quality Unit (WQU) sizing and Total Suspended Solids (TSS) removal calculations are attached.

101 Walnut Street
PO Box 9151
Watertown, MA 02472
P 617.924.1770

Hydrologic Analysis:

Proposed Conditions

All stormwater runoff from the Block 5B will be routed through a series of catch basins with deep sumps and oil/debris traps, proprietary separators and drainage pipe networks on-site and in the right-of-way prior to discharging to the 72-inch outfall (Design Point 6). The stormwater runoff from shared driveway between and adjacent walkways and landscaped areas Block 5B and Block 5A either flow directly to a Stormceptor 450i proprietary water quality unit on site, or is collected by a trench drain that is then directed to the Stormceptor 450i unit, which will provide water quality treatment prior to discharging to an existing drain line in Foley Street through the roadway system that eventually discharges to the 72-inch outfall. The stormwater runoff generated by the roof of the Block 5B building are collected by several roof drains that connect directly into the existing drain lines within Canal Street and Grand Union Boulevard, through the roadway system that eventually discharges to the 72-inch outfall. This runoff pattern is generally unchanged from the November 2008 NOI, though the layout of the roadways has been revised slightly and the Partners Office project has been included instead of the IKEA project on Parcel 11A. An updated version of the previously presented Table 2 provides a summary of the proposed conditions hydrologic data.

Table 2
Proposed Conditions Hydrologic Data

| <i>Description (Drainage Area #)</i> | <i>Discharge Location</i> | <i>Design Point</i> | <i>Area (acres)</i> | <i>Curve Number</i> | <i>Time of Concentration n (min)</i> |
|---|---|--------------------------------|--------------------------------|--------------------------------|---|
| <i>R-1</i> | <i>Existing swale/depression</i> | <i>4</i> | <i>0.5</i> | <i>88</i> | <i>2.8</i> |
| <i>O-1</i> | <i>New 72-inch Outfall Overland to Mystic River</i> | <i>6</i> | <i>63.5</i> | <i>95</i> | <i>16.2</i> |
| <i>S-9</i> | | <i>5</i> | <i>1.8</i> | <i>82</i> | <i>11.5</i> |
| <i>M-1</i> | <i>84-inch SMC</i> | <i>1</i> | <i>9.6</i> | <i>95</i> | <i>5.3</i> |
| <i>M-2</i> | <i>84-inch SMC</i> | <i>1</i> | <i>10.7</i> | <i>97</i> | <i>11.6</i> |
| <i>M-3</i> | <i>84-inch SMC</i> | <i>1</i> | <u><i>2.5</i></u> | <i>95</i> | <i>4.9</i> |
| Total: | | | 88.6 | | |

A revised hydrologic analysis was conducted for the site based on the input parameters described above. As in the previous submission, the rainfall-runoff response of the Site under existing and proposed conditions was evaluated for storm events with recurrence intervals of 2, 10, 25, and 100-years. Rainfall volumes used for this analysis were based on the Natural Resources Conservation Service (NRCS) Type III, 24-hour storm event for Middlesex County. Runoff coefficients for the existing and proposed conditions were determined using NRCS Technical Release 55 (TR-55) methodology as provided in HydroCAD.

Drainage areas used in the analyses are represented above and are depicted on the attached Figures 1 and 2. Figure 1 is unchanged from the November 2008 report. Table 3 presents a summary of the existing and proposed conditions peak discharge rates.

Table 3
Peak Discharge Rates (cubic feet per second)

| Design Point | 2-year | 10-year | 25-year | 100-year |
|---|---------------|----------------|----------------|-----------------|
| Design Point 1: MWRA 84-inch SMC | | | | |
| <i>Existing</i> | 117.8 | 172.1 | 206.9 | 249.2 |
| <i>Proposed</i> | 58.8 | 86.6 | 104.4 | 126.0 |
| Design Point 2: Mystic River (42-inch culvert) | | | | |
| <i>Existing</i> | 2.0 | 2.1 | 2.1 | 2.2 |
| <i>Proposed</i> | 0.0 | 0.0 | 0.0 | 0.0 |
| Design Point 3: Existing Swale/CBs | | | | |
| <i>Existing</i> | 1.3 | 2.1 | 2.7 | 3.3 |
| <i>Proposed</i> | 0.0 | 0.0 | 0.0 | 0.0 |
| Design Point 4: Existing Swale/CBs | | | | |
| <i>Existing</i> | 1.3 | 2.2 | 2.7 | 3.4 |
| <i>Proposed</i> | 1.3 | 2.2 | 2.7 | 3.4 |
| Design Point 5: Mystic River (Overland) | | | | |
| <i>Existing</i> | 29.7 | 50.4 | 63.9 | 80.5 |
| <i>Proposed</i> | 2.7 | 4.8 | 6.2 | 7.9 |
| Design Point 6: New 72-inch Outfall | | | | |
| <i>Existing</i> | 0.0 | 0.0 | 0.0 | 0.0 |
| <i>Proposed</i> | 138.0 | 205.1 | 247.9 | 300.0 |

The revised stormwater management system analyses indicate that there will be a net improvement in terms of the peak rate of discharge and volume of runoff resulting from the site design modifications while maintaining the previous design intent in accordance with the Massachusetts Stormwater Handbook.

Water Quality

The revised stormwater management system provides the required treatment for a 1-inch water quality volume as required. The previously proposed treatment trains for all design points have been maintained. Water quality calculations are proved in Appendix A of the memorandum.

Water quality treatment for Block 5B runoff consists of an operation and maintenance program for water quality measures, a construction phase spill prevention plan and water quality units.

Operation and Maintenance (O&M) Program

A detailed Stormwater O&M program has been prepared for the Project. This plan includes detailed inspection criteria and identifies the responsible parties for implementing the program. In summary, The City of Somerville will be responsible for the maintenance and operation of the street drainage system, including street sweeping, catch basin and manhole cleaning, and maintenance of the street related structures. Federal Realty will be responsible for the maintenance and operation of the Block 5B stormwater management systems including inspection, cleaning and maintenance of the drainage structure, and water quality unit on the site. The maintenance and operation of the 72-inch stormwater outfall, associated tide gate and outfall erosion control measures will be the responsibility of the City of Somerville, in accordance with their EPA NPDES MS4 general permit that covers all stormwater outfalls in the City.

Spill Prevention

A spill prevention and control plan is an important BMP to help minimize potential sources of pollution to ground and surface waters both during construction and as part of the long term operation and maintenance measures of a development. Spill prevention is achieved with the proper storage and handling of hazardous materials. During construction, this is addressed in the Stormwater Pollution Prevention Plan (SWPPP) for Construction Activities to be prepared and implemented by the Site Contractor. The general response procedures for spills at any time are outlined in Chapter 8 of the Final Environmental Impact Report (FEIR) which includes a spill response procedure form, a sample hazardous waste/oil spill report, an emergency response equipment inventory and an emergency notification phone numbers form.

Catch Basins with Sumps and Oil/Debris Traps and Trench Drains

There are no new catch basins proposed in the Project Site. The Project does propose to utilize a trench drain to collect surface stormwater runoff generated by the shared driveway between Blocks 5A and 5B before the runoff flows down the driveway ramp and into the underground garage in Block 5B. The trench drain directs the collected runoff to the water quality unit on Site to remove sediment and debris.

Water Quality Units

The proposed Stormceptor 450i water quality unit serves as treatment for runoff from the Block 5B valet drive and parking garage entrance, prior to discharge to the 72-inch outfall. The stormwater runoff from Block 5B paved areas that drain to the proposed proprietary separator receives TSS and oil removal through these proprietary separators. Proprietary units are key features for TSS removal within dense ultra-urban brownfield redevelopment settings where space is a limiting factor for placement of alternative large scale surface BMPs.

The Contech Vortechs Units throughout the PUD roadways efficiently remove TSS and free oil from the stormwater runoff, including the runoff generated by the Block 5B sidewalks prior to discharging to the 72-inch outfall on the Mystic River. The units prevent the re-suspension of settled material, and allow for safe and easy removal of collected undesirable material.

The water quality units will be inspected four times per year and cleaned a minimum of once per year, or when the sediment depth reaches within six inches of the dry weather water surface elevation.

Compliance with Massachusetts Department of Environmental Protection (DEP) - Stormwater Management Standards

As demonstrated below, the proposed Project fully complies with the DEP Stormwater Management Standards.

Standard 1: No New Untreated Discharges or Erosion to Wetlands

The stormwater runoff tributary to the new 72-inch outfall will receive water quality treatment in conformance with the Best Management Practices outlined in the Stormwater Management Performance Standards and Guidelines. The Block 5B redevelopment will result in improvements to the quality of stormwater discharged from the Project Site. These improvements will be achieved by a combination of structural and non-structural Best Management Practices (BMPs) implemented at the Project Site such as regular pavement sweeping and litter control program, installation of deep-sump catch basins with oil/debris traps and water quality structures. Outfall erosion protection sizing computations were provided in the November 2008 NOI.

Standard 2: Peak Rate Attenuation

The overall Project results in either no increase or a reduction in the peak discharge rate for the 2, 10, 25, and 100-year storm events for Design Points 1 through 5 (DP-1 – DP-5). Design Point 6 (DP-6) is a new design point for the proposed 72-inch outfall which is not present under existing conditions. Since there are no existing flows at this design point, the post-development flows are shown as an increase from existing conditions. However, because the stormwater is discharging into the tidal portion of the Mystic River it is not necessary for post-development peak discharge rates to be equal or less than those in pre-development as outlined in Standard 2 of the Massachusetts DEP Stormwater Management Regulations. The revised peak discharge rates to DP-6 included in Table 3 of this report are less than those presented in the November 2008 NOI, as required by Condition 62 of the May 8, 2009 Order of Conditions. The use of bioretention, subsurface detention and an upgraded drainage system contribute to a peak rate reduction. Appropriate

measures are incorporated to protect against surcharging the system by use of a tide gate and against erosion and turbidity using riprap protection at the outlet. Although this is a new outfall, a large majority of the stormwater discharging at this outfall is not newly generated but is rerouted from the Somerville Marginal Conduit which also discharges below the Amelia Earhart Dam in the tidal portion of the Mystic River.

Standard 3: Stormwater Recharge

The pre-development condition of the Project Site was almost completely impervious and little if any infiltration existed. Also, soil on the Project Site is contaminated, compacted fill material, or poor quality material which makes it unsuitable for infiltration. Additionally, there are no drinking water supplies on or near the Project Site that require recharge. Finally, the Project is located at the terminus of the Mystic River and therefore any infiltration on the site is an insignificant portion of the flows that are supplying the river.

Standard 4: Water Quality

The Project Site is a dense ultra-urban redevelopment on a brownfield site. However, water quality treatment for runoff from the Project Site meets or exceeds the goal of 80 percent TSS Removal. TSS Removal worksheets are included in Attachment A of this memorandum. Due to the urban nature of the Project and the goal for maximizing dense development opportunities, water quality treatment techniques consistent with urban area constraints were selected.

Standard 5: Land Uses with Higher Potential Pollutant Loads (LUHPPLs)

The Project site is a brownfield site which is a LUHPPL. Stormwater management BMP's have been selected and designed to comply with this standard. Under existing conditions infiltration is not currently significant at the Project Site and as described above infiltration is not recommended or proposed. Water quality units, tree filter boxes, bioretention basins, and extensive operations and maintenance requirements address the concerns for LUHPPLs. Minimal surface parking is included on the Project Site with the majority of vehicle parking located in covered garages as part of future Project phases, therefore reducing the effect of the LYHPPL's impervious area to a level of typical roadways.

Standard 6: Critical Areas

The existing MWRA 84-inch SMC and the proposed 72-inch outfall will discharge to a "Prohibited" shellfish growing area. Stormwater discharging to this area is treated for 1-inch of runoff and will utilize the applicable stormwater management BMPs approved for critical areas.

Standard 7: Redevelopments and Other Projects Subject to the Standards only to the Maximum Extent Practicable

The Project, while a redevelopment project as defined by the regulations, fully complies with all applicable stormwater standards. The proposed stormwater management system improves water quality and reduces flow to the frequently surcharged MWRA 84-inch SMC by reducing peak stormwater runoff from the Project Site.

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Controls

The Project will disturb greater than 1 acre of land and is therefore required to obtain coverage under the Environmental Protection Agency (EPA) National Pollutant Discharge Elimination System (NPDES) Construction General Permit. As required under this permit, a Stormwater Pollution Prevention Plan (SWPPP) will be developed and submitted before land disturbance begins. Recommended construction period pollution prevention and erosion and sedimentation controls to be finalized in the SWPPP are unchanged from the November 2008 NOI.

Standard 9: Operation and Maintenance Plan

Recommended practices for operating and maintaining long term stormwater BMPs are unchanged from the November 2008 NOI.

Standard 10: Prohibition of Illicit Discharges

Sanitary sewer and storm drainage structures remaining from previous development which are part of the redevelopment area will be removed or will be incorporated into updated sanitary sewer and separate stormwater sewer systems. The design plans submitted with this report have been designed so that the components included therein are in full compliance with current standards. No statement is made with regard to the drainage and sanitary sewer systems in portions of the site not included in the redevelopment project area. The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges.

Conclusion:

The Stormwater Management Plan presented herein and as shown on the plans provides functionality for Block 5B while maintaining previously submitted design elements and intent. The proposed modifications include Best Management Practices for maintaining stormwater runoff quality both during and after construction, and are designed to protect downstream receiving waters from stormwater related impacts.


Appendix A

Computations and Supporting Information

- Figure 1 – Existing Conditions Drainage Areas
- Figure 2 – Proposed Conditions Drainage Areas
- TSS Removal Worksheets
- Block 5B Stormceptor Design Summary

Saved Tuesday, November 11, 2008 3:51:54 PM WOODMAN Plotted Tuesday, November 11, 2008 3:52:06 PM Goodman, Michael

\\MAWA\LD\08518.05\CAD\LD\ENG\DRAINAGE AREAS\FULL BUILD DRAINAGE FIGURES\08518.05
C:\DRIVE\AREAS\FIGURES\08518.05



Vanasse Hangen Brustlin, Inc.

Transportation
Land Development
Environmental Services

101 Walnut Street, P.O. Box 9151
Watertown, Massachusetts 02471
617.924.1770 • FAX 617.924.2286

| LEGEND | |
|--------|---------------------------------|
| | FOND |
| | DESIGN POINT |
| | REACH |
| | DRAINAGE AREA DESIGNATION |
| | DRAINAGE AREA BOUNDARY |
| | LINE OF CONCENTRATION FLOW LINE |
| | 100' BUFFER ZONE |
| | WETLAND BOUNDARY |
| | 150' W.O.D. BOUNDARY |
| | 300' W.O.D. BOUNDARY |
| | 25' RIVERFRONT BOUNDARY |

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| | | | |
|----------------|-------------------|------------|-------|
| No. | Revision | Date | Appd. |
| Designed by | Drawn by | Checked by | |
| CAD checked by | Approved by | | |
| Scale 1"=150' | Date May 15, 2008 | | |
| Project Title | | | |


Assembly Square
Planned Unit
Development (PUD)
Assembly Square Drive
Somerville, Massachusetts
Issued for
Stormwater Management Report

Not Approved for Construction
Drawing Title

Figure 1
Existing Conditions Full
Build Project Drainage Areas

150 0 150 300
SCALE IN FEET

Drawing Number
F-1
Sheet 1 of 1
Project Number
08518.05



| LEGEND | |
|--------|---------------------------------|
| | POND |
| | DESIGN POINT |
| | REACH |
| | DRAINAGE AREA DESIGNATION |
| | DRAINAGE AREA BOUNDARY |
| | TIME OF CONCENTRATION FLOW LINE |
| | 100' BUFFER ZONE |
| | WETLAND BOUNDARY |
| | 150' W.O.D. BOUNDARY |
| | 300' W.O.D. BOUNDARY |
| | 25' RIVERFRONT BOUNDARY |

Assembly Row
Planned Unit
Development (PUD)

Assembly Row
Somerville, Massachusetts

| No. | Revision | Date | Appr. |
|-----|----------|------|-------|
| | | | |
| | | | |
| | | | |
| | | | |

| | |
|---------------------------------|------------------|
| Designed by | Checked by |
| Issued for | Date |
| Stormwater Management Report | January 27, 2017 |
| Not Approved for Construction | |

Figure 2
Proposed Full Build
Project Drainage Areas

Drawing Number

F-2

Sheet 1 of 1

Project Number
08518.05





VHB, Inc.
101 Walnut Street
Watertown, MA 02471
(617) 924-1770

TSS Removal Calculation Worksheet

Project Name: Block 5B
Project Number: 08518.05
Location: Somerville, MA
Discharge Point: DP-6
Drainage Area(s): Sidewalks & Roads (O-1)

Sheet: 1 OF 1
Date: January 2017
Computed by: DJM
Checked by: PTM

| A | B | C | D | E |
|----------------------------------|-------------------|---------------------|----------------------|----------------------|
| BMP* | TSS Removal Rate* | Starting TSS Load** | Amount Removed (B*C) | Remaining Load (D-E) |
| Street Sweeping - 0% | 0% | 1.00 | 0.00 | 1.00 |
| Deep Sump and Hooded Catch Basin | 25% | 1.00 | 0.25 | 0.75 |
| Existing Water Quality Unit*** | 73% | 0.75 | 0.55 | 0.20 |
| | 0% | 0.20 | 0.00 | 0.20 |
| | 0% | 0.20 | 0.00 | 0.20 |

* BMP and TSS Removal Rate Values from the MassDEP Stormwater Handbook Vol.

** Equals remaining load from previous BMP (E)

*** To be conservative, 73% removal is used for this calculation for the Existing Water Quality Unit.

**Treatment Train
TSS Removal =**

80%



VHB, Inc.
101 Walnut Street
Watertown, MA 02471
(617) 924-1770

TSS Removal Calculation Worksheet

Project Name: Block 5B
Project Number: 08518.05
Location: Somerville, MA
Discharge Point: DP-6
Drainage Area(s): Sidewalks & Roads (O-1)

Sheet: 1 OF 1
Date: January 2017
Computed by: DJM
Checked by: PTM

| A | B | C | D | E |
|---------------------|-------------------|---------------------|----------------------|----------------------|
| BMP* | TSS Removal Rate* | Starting TSS Load** | Amount Removed (B*C) | Remaining Load (D-E) |
| Stormceptor 450i*** | 80% | 1.00 | 0.80 | 0.20 |
| | 0% | 0.20 | 0.00 | 0.20 |
| | 0% | 0.20 | 0.00 | 0.20 |
| | 0% | 0.20 | 0.00 | 0.20 |
| | 0% | 0.20 | 0.00 | 0.20 |

* BMP and TSS Removal Rate Values from the MassDEP Stormwater Handbook Vol.

** Equals remaining load from previous BMP (E)

*** Stormceptor sizing calculation gives a TSS removal rate of 94%. To be conservative, 80% removal is used for this calculation.

**Treatment Train
TSS Removal =**

80%



Stormceptor Design Summary

PCSWMM for Stormceptor

Project Information

| | |
|----------------|-------------------------|
| Date | 12/7/2015 |
| Project Name | Block 5B - Assembly Row |
| Project Number | 08518.11 |
| Location | Somerville, MA |

Designer Information

| | |
|---------|------------|
| Company | VHB |
| Contact | Dan Meegan |

Notes

| |
|-----|
| N/A |
|-----|

Drainage Area

| | |
|--------------------|-----|
| Total Area (ac) | 0.1 |
| Imperviousness (%) | 93 |

The Stormceptor System model STC 450i achieves the water quality objective removing 94% TSS for a Fine (organics, silts and sand) particle size distribution.

Rainfall

| | |
|------------------|----------------|
| Name | BOSTON WSFO AP |
| State | MA |
| ID | 770 |
| Years of Records | 1948 to 2005 |
| Latitude | 42°21'38"N |
| Longitude | 71°0'38"W |

Water Quality Objective

| | |
|-----------------|----|
| TSS Removal (%) | 80 |
|-----------------|----|

Upstream Storage

| Storage (ac-ft) | Discharge (cfs) |
|--------------------|--------------------|
| 0 | 0 |

Stormceptor Sizing Summary

| Stormceptor Model | TSS Removal % |
|-------------------|------------------|
| STC 450i | 94 |
| STC 900 | 97 |
| STC 1200 | 97 |
| STC 1800 | 97 |
| STC 2400 | 98 |
| STC 3600 | 98 |
| STC 4800 | 98 |
| STC 6000 | 98 |
| STC 7200 | 99 |
| STC 11000 | 99 |
| STC 13000 | 99 |
| STC 16000 | 99 |



Particle Size Distribution

Removing silt particles from runoff ensures that the majority of the pollutants, such as hydrocarbons and heavy metals that adhere to fine particles, are not discharged into our natural water courses. The table below lists the particle size distribution used to define the annual TSS removal.

| Fine (organics, silts and sand) | | | | | | | |
|---------------------------------|-------------------|------------------|---------------------------|--|---------------------|-------------------|---|
| Particle Size µm | Distribution % | Specific Gravity | Settling Velocity ft/s | | Particle Size µm | Distribution % | Specific Gravity Settling Velocity ft/s |
| 20 | 20 | 1.3 | 0.0013 | | | | |
| 60 | 20 | 1.8 | 0.0051 | | | | |
| 150 | 20 | 2.2 | 0.0354 | | | | |
| 400 | 20 | 2.65 | 0.2123 | | | | |
| 2000 | 20 | 2.65 | 0.9417 | | | | |

Stormceptor Design Notes

- Stormceptor performance estimates are based on simulations using PCSWMM for Stormceptor.
- Design estimates listed are only representative of specific project requirements based on total suspended solids (TSS) removal.
- Only the STC 450i is adaptable to function with a catch basin inlet and/or inline pipes.
- Only the Stormceptor models STC 450i to STC 7200 may accommodate multiple inlet pipes.
- Inlet and outlet invert elevation differences are as follows:

Inlet and Outlet Pipe Invert Elevations Differences

| Inlet Pipe Configuration | STC 450i | STC 900 to STC 7200 | STC 11000 to STC 16000 |
|--------------------------|----------|---------------------|------------------------|
| Single inlet pipe | 3 in. | 1 in. | 3 in. |
| Multiple inlet pipes | 3 in. | 3 in. | Only one inlet pipe. |

- Design estimates are based on stable site conditions only, after construction is completed.
- Design estimates assume that the storm drain is not submerged during zero flows. For submerged applications, please contact your local Stormceptor representative.
- Design estimates may be modified for specific spills controls. Please contact your local Stormceptor representative for further assistance.
- For pricing inquiries or assistance, please contact Rinker Materials 1 (800) 909-7763 www.rinkerstormceptor.com