


DETAIL-BRICK PAVER WALKWAY & PATIO



TYPICAL PLANTING DETAIL

GENERAL NOTES - LANDSCAPE WORK

1) ALL PLANT MATERIAL SHALL CONFORM TO THE GUIDELINES ESTABLISHED BY "THE AMERICAN STANDARD FOR NURSERY STICK", PUBLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN, LATEST EDITION.

2) NO PLANT SUBSTITUTES SHALL BE ALLOWED WITHOUT PRIOR APPROVAL BY THE ARCHITECT.

3) ALL PLANTS SHALL BE BALLED AND BURLAPPED OR CONTAINER GROWN UNLESS OTHRWISE NOTED ON PLANT LIST.

4) ALL PLANTS SHALL BE APPROVED BY THE ARCHITECT PRIOR TO THEIR INSTALLATION ON THE SITE.


5) REPORT ANY DISCREPANCIES BETWEEN THE DRAWINGS AND THE FIELD CONDITIONS TO THE ARCHITECT PRIOR TO PLANTING.

6) CONTRACTOR SHALL POSITION ALL PLANT MATERIAL IN LOCATIONS SHOWN ON PLANT FOR REVIEW AND ADJUSTMENT BY ARCHITECT. EDGES OF PLANTING BEDS ARE TO BE STAKED. OBTAIN FINAL APPROVAL OF ARCHITECT PRIOR TO PLANTING.

7) CONTRACTOR SHALL LOCATE AND VERIFY ALL BELOW GRADE UTILITY LOCATIONS PRIOR TO PLANTING. ANY CONFLICTS SHALL BE REPORTED TO THE ARCHITECT.

8) ROTOTILL ALL PLANTING BEDS TO DEPTH OF 12" PRIOR TO PREPARATION.

9) PROVIDE 4" SCREENED LOAM FOR ALL PLANTING BEDS.10) PROVIDE MIN 2" DARK MULCH FOR ALL PLANTING BEDS OVER WEED CLOTH.



ARBOR DETAIL

SCALE 3/16" = 1'-0"

CRAGIE STREET (PUBLIC - 50' WIDE)

—6' H FENCE

·DECK

20.0'

UNIT 4

BUILDING 2

UNIT 5

VISITOR SPACE

TRASH

ENCL

BUILDING 3

MULTI-FAMILY

0.0' FRONT SB (ADJUSTED)

42

(3 UNITS, NOS.6-8)

EXTG

3 STY

ELEV = 61.5

1/////

7/////

BIO/INFILTRATION GARDEN

-RETAINING WALL

20.0' REAR SB

22.0'


18.0'

ELEV = 62.0'

LINE OF BLDG ABV

<+ PARKING LVL

20.0'



EXT'G TREE

14.75'

STEPS

UNIT

TYP

PATIO,

ELEV = 70.5'

18.0'

Q____

22.0'

UNIT 3

BUILDING

3 UNITS

UNIT 2

UNIT 1

2-CAR GARAGE BLW,

FIRST FLR=71.5', TYP

UTIL

R41.0'

R27.6'

BACKOUT

18.0'

DRIVEWAY

18.0'

DRIVEWAY

PETER QUINN ARCHI TECTS

ARCHITECTURE
PLANNING
COMMUNITY DESIGN

PETER QUINN ARCHITECTS LLC 1955 MASS AVE, SUITE 4 CAMBRIDGE, MA 02140 PH 617-354-3989 FAX 617-868-0280

SEAL

CONSULTANT

PROJECT

-PROPOSED 5 UNITS

+/- 1,300-SF EACH

LOT AREA

=15.335-SF

PROPOSED NEW —TREES, MIN 3" CALIPER @ PLANTING TYP 8 TREES MIN

GRANITE CURB

/////////

EXT'G TREES TO BE REMOVED

EXT'G TREES TO BE SAVED

8-UNIT DEVELOPMENT 5 NEW & 3 EXT'G

42 CRAIGIE ST SOMERVILLE, MA

PREPARED FOR

FELIX CONSILVIO, JR 42 CRAIGIE STREET LLC 92 HIGH ST, SUITE 27 MEDFORD, MA 02150

DRAWING TITLE

LANDSCAPE PLAN & DETAILS

SCALE AS NOTED

REVISION / ISSUE DATE
ISD SUBM 10 JAN 2008
ISD REVISION 21 JAN 2008

SPSR APPL 11 FEB 2008


SPSR REVISION 13 MAR 2008

SPSR REVISION 11 JUNE 2008

DRAWN BY REVIEWED BY PQ

SHEET

A-1



42 CRAIGIE ST
PROPOSED REVISIONS TO ELEVATION
6/12/08 PQA LLC



REAR YARD ELEVATION BLDG-1 UNIT 1, 2 & 3

REAR YARD ELEVATION BLDG-2 UNIT 4 & 5

SCALE: 1/8" = 1'-0"

SCALE: 1/8" = 1'-0"

42 CRAIGIE ST
PROPOSED REVISIONS TO ELEVATION
6/12/08 PQA LLC