

**LOCATION MAP** 

# APPLICATION FOR SPECIAL PERMIT WITH SITE PLAN REVIEW

# PROPOSED MIXED USE DEVELOPMENT WITH CLIMATE-CONTROLLED STORAGE FACILITY

50 MIDDLESEX AVENUE SOMERVILLE, MASSACHUSETTS



SSG DEVELOPMENT, LLC 651 WASHINGTON STREET, SUITE 200 BROOKLINE, MASSACHUSETTS

PREPARED BY:



ARCHITECTURE ENGINEERING PLANNING LANDSCAPE ARCHITECTURE

LAND SURVEYING ENVIRONMENTAL SCIENCES

355 RESEARCH PARKWAY MERIDEN, CONNECTICUT 06450 (203) 630-1406 (203) 630-2615 Fax

MR. DAVE FULTON SSG DEVELOPMENT, LLC

VICINITY MAP

651 WASHINGTON STREET, SUITE 200 BROOKLINE, MASSACHUSETTS 02446 OFFICE: (617) 938-6478 X202 FAX: (617 278-1552



DATES

ISSUE DATE: MARCH 29, 2011

Companies

ALTA/ACSM LAND TITLE SURVEY CONTEXT MAP OPEN SPACE REQUIREMENT PLAN FUTURE OPEN SPACE REQUIREMENT PLAN SITE PLAN **FUTURE SITE PLAN** GRADING AND DRAINAGE PLAN SITE UTILITIES PLAN EROSION AND SEDIMENTATION CONTROL PLAN EROSION AND SEDIMENTATION CONTROL NOTES


TITLE SHEET

LANDSCAPE AND SITE LIGHTING PLAN FUTURE LANDSCAPE AND SITE LIGHTING PLAN

DETAIL SHEETS DN-1, 2, 3, & 4 LANDSCAPE DETAIL SHEETS DN-5, 6, & 7

CAD FILE: CV08C297801 THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF BL COMPANIE

CONTENTS



THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF BL COMPANIES


Companies

ARCHITECTURE
ENGINEERING
PLANNING
LANDSCAPE ARCHITECTURE
LAND SURVEYING
ENVIRONMENTAL SCIENCES

355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax

CONTEXT MAP

CM-1



## OPEN SPACE REQUIREMENT

AREA #	OPEN SPACE SQUARE FOOTAGE AREA
1	12,125 S.F.
2	1,212 S.F.
3	1,153 S.F.
4	1,097 S.F.
5	522 S.F.
6	228 S.F.
7	126 S.F.
R	2.057 S.F

TOTAL SITE AREA INCL. "OFF-SITE OPEN SPACE"	51,204 S.F.
25% OPEN SPACE AREA REQUIRED	12,801 S.F.
TOTAL OPEN SPACE AREA PROVIDED	18,520 S.F.
% OPEN SPACE AREA PROVIDED	36.17%

## USEABLE OPEN SPACE REQUIREMENT

AREA #	OPEN SPACE SQUARE FOOTAGE AREA
1	12,125 S.F.
2	1,212 S.F.
6	228 S.F.
7	126 S.F.
8	2,057 S.F.

TOTAL SITE AREA INCL. "OFF-SITE OPEN SPACE"	51,204 S.F.
12.5% USEABLE OPEN SPACE AREA REQUIRED	6,401 S.F.
TOTAL USEABLE OPEN SPACE AREA PROVIDED	15,748 S.F.
% USEABLE OPEN SPACE AREA PROVIDED	30.76%



ARCHITECTURE
ENGINEERING
PLANNING
LANDSCAPE ARCHITECTURE
LAND SURVEYING
ENVIRONMENTAL SCIENCES

355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax



SINAL ENGINEERS

SO MIDDLESEX AVENUE

:VISIONS Sate Desc.

Oesigned

Drawn

Checked

Approved

Designed
Drawn
Checked
Approved
Scale
Project No.
Date
3
CAD File:


Project No. 08C2978
Date 3/29/2011
CAD File: 0S08C297801-A

Title
OPEN SPACE
REQUIREMENT

REQUIREMENT PLAN

Sheet No.

OS-1



## OPEN SPACE REQUIREMENT

	AREA #	OPEN SPACE SQUARE FOOTAGE AREA
	1	3,875 S.F.
	2	1,212 S.F.
	3	1,153 S.F.
	4	1,097 S.F.
` .	5	522 S.F.
	6	228 S.F.
	7	126 S.F.
	8	2,057 S.F.
	9	1.214 S.F.

TOTAL SITE AREA INCL. "OFF-SITE OPEN SPACE" (WITHOUT ROADWAY)	44,165 S.F.
25% OPEN SPACE AREA REQUIRED	11,041 S.F.
TOTAL OPEN SPACE AREA PROVIDED	11,484 S.F.
% OPEN SPACE AREA PROVIDED	26.00%

TOTAL SITE AREA INCL. "OFF-SITE OPEN SPACE" (WITHOUT ROADWAY)	44,165 S.F.
25% OPEN SPACE AREA REQUIRED	11,041 S.F.
TOTAL OPEN SPACE AREA PROVIDED	11,484 S.F.
% OPEN SPACE	26.00%

AREA #	OPEN SPACE SQUARE FOOTAGE AREA
1	3,875 S.F.
2	1,212 S.F.
6	228 S.F.
7	126 S.F.
8	2.057 S.F.

AREA #	ROADWAY SQUARE FOOTAGE	AREA
10 ROADWAY	7,039 S.F.	

1,214 S.F.


## USEABLE OPEN SPACE REQUIREMENT

TOTAL SITE AREA INCL. "OFF-SITE OPEN SPACE" (WITHOUT ROADWAY)	44,165 S.F.
12.5% USEABLE OPEN SPACE AREA REQUIRED	6,401 S.F.
TOTAL USEABLE OPEN SPACE AREA PROVIDED	8,712 S.F.
% USEABLE OPEN SPACE AREA PROVIDED	19.73%
	INCL. "OFF-SITE OPEN SPACE" (WITHOUT ROADWAY)  12.5% USEABLE OPEN SPACE AREA REQUIRED  TOTAL USEABLE OPEN SPACE AREA PROVIDED  % USEABLE OPEN SPACE AREA

OPEN SPACE" (WITHOUT ROADWAY)	TT, 100 3.1 .
12.5% USEABLE OPEN SPACE AREA REQUIRED	6,401 S.F.
TOTAL USEABLE OPEN SPACE AREA PROVIDED	8,712 S.F.
% USEABLE OPEN SPACE AREA PROVIDED	19.73%

Companies
ARCHITECTURE ENGINEERING PLANNING LANDSCAPE ARCHITECTURE LAND SURVEYING ENVIRONMENTAL SCIENCES
以中央中央中央中央中央中央中央中央中央中央中央中央中央中央中央中央中央中央中央


355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax



08C2978 3/29/2011 CAD File: 0508C297801-A

FUTURE OPEN SPACE
REQUIREMENT
PLAN

AREA # SQUARE FOOTAGE AREA  10 ROADWAY 7,039 S.F.		
S 97.86 VCC CONCRETE WALK 8"METAL INV OUT 94.55 87.45	CS RIM EL 96.81  TOPLOF METAL HOOD EL 94.52  97.40 VGC 97.67  96.97 QG 96.83	97.86
DMH RIM EL. 98.34  6°CAS NE   6°C	OMH RIM EL. 97.74 ROP OF WATER EL. 93.69  HI 6°GAS LINE GAS	GAS —
ERS  ON  ON  ON  ON  ON  ON  ON  ON  ON  O	TWO (A: AND City Street (a) 12"RCP INV EL. 90.28 12"RCP INV EL. 90.28 12"RCP INV EL. 90.28 12"RCP INV EL. 91.06 12"RCP INV EL. 91.06 12"RCP INV EL. 91.32 22 22 22 22 22 22 22 22 22 22 22 22 2	AREA 6  Sen
PROP D D D D BB.30 D D D BB.30 D D D BB.30 D D D D D D D D D D D D D D D D D D D	GOY UPW/LT. GATE  OHW LOW PW TO THE T	ON TOWN OHW
RRM POLE GUY SUPPORT APPROXIMATE LIPPOSSIBLE ENGRO. SEE NOTE SH 2	PROPOSED 98.44  SELF STORAGE FACILITY	18' PROPOSED AREA 8 OPEN OPEN OPEN OPEN OPEN OPEN OPEN OPEN
AREA 14	135,295 ± S.F.  REQUIRED PARKING - 93 SPACES PROPOSED PARKING - 18 SPACES PFE-98.45±	BITUMINDUS CONCRETE PAVEMENT  OF CAN'T CAN
TOP OF MARIN PROPERTY OF THE P	SR.533  SPORT ON G  STORY ON G	GAS
18 +97.23 	AREA 5 13' 30' 17/16-18-18-18-18-18-18-18-18-18-18-18-18-18-	GAS
AREA 2	PACCESS WARTE BEANGES CLEAR 17.76 CLEAR GAS GAS CLEAR GA	Company of the state of the sta
GRASS OF FAREMENT TO STATE OF	ONORETE 98.78  ONORETE PAVEMENT GAS TROUBLE PAVEMEN	OMP AM E. B. 28.472  Jac Roy and E. 24.22  Jac Roy and E. 24.22  Jac Roy and E. 24.22
The state of the s	MyStiC NID ROSTIGET AND WIDE CITY STEEL OF THE CITY OF	
100 03 Color	GAS LINE GAS LINE GAS STORE STORE SAND TWO STORE SAND STORE SAND STORE SAND SAND STORE SAND SAND SAND SAND SAND SAND SAND SAND	
THE TOTAL TO SEE THE PROOF OF T	The state of the s	GRAPHIC SCALE 20 10 0 20 SCALE IN FEET
©2008 BL COMPANIES, INC. THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF BL COMPANIES		



**ARCHITECTURE ENGINEERING** PLANNING LANDSCAPE ARCHITECTURE LAND SURVEYING **ENVIRONMENTAL SCIENCES** 

> 355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax



 $\mathbf{m}$ S


Checked Approved Scale

08C2978 Project No 3/29/2011

CAD File: DM08C297801

Sheet No.

DEMOLITION



**ARCHITECTURE ENGINEERING** ANDSCAPE ARCHITECTURE


> Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax



05 A §§§

A.B.U. 1"=30' 08C2978 3/29/2011

SP-1



©2008 BL COMPANIES, INC. THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF BL COMPANIE

**ARCHITECTURE ENGINEERING** LANDSCAPE ARCHITECTURE LAND SURVEYING

> 355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax

**ENVIRONMENTAL SCIENCES** 




DING.  $\mathbf{\Omega}$ 

Designed A.B.U. Checked 08C2978 3/29/2011

CAD File: SP08C297802

**FUTURE SITE PLAN** 

SP-2





ARCHITECTURE ENGINEERING PLANNING LANDSCAPE ARCHITECTURE LAND SURVEYING **ENVIRONMENTAL SCIENCES** 

> 355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax



BUILDING SED SELF-STORAGE 50 MIDDLESEX AVENUE .E, MASSACHUSETTS, MIDDL **PROPO** 

Drawn Checked Approved Scale

08C2978 Project N 3/29/2011 CAD File: GD09C297801

**GRADING AND** 

DRAINAGE PLAN

GD-

Companies

ARCHITECTURE
ENCINEERING

ARCHITECTURE
ENGINEERING
PLANNING
LANDSCAPE ARCHITECTURE
LAND SURVEYING
ENVIRONMENTAL SCIENCES

355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax



PROPOSED SELF-STORAGE BUILDING
50 MIDDLESEX AVENUE
SOMERVILLE, MASSACHUSETTS, MIDDLESEX COUNT

Designed
Drawn
Checked
Approved


A.B.U.
A.B.U.

1"=30'
0. 08C2978
3/29/2011

CAD File:
SU08C297801
parameters are all the latest and the latest


SITE UTILITIES
PLAN

SU-1



ARCHITECTURE PLANNING LANDSCAPE ARCHITECTURE LAND SURVEYING **ENVIRONMENTAL SCIENCES** 

355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax



BUILDING

08C2978

CAD File: EC08C297801

**SEDIMENTATION** AND EROSION **CONTROL PLAN** 

EC-1

THE ANTICIPATED STARTING DATE FOR CONSTRUCTION IS JUNE 2010 WITH COMPLETION ANTICIPATED AUGUST 2010. APPROPRIATE EROSION CONTROL MEASURES AS DESCRIBED HEREIN, SHALL BE INSTALLED BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF ALL DEMOLITION OR CONSTRUCTION ACTIVITY. SCHEDULE WORK TO MINIMIZE THE LENGTH OF TIME THAT BARE SOIL WILL BE EXPOSED.

#### CONTINGENCY EROSION PLAN

THE CONTRACTOR SHALL INSTALL ALL SPECIFIED EROSION CONTROL MEASURES AND WILL BE REQUIRED TO MAINTAIN THEM IN THEIR INTENDED FUNCTIONING CONDITION. THE AGENTS OF THE UNIVERSITY OF MASSACHUSETTS AND/OR CIVIL ENGINEER SHALL HAVE THE AUTHORITY TO REQUIRE SUPPLEMENTAL MAINTENANCE OR ADDITIONAL MEASURES IF FIELD CONDITIONS ARE ENCOUNTERED BEYOND WHAT WOULD NORMALLY BE ANTICIPATED.

#### CONSTRUCTION SEQUENCE

THE FOLLOWING CONSTRUCTION SEQUENCE IS RECOMMENDED 1. CONTACT UNIVERSITY OF MASSACHUSETTS AGENT AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO COMMENCEMENT OF ANY DEMOLITION, CONSTRUCTION OR REGULATED ACTIVITY ON THIS PROJECT.

2. CLEARING LIMITS SHALL BE PHYSICALLY MARKED IN THE FIELD AND APPROVED BY THE UNIVERSITY OF MASSACHUSETTS AGENT PRIOR TO THE START OF WORK ON THE SITE. INSTALL TREE PROTECTION AND PERIMETER SILT FENCE.

3. INSTALL SILT SACKS ON CATCH BASIN INLETS. INSTALL SILT FENCE AND OTHER EROSION CONTROL DEVICES INDICATED ON THESE PLANS AT PERIMETER OF PROPOSED SITE DISTURBANCE AND INSTALL ALL EROSION CONTROL MEASURES AND TREE PROTECTION INDICATED ON THESE PLANS.

- 4. STOCKPILE TOPSOIL. INSTALL EROSION CONTROLS AT STOCKPILES.
- 5. SITE DEMOLITION AND REMOVAL. PAVEMENT REMOVAL AND RECLAMATION.
- 6. INSTALL SILT FENCE. COMMENCE RESETTING OF STORM DRAINAGE SYSTEM.

7. COMMENCE EARTHWORK. CONSTRUCT PAVEMENT SUBGRADE. INSTALL ADDITIONAL EROSION CONTROLS AS WORK PROGRESSES AND CONTINUE STORM DRAINAGE SYSTEM CONSTRUCTION, TOPSOIL AND SEED SLOPES WHICH HAVE ACHIEVED FINAL SITE

- 8. CONSTRUCTION STAKING OF ALL PARKING AREA CORNERS AND ACCESS DRIVES.
- 9. ROUGH GRADING AND FILLING OF SUBGRADES AND SLOPES.

10.IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION.

11. BEFORE DISPOSING OF SOIL OR RECEIVING BORROW FOR THE SITE, THE CONTRACTOR MUST PROVIDE EVIDENCE THAT EACH SPOIL OR BORROW AREA HAS AN EROSION AND SEDIMENT CONTROL PLAN APPROVED BY THE UNIVERSITY OF MASSACHUSETTS, AND WHICH IS BEING IMPLEMENTED AND MAINTAINED. THE CONTRACTOR SHALL ALSO NOTIFY THE UNIVERSITY OF MASSACHUSETTS IN WRITING OF ALL RECEIVING SPOIL AND BORROW AREAS WHEN THEY HAVE BEEN IDENTIFIED.

12. THROUGHOUT CONSTRUCTION SEQUENCE, REMOVE SEDIMENT FROM BEHIND SILT FENCES AND OTHER EROSION CONTROL DEVICES, AS REQUIRED, REMOVAL SHALL BE ON A PERIODIC BASIS (EVERY SIGNIFICANT RAINFALL OF 0.10 INCH OR GREATER). INSPECTION OF EROSION CONTROL MEASURES SHALL BE ON A WEEKLY BASIS AND AFTER EACH RAINFALL OF 0.10 INCHES OF GREATER. SEDIMENT COLLECTED SHALL BE DEPOSITED AND SPREAD EVENLY UPLAND ON SLOPES DURING CONSTRUCTION.

- COMPLETE GRADING TO SUBGRADES AND CONSTRUCT PARKING AREA SUBGRADE.
- 14. CONSTRUCT CURBS AND PAVEMENT STRUCTURES.
- 15. CONDUCT FINE GRADING.
- 16. PAVING OF PARKING AREAS AND DRIVEWAYS.
- 17. FINAL FINE GRADING OF SLOPE AND NON-PAVED AREAS.

18. PLACE 4" TOPSOIL ON SLOPES AFTER FINAL GRADING IS COMPLETED. FERTILIZE SEED AND MULCH. SEED MIXTURE TO BE INSTALLED APRIL 15 - JUNE 1 OR AUGUST 15-OCTOBER 1 USE EROSION CONTROL BLANKETS AS REQUIRED OR ORDERED FOR SLOPES GREATER THAN 3:1 AND AS SHOWN ON LANDSCAPE PLANS OR EROSION CONTROL PLANS. FOR TEMPORARY STABILIZATION BEYOND SEEDING DATES USE ANNUAL RYE AT 4.0 LBS/1,000 S.F. FERTILIZE WITH 10-10-10 AT 1.0 LBS. OF NITROGEN PER 1,000 S.F. AND LIME AT 100 LBS/1,000 S.F. (MAX.).

#### 19. LANDSCAPE PERIMETER AREAS.

20. INSTALL SIGNING AND PAVEMENT MARKINGS

21. CLEAN STORM DRAINAGE PIPE STRUCTURES, DETENTION SYSTEMS AND WATER QUALITY DEVICES OF DEBRIS AND SEDIMENT. 22. UPON DIRECTION OF THE UNIVERSITY OF MASSACHUSETTS AGENT, EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED FOLLOWING STABILIZATION OF THE SITE OPERATION REQUIREMENTS

#### CLEARING AND GRUBBING OPERATIONS

. ALL SEDIMENTATION AND EROSION CONTROL MEASURES, WILL BE INSTALLED PRIOR TO THE START OF CLEARING AND GRUBBING AND DEMOLITION OPERATIONS.

2. FOLLOWING INSTALLATION OF ALL SEDIMENTATION AND EROSION CONTROL MEASURES, THE CONTRACTOR SHALL NOT PROCEED WITH GRADING, FILLING OR OTHER CONSTRUCTION OPERATIONS UNTIL THE ENGINEER HAS INSPECTED AND APPROVED

3. THE CONTRACTOR SHALL TAKE EXTREME CARE DURING CLEARING AND GRUBBING OPERATIONS SO AS NOT TO DISTURB UNPROTECTED WETLAND AREAS OR SEDIMENTATION AND EROSION CONTROL DEVICES.

4. FOLLOWING THE COMPLETION OF CLEARING AND GRUBBING OPERATIONS, ALL AREAS SHALL BE STABILIZED WITH TOPSOIL AND SEEDING OR PROCESSED AGGREGATE STONE AS SOON AS PRACTICAL.

#### ROUGH GRADING OPERATIONS

1. DURING THE REMOVAL AND/OR PLACEMENT OF EARTH AS INDICATED ON THE GRADING PLAN, TOPSOIL SHALL BE STRIPPED AND APPROPRIATELY STOCKPILED FOR REUSE.

#### 2. ALL STOCKPILED TOPSOIL SHALL BE SEEDED, MULCHED WITH HAY, AND ENCLOSED BY A SILTATION FENCE.

FILLING OPERATIONS 1. PRIOR TO FILLING, ALL SEDIMENTATION AND EROSION CONTROL DEVICES SHALL BE PROPERLY IMPLEMENTED, MAINTAINED

2. ALL FILL MATERIAL ADJACENT TO ANY WETLAND AREAS, IF APPLICABLE TO THIS PROJECT, SHALL BE GOOD QUALITY, WITH LESS THAN 5% FINES PASSING THROUGH A #200 SIEVE (BANK RUN). SHALL BE PLACED IN LIFT THICKNESSES NOT GREATER THAN THAT SPECIFIED IN PROJECT SPECIFICATIONS AND/OR THE PROJECT GEOTECHNICAL REPORT. LIFTS SHALL BE COMPACTED TO 95% MAX. DRY DENSITY MODIFIED PROCTOR OR AS SPECIFIED IN THE CONTRACT SPECIFICATIONS OR IN THE GEOTECHNICAL

#### PLACEMENT OF DRAINAGE STRUCTURES, UTILITIES, AND CONSTRUCTION OPERATIONS

AND FULLY INSTALLED, AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THIS PLAN.

1. SILT FENCES SHALL BE INSTALLED AT THE DOWNHILL SIDES OF EXCAVATIONS, AND MATERIAL STOCKPILES. HAY BALES MAY BE USED IF SHOWN ON THE EROSION CONTROL PLANS OR IF DIRECTED BY THE CIVIL ENGINEER.

#### FINAL GRADING AND PAVING OPERATIONS

. ALL INLET AND OUTLET PROTECTION SHALL BE PLACED AND MAINTAINED AS SHOWN ON EROSION CONTROL PLANS AND DETAILS, AND AS DESCRIBED IN SPECIFICATIONS AND AS DESCRIBED HEREIN.

2. NO CUT OR FILL SLOPES SHALL EXCEED 2:1 EXCEPT WHERE STABILIZED BY ROCK FACED EMBANKMENTS OR EROSION CONTROL BLANKETS, JUTE MESH AND VEGETATION. ALL SLOPES SHALL BE SEEDED, AND ANY ROAD OR DRIVEWAY SHOULDER AND BANKS SHALL BE STABILIZED IMMEDIATELY UPON COMPLETION OF FINAL GRADING UNTIL TURF IS ESTABLISHED.

- 3. PAVEMENT SUB-BASE AND BASE COURSES SHALL BE INSTALLED OVER AREAS TO BE PAVED AS SOON AS FINAL SUB-GRADES ARE ESTABLISHED AND UNDERGROUND UTILITIES AND STORM DRAINAGE SYSTEMS HAVE BEEN INSTALLED.
- 4. AFTER CONSTRUCTION OF PAVEMENT, TOPSOIL, FINAL SEED, MULCH AND LANDSCAPING, REMOVE ALL TEMPORARY EROSION CONTROL DEVICES ONLY AFTER ALL AREAS HAVE BEEN PAVED AND/OR GRASS HAS BEEN WELL ESTABLISHED AND THE SITE HAS BEEN INSPECTED AND APPROVED BY THE UNIVERSITY OF MASSACHUSETTS.

#### INSTALLATION OF SEDIMENTATION AND EROSION CONTROL MEASURES

A. DIG A SIX INCH TRENCH ON THE UPHILL SIDE OF THE DESIGNATED FENCE LINE LOCATION.

B. POSITION THE POST AT THE BACK OF THE TRENCH (DOWNHILL SIDE), AND HAMMER THE POST AT LEAST 1.5 FEET INTO THE GROUND.

C. LAY THE BOTTOM SIX INCHES OF THE FABRIC INTO THE TRENCH TO PREVENT UNDERMINING BY STORM WATER RUN-OFF. D. BACKFILL THE TRENCH AND COMPACT

#### OPERATION AND MAINTENANCE OF SEDIMENTATION AND EROSION

#### CONTROL MEASURES

I. SILTATION FENCE A. ALL SILTATION FENCES SHALL BE INSPECTED AS A MINIMUM WEEKLY OR AFTER EACH RAINFALL. ALL DETERIORATED FABRIC AND DAMAGED POSTS SHALL BE REPLACED AND PROPERLY REPOSITIONED IN ACCORDANCE WITH THIS PLAN.

B. SEDIMENT DEPOSITS SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THEY EXCEED A HEIGHT OF ONE FOOT.

EROSION AND SEDIMENT CONTROL PLAN 1. SILT FENCE WILL BE INSTALLED ALONG THE TOE OF ALL CRITICAL CUT AND FILL SLOPES.

2. CATCH BASINS WILL BE PROTECTED WITH SILT SACKS OR OTHER INLET PROTECTION DEVICES PER DETAILS, THROUGHOUT THE CONSTRUCTION PERIOD AND UNTIL ALL DISTURBED AREAS ARE THOROUGHLY STABILIZED.

3. ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS OF THE MASSACHUSETTS EROSION AND SEDIMENT CONTROL GUIDELINES FOR URBAN AND SUBURBAN AREA LATEST EDITION

4. EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED PRIOR TO DEMOLITION AND/OR CONSTRUCTION WHENEVER

5. ALL CONTROL MEASURES WILL BE MAINTAINED IN EFFECTIVE CONDITION THROUGHOUT THE DEMOLITION AND CONSTRUCTION

6. ADDITIONAL CONTROL MEASURES WILL BE INSTALLED DURING THE CONSTRUCTION PERIOD, IF NECESSARY OR REQUIRED OR AS DIRECTED BY THE ENGINEER OR BY UNIVERSITY OF MASSACHUSETTS.

INTENT AND REQUIREMENTS OF THE EROSION CONTROL PLANS, NOTES, AND DETAILS. 8. THE CONTRACTOR IS ASSIGNED THE RESPONSIBILITY FOR IMPLEMENTING THIS EROSION AND SEDIMENT CONTROL PLAN, THIS RESPONSIBILITY INCLUDES THE INSTALLATION AND MAINTENANCE OF CONTROL MEASURES, INFORMING ALL PARTIES ENGAGED ON THE CONSTRUCTION SITE OF THE REQUIREMENTS AND OBJECTIVES OF THE PLAN, NOTIFICATION OF THE UNIVERSITY OF MASSACHUSETTS. OFFICE OR GOVERNING AUTHORITY OF ANY TRANSFER OF THIS RESPONSIBILITY AND FOR

7. SEDIMENT REMOVED FROM EROSION CONTROL STRUCTURES WILL BE DISPOSED IN A MANNER WHICH IS CONSISTENT WITH THE

#### SEDIMENT AND EROSION CONTROL NOTES

 THE SEDIMENT AND EROSION CONTROL PLAN IS ONLY INTENDED TO DESCRIBE THE SEDIMENT AND EROSION CONTROL TREATMENT FOR THIS SITE. SEE SEDIMENT AND EROSION CONTROL DETAILS AND CONSTRUCTION SEQUENCE. REFER TO SITE PLAN FOR GENERAL INFORMATION AND OTHER CONTRACT PLANS FOR APPROPRIATE INFORMATION.

CONVEYING A COPY OF THE EROSION AND SEDIMENT CONTROL PLAN IF THE TITLE TO THE LAND IS TRANSFERRED.

2. THE CONTRACTOR IS RESPONSIBLE FOR IMPLEMENTING THIS SEDIMENT AND EROSION CONTROL PLAN. THIS RESPONSIBILITY INCLUDES THE PROPER INSTALLATION AND MAINTENANCE OF EROSION CONTROL MEASURES, INFORMING ALL PARTIES ENGAGED WITH CONSTRUCTION ON THE SITE OF THE REQUIREMENTS AND OBJECTIVES OF THIS PLAN, INFORMING THE GOVERNING AUTHORITY OR INLAND WETLANDS AGENCY OF ANY TRANSFER OF THIS RESPONSIBILITY, AND FOR CONVEYING A COPY OF THE SEDIMENT & EROSION CONTROL PLAN IF THE TITLE TO THE LAND IS TRANSFERRED.

3. VISUAL SITE INSPECTIONS SHALL BE CONDUCTED WEEKLY, AND AFTER EACH MEASURABLE PRECIPITATION EVENT OF 0.50 INCHES OR GREATER BY QUALIFIED PERSONNEL, TRAINED AND EXPERIENCED IN EROSION AND SEDIMENT CONTROL, TO ASCERTAIN THAT THE EROSION AND SEDIMENT CONTROL (E&S) BMPS ARE OPERATIONAL AND EFFECTIVE IN PREVENTING POLLUTION. A WRITTEN REPORT OF EACH INSPECTION SHALL BE KEPT, AND INCLUDE: A)A SUMMARY OF THE SITE CONDITIONS, E&S BMPS, AND COMPLIANCE; AND

B) THE DATE, TIME, AND THE NAME OF THE PERSON CONDUCTING THE INSPECTION

4. THE CONTRACTOR SHALL CONSTRUCT ALL SEDIMENT AND EROSION CONTROLS IN ACCORDANCE WITH MASSACHUSETTS EROSION AND SEDIMENT CONTROL GUIDELINES FOR URBAN AND SUBURBAN AREAS LATEST EDITION IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, AND AS DIRECTED BY THE UNIVERSITY OF MASSACHUSETTS. THE CONTRACTOR SHALL KEEP A COPY OF THE GUIDELINES ON-SITE FOR REFERENCE DURING CONSTRUCTION.

ADDITIONAL AND/OR ALTERNATIVE SEDIMENT AND EROSION CONTROL MEASURES MAY BE INSTALLED DURING THE CONSTRUCTION PERÍOD IF FOUND NECESSARY BY THE CONTRACTOR, UMASS FACILITIES PLANNING, SITE ENGINEER, OR GOVERNING AGENCIES. THE CONTRACTOR SHALL CONTACT THE UMASS FACILITIES PLANNING AND APPROPRIATE GOVERNING AGENCIES FOR APPROVAL IF ALTERNATIVE CONTROLS OTHER THAN THOSE SHOWN ON THE PLANS ARE PROPOSED.

6. THE CONTRACTOR SHALL INSPECT ALL SEDIMENT AND EROSION CONTROLS BEFORE AND AFTER EACH STORM (0.10 INCHES OR GREATER RAINFALL), OR AT LEAST WEEKLY, TO VERIFY THAT THE CONTROLS ARE OPERATING PROPERLY AND MAKE

7. THE CONTRACTOR SHALL KEEP A SUPPLY OF EROSION CONTROL MATERIAL (SILT FENCE, ETC.) ON-SITE FOR MAINTENANCE 8. PROTECT EXISTING TREES THAT ARE TO BE SAVED BY FENCING AT THE DRIP LINE OR AS SHOWN WITH SNOW FENCE,

ORANGE SAFETY FENCE, OR EQUIVALENT FENCING. ANY LIMB TRIMMING SHOULD BE DONE BEFORE CONSTRUCTION BEGINS IN THAT AREA; FENCING SHALL BE MAINTAINED AND REPAIRED DURING CONSTRUCTION.

9. INSTALL PERIMETER SEDIMENT CONTROLS PRIOR TO CLEARING OR CONSTRUCTION. ALL CONSTRUCTION SHALL BE CONTAINED WITHIN THE LIMIT OF DISTURBANCE, WHICH SHALL BE MARKED WITH SILT FENCE, SAFETY FENCE, RIBBONS, OR OTHER MEANS PRIOR TO CLEARING. CONSTRUCTION ACTIVITY SHALL REMAIN ON THE UPHILL SIDE OF THE SILT FENCE UNLESS WORK IS SPECIFICALLY CALLED FOR ON THE DOWNHILL SIDE OF THE FENCE.

10. TOPSOIL SHALL BE STRIPPED AND STOCKPILED FOR USE IN FINAL LANDSCAPING. ALL EARTH STOCKPILES SHALL HAVE HAY BALES OR SILT FENCE AROUND THE LIMIT OF PILE. PILES SHALL BE TEMPORARILY SEEDED IF PILE IS TO REMAIN IN

11. COMPLY WITH REQUIREMENTS OF <u>NPDES GENERAL PERMIT FOR CONSTRUCTION DEWATERINGS ACTIVITY DISCHARGES</u>, FOR STORMWATER DISCHARGE FROM CONSTRUCTION ACTIVITIES AND WITH MASSACHUSETTS DEP RECORD KEEPING AND INSPECTION

12. MINIMIZE LAND DISTURBANCES. SEED AND MULCH DISTURBED AREAS WITH TEMPORARY MIX AS SOON AS PRACTICABLE (2 WEEK MAXIMUM UNSTABILIZED PERIOD) USING PERENNIAL RYEGRASS AT 40 LBS PER ACRE. MULCH ALL CUT AND FILL SLOPES AND SWALES WITH LOOSE HAY AT A RATE OF 2 TONS PER ACRE. IF NECESSARY, REPLACE LOOSE HAY ON SLOPES WITH EROSION CONTROL BLANKETS OR JUTE CLOTH, MODERATELY GRADED AREAS, ISLANDS, AND TEMPORARY CONSTRUCTION STAGING AREAS MAY BE HYDROSEEDED WITH TACKIFIER.

13. MAINTAIN EXISTING PAVED AREAS FOR CONSTRUCTION STAGING FOR AS LONG AS POSSIBLE. REMOVE AND REUSE BROKEN PAVEMENT LATER DURING ROUGH GRADING EARTHWORK PHASE IF INDICATED ON GRADING PLANS.

14. SILT FENCE AND OTHER SEDIMENT CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH CONTRACT DRAWINGS AND MANUFACTURER'S RECOMMENDATIONS PRIOR TO WORK IN ANY UPLAND AREAS. 15. INSTALL SILT FENCE ACCORDING TO MANUFACTURER'S INSTRUCTION, PARTICULARLY, BURY LOWER EDGE OF FABRIC INTO GROUND. SILT FENCE SHALL BE MIRAFI ENVIROFENCE, AMOCO SILT STOP OR EQUIVALENT APPROVED BY THE ENGINEER. FILTER

FABRIC USED SHALL BE MIRAFI 100X OR EQUIVALENT. SEE SPECIFICATIONS FOR FURTHER INFORMATION. 6. DIRECT ALL DEWATERING PUMP DISCHARGE TO A SEDIMENT CONTROL DEVICE SUCH AS TEMPORARY PITS, OR GRASS FILTERS WITHIN THE APPROVED LIMIT OF DISTURBANCE. DISCHARGE TO STORM DRAINAGE SYSTEM OR SURFACE WATERS FROM

SEDIMENT CONTROLS SHALL BE CLEAR. 17. SWEEP AFFECTED PORTIONS OF OFF SITE ROADS ONE OR MORE TIMES A DAY (OR LESS FREQUENTLY IF TRACKING IS NOT A PROBLEM) DURING CONSTRUCTION. OTHER DUST CONTROL MEASURES TO BE USED AS NECESSARY INCLUDE WATERING DOWN

DISTURBED AREAS, USING CALCIUM CHLORIDE, AND COVERING LOADS ON DUMP TRUCKS. 18. CLEAN ACCUMULATED SEDIMENT FROM CATCH BASIN SUMPS AS NECESSARY AND AS DIRECTED BY THE CIVIL ENGINEER OR OWNER'S CONSTRUCTION REPRESENTATIVE. REMOVE ACCUMULATED SEDIMENT FROM BEHIND SILT FENCE WHEN LEVEL REACHES ONE FOOT AT SILT FENCE. DISPOSE OF SEDIMENT LEGALLY EITHER ON OR OFF SITE.

19.IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION.

20. ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE THROUGH A SEDIMENT CONTROL BMP, SUCH AS A PUMPED WATER FILTER BAG OR EQUIVALENT SEDIMENT REMOVAL FACILITY, OVER UNDISTURBED VEGETATED AREAS.

21. ANY STOCKPILES OF STRIPPED MATERIALS ARE TO BE PERIODICALLY SPRAYED WITH WATER OR A CRUSTING AGENT TO

STABILIZE POTENTIALLY WIND-BLOWN MATERIAL. HAUL ROADS BOTH INTO AND AROUND THE SITE ARE TO BE SPRAYED AS NEEDED TO SUPPRESS DUST. TRUCKS HAULING IMPORT FILL MATERIAL ARE TO BE TARPED TO AID IN THE CONTROL OF AIRBORNE DUST. DURING HIGH WIND EVENTS (20 TO 30 MPH SUSTAINED) CONSTRUCTION ACTIVITY SHALL BE LIMITED OR CEASED IF DUST CANNOT BE CONTROLLED BY WETTING.

22. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM OF 70% UNIFORM PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING OR OTHER MOVEMENTS.

23. MAINTAIN ALL PERMANENT AND TEMPORARY SEDIMENT CONTROL DEVICES IN EFFECTIVE CONDITION THROUGHOUT THE CONSTRUCTION PERIOD. UPON COMPLETION OF WORK SWEEP PARKING LOT AND REMOVE ALL TEMPORARY SEDIMENT CONTROLS WHEN AUTHORIZED BY LOCAL GOVERNING AUTHORITY. FILE NOT (NOTICE OF TERMINATION) WITH GOVERNING AUTHORITY RESPONSIBLE FOR REGULATING STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES PER NPDES.

24. STONE CONSTRUCTION ENTRANCE ANTI-TRACKING PADS SHALL BE INSTALLED AT THE START OF CONSTRUCTION AND MAINTAINED THROUGHOUT THE DURATION OF CONSTRUCTION. THE LOCATION OF THE TRACKING PADS MAY CHANGE AS VARIOUS PHASES OF CONSTRUCTION ARE COMPLETED.

#### MASSACHUSETTS SWPPP NOTES:

THE CONTRACTOR MUST PREPARE THE SWPPP AND SUBMIT THE EPA NOTICE OF INTENT AND NOTICE OF TERMINATION PRIOR TO AND UPON THE COMPLETION OF THE PROJECT. THE SWPPP MUST BE REVIEWED AND APPROVED BY THE ENGINEER AND

#### POLLUTION PREVENTION PLAN CONTENTS: CONTROLS TO REDUCE POLLUTANTS

A. THE SWPPP MUST INCLUDE A DESCRIPTION OF ALL POLLUTION CONTROL MEASURES (I.E., BMPS) THAT WILL BE IMPLEMENTED AS PART OF THE CONSTRUCTION ACTIVITY TO CONTROL POLLUTANTS IN STORM WATER DISCHARGES. FOR EACH MAJOR ACTIVITY IDENTIFIED IN THE PROJECT DESCRIPTION, THE SWPPP MUST CLEARLY DESCRIBE CONTROL MEASURES NECESSARY TO COMPLY WITH THIS PERMIT AND APPLICABLE LAWS AND REGULATIONS, THE GENERAL SEQUENCE DURING THE CONSTRUCTION PROCESS IN WHICH THE MEASURES WILL BE IMPLEMENTED, AND WHICH OPERATOR IS RESPONSIBLE FOR THE CONTROL MEASURE'S IMPLEMENTATION.

B. THE SWPPP MUST INCLUDE A DESCRIPTION OF INTERIM AND PERMANENT STABILIZATION PRACTICES FOR THE SITE, INCLUDING A SCHEDULE OF WHEN THE PRACTICES WILL BE IMPLEMENTED. SITE PLANS SHOULD ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE POSSIBLE AND THAT DISTURBED PORTIONS OF THE SITE ARE STABILIZED. USE OF IMPERVIOUS SURFACES FOR STABILIZATION SHOULD BE AVOIDED.

C. THE FOLLOWING RECORDS MUST BE MAINTAINED AS PART OF THE SWPPP

1. DATES WHEN MAJOR GRADING ACTIVITIES OCCUR: 2. DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE; AND 3. DATES WHEN STABILIZATION MEASURES ARE INITIATED.

D. THE SWPPP MUST INCLUDE A DESCRIPTION OF STRUCTURAL PRACTICES: TO DIVERT FLOWS FROM EXPOSED SOILS; TO RETAIN/DETAIN FLOWS; OR TO OTHERWISE LIMIT RUNOFF AND THE DISCHARGE OF POLLUTANTS FROM EXPOSED AREAS OF THE SITE. PLACEMENT OF STRUCTURAL PRACTICES IN FLOODPLAINS MUST BE IN ACCORDANCE WITH APPLICABLE REGULATIONS. THE SWPPP MUST INCLUDE A DESCRIPTION OF ALL POST-CONSTRUCTION STORM WATER MANAGEMENT MEASURES THAT WILL BE INSTALLED DURING THE CONSTRUCTION PROCESS TO CONTROL POLLUTANTS IN STORM WATER DISCHARGES AFTER CONSTRUCTION OPERATIONS HAVE BEEN COMPLETED.

F. THE SWPPP MUST DESCRIBE MEASURES TO PREVENT THE DISCHARGE OF SOLID MATERIALS, INCLUDING BUILDING MATERIALS, TO SURFACE WATERS OF THE UNITED STATES, EXCEPT AS AUTHORIZED BY A PERMIT ISSUED UNDER SECTION 404 OF THE

G. THE SWPPP MUST DESCRIBE MEASURES TO MINIMIZE, TO THE EXTENT PRACTICABLE, OFF-SITE VEHICLE TRACKING OF SEDIMENTS ONTO PAVED SURFACES AND THE GENERATION OF DUST.

H. THE SWPPP MUST INCLUDE A DESCRIPTION OF CONSTRUCTION AND WASTE MATERIALS EXPECTED TO BE STORED ON-SITE WITH UPDATES AS APPROPRIATE. THE SWPPP MUST ALSO INCLUDE A DESCRIPTION OF CONTROLS, INCLUDING STORAGE PRACTICES, TO MINIMIZE EXPOSURE OF THE MATERIALS TO STORM WATER, AND SPILL PREVENTION AND RESPONSE PRACTICES.

I. THE SWPPP MUST INCLUDE A DESCRIPTION OF POLLUTANT SOURCES FROM AREAS OTHER THAN CONSTRUCTION (INCLUDING STORM WATER DISCHARGES FROM DEDICATED ASPHALT PLANTS AND DEDICATED CONCRETE PLANTS), AND A DESCRIPTION OF CONTROLS AND MEASURES THAT WILL BE IMPLEMENTED AT THOSE SITES TO MINIMIZE POLLUTANT DISCHARGES.

A. INSPECTIONS MUST BE CONDUCTED AT LEAST ONCE EVERY 14 CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM EVENT OF 0.5 INCHES OR GREATER.

B. INSPECTION FREQUENCY MAY BE REDUCED TO AT LEAST ONCE EVERY MONTH IF:

- THE ENTIRE SITE IS TEMPORARILY STABILIZED. 2. RUNOFF IS UNLIKELY DUE TO WINTER CONDITIONS (E.G., SITE IS COVERED
- WITH SNOW, ICE, OR THE GROUND IS FROZEN), 3. CONSTRUCTION IS OCCURRING DURING SEASONAL ARID PERIODS IN ARID AREAS AND SEMI-ARID AREAS.

C. INSPECTIONS MUST BE CONDUCTED BY QUALIFIED PERSONNEL (PROVIDED BY THE OPERATOR OR COOPERATIVELY BY MULTIPLE OPERATORS). "QUALIFIED PERSONNEL" MEANS A PERSON KNOWLEDGEABLE IN THE PRINCIPLES AND PRACTICE OF EROSION AND SEDIMENT CONTROLS WHO POSSESSES THE SKILLS TO ASSESS CONDITIONS AT THE CONSTRUCTION SITE THAT COULD IMPACT STORM WATER QUALITY AND TO ASSESS THE EFFECTIVENESS OF ANY SEDIMENT AND EROSION CONTROL MEASURES SELECTED TO CONTROL THE QUALITY OF STORM WATER DISCHARGES FROM THE CONSTRUCTION ACTIVITY.

D. INSPECTIONS MUST INCLUDE ALL AREAS OF THE SITE DISTURBED BY CONSTRUCTION ACTIVITY AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION. INSPECTORS MUST LOOK FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE STORM WATER CONVEYANCE SYSTEM, SEDIMENTATION AND EROSION CONTROL MEASURES IDENTIFIED IN THE SWPPP MUST BE OBSERVED TO ENSURE PROPER OPERATION. DISCHARGE LOCATIONS MUST BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING VIOLATIONS TO SC'S WATER QUALITY STANDARDS, WHERE ACCESSIBLE. WHERE DISCHARGE LOCATIONS ARE INACCESSIBLE, NEARBY DOWNSTREAM LOCATIONS MUST BE INSPECTED TO THE EXTENT THAT SUCH INSPECTIONS ARE PRACTICABLE, LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE MUST BE INSPECTED FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING.

E. FOR EACH INSPECTION REQUIRED ABOVE, YOU MUST COMPLETE AN INSPECTION REPORT. AT A MINIMUM, THE INSPECTION REPORT MUST INCLUDE:

- 2. NAMES, TITLES, AND QUALIFICATIONS OF PERSONNEL MAKING THE INSPECTION:
- 3. WEATHER INFORMATION FOR THE PERIOD SINCE THE LAST INSPECTION (OR SINCE COMMENCEMENT OF CONSTRUCTION ACTIVITY IF THE FIRST INSPECTION) INCLUDING A BEST ESTIMATE OF THE BEGINNING OF EACH STORM EVENT. DURATION OF EACH STORM EVENT, APPROXIMATE AMOUNT OF RAINFALL FOR EACH STORM EVENT (IN INCHES), AND WHETHER YOU KNOW IF ANY
- DISCHARGES OCCURRED 4. WEATHER INFORMATION AND A DESCRIPTION OF ANY DISCHARGES
- OCCURRING AT THE TIME OF THE INSPECTION; 5. LOCATION(S) OF DISCHARGES OF SEDIMENT OR OTHER POLLUTANTS FROM
- THE SITE: 6. LOCATION(S) OF BMPS THAT NEED MAINTENANCE; 7. LOCATION(S) OF BMPS THAT FAILED TO OPERATE AS DESIGNED OR PROVED
- INADEQUATE FOR A PARTICULAR LOCATION; 8. LOCATION(S) WHERE ADDITIONAL BMPS ARE NEEDED THAT DID NOT EXIST AT
- THE TIME OF INSPECTION; AND 9. CORRECTIVE ACTION REQUIRED INCLUDING ANY CHANGES TO THE SWPPF NECESSARY AND IMPLEMENTATION DATES.

A RECORD OF EACH INSPECTION AND OF ANY ACTIONS TAKEN IN ACCORDANCE WITH THIS PART MUST BE RETAINED AS PART OF THE SWPPP FOR AT LEAST THREE YEARS FROM THE DATE THAT PERMIT COVERAGE EXPIRES OR IS TERMINATED. THE INSPECTION REPORTS MUST IDENTIFY ANY INCIDENTS OF NON-COMPLIANCE WITH THE PERMIT CONDITIONS. WHERE A REPORT DOES NOT IDENTIFY ANY INCIDENTS OF NON-COMPLIANCE, THE REPORT MUST CONTAIN A CERTIFICATION THAT THE CONSTRUCTION PROJECT OR SITE IS IN COMPLIANCE WITH THE SWPPP AND THIS PERMIT. THE REPORT MUST BE SIGNED IN ACCORDANCE WITH APPENDIX G, SECTION 11 OF THE NPDES GENERAL PERMIT FOR STORM WATER DISCHARGE FROM CONSTRUCTION ACTIVITIES (G.P.).

#### MAINTAINING AN UPDATED PLAN

MANAGEMENT PRACTICES

A. THE SWPPP, INCLUDING THE SITE MAP, MUST BE AMENDED WHENEVER THERE IS A CHANGE IN DESIGN, CONSTRUCTION, OPERATION, OR MAINTENANCE AT THE CONSTRUCTION SITE THAT HAS OR COULD HAVE A SIGNIFICANT EFFECT ON THE DISCHARGE OF POLLUTANTS TO THE WATERS OF THE UNITED STATES THAT HAS NOT BEEN PREVIOUSLY ADDRESSED IN THE

B. THE SWPPP MUST BE AMENDED IF DURING INSPECTIONS OR INVESTIGATIONS BY SITE STAFF, OR BY LOCAL, COMMONWEALTH, TRIBAL OR FEDERAL OFFICIALS. IT IS DETERMINED THAT THE SWPPP IS INEFFECTIVE IN ELIMINATING OR SIGNIFICANTLY MINIMIZING POLLUTANTS IN STORM WATER DISCHARGES FROM THE CONSTRUCTION SITE.

C. BASED ON THE RESULTS OF AN INSPECTION, THE SWPPP MUST BE MODIFIED AS NECESSARY TO INCLUDE ADDITIONAL OR MODIFIED BMPS DESIGNED TO CORRECT PROBLEMS IDENTIFIED. REVISIONS TO THE SWPPP MUST BE COMPLETED WITHIN SEVEN (7) CALENDAR DAYS FOLLOWING THE INSPECTION. IMPLEMENTATION OF THESE ADDITIONAL OR MODIFIED BMPS MUST BE ACCOMPLISHED AS DESCRIBED IN SUBPART 3.6.B OF THE G.P.

A. ALL CONTROL MEASURES MUST BE PROPERLY SELECTED, INSTALLED, AND MAINTAINED IN ACCORDANCE WITH ANY RELEVANT MANUFACTURER SPECIFICATIONS AND GOOD ENGINEERING PRACTICES. IF PERIODIC INSPECTIONS OR OTHER INFORMATION INDICATES A CONTROL HAS BEEN USED INAPPROPRIATELY, OR INCORRECTLY, THE OPERATOR MUST REPLACE OR MODIFY THE CONTROL FOR SITE SITUATIONS AS SOON AS PRACTICABLE.

B. IF SEDIMENT ESCAPES THE CONSTRUCTION SITE, OFF-SITE ACCUMULATIONS OF SEDIMENT MUST BE REMOVED AT A FREQUENCY SUFFICIENT TO MINIMIZE OFF-SITE.

C. LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.

D. EXCEPT AS PROVIDED BELOW, STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED. 1. WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS, STABILIZATION MEASURES MUST BE INITIATED

AS SOON AS PRACTICABLE. 2. WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.

#### DOCUMENTATION OF PERMIT ELIGIBILITY RELATED TO TOTAL MAXIMUM DAILY LOADS

THE SWPPP MUST INCLUDE DOCUMENTATION SUPPORTING A DETERMINATION OF PERMIT ELIGIBILITY WITH REGARD TO WATERS THAT HAVE A TMDL THAT HAVE AN EPA-ESTABLISHED OR APPROVED TMDL, INCLUDING A. IDENTIFICATION OF WHETHER YOUR DISCHARGE IS IDENTIFIED, EITHER SPECIFICALLY OR GENERALLY, IN AN EPA-ESTABLISHED APPROVED TMDL AND ANY ASSOCIATED ALLOCATIONS, REQUIREMENTS, AND ASSUMPTIONS IDENTIFIED FOR YOUR DISCHARGE;


B. SUMMARIES OF CONSULTATION WITH COMMONWEALTH OR FEDERAL TMDL AUTHORITIES ON CONSISTENCY OF SWPPP CONDITIONS WITH THE APPROVED TMDL, AND C. MEASURES TAKEN BY YOU TO ENSURE THAT YOUR DISCHARGE OF POLLUTANTS FROM THE SITE IS CONSISTENT WITH THE

ASSUMPTIONS AND REQUIREMENTS CONTAINED IN THE EPA-ESTABLISHED OR APPROVED TMDL, INCLUDING ANY SPECIFIC

WASTELOAD ALLOCATION THAT HAS BEEN ESTABLISHED THAT WOULD APPLY TO YOUR DISCHARGE.

ARCHITECTURE **ENGINEERING** LANDSCAPE ARCHITECTURE LAND SURVEYING ENVIRONMENTAL SCIENCES

> 355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax



()O

A.J.L.

N.T.S.

08C2978

3/29/2011

Checked Approved Project No Date

EC08C297802

SEDIMENTATION AND EROSION CONTROL NOTES

IG	36	ilex glabra 'Compacta'	COMPACT INKBERRY	#3 CONT.	24" -30' HT.	UNIFORM, WELL DEV. 3' O.C.	
FM	20	Fargesia murieliae	UMBRELLA BAMBOO	#5 CONT.	4'-6' HT.	5' O.C.	
HRL KEY	IBS &		COMMON NAME	ROOT	SIZE	COMMENTS	
ZS 5 Zelkova serrata 'Green Vase'		Zelkova serrata 'Green Vase'	JAPANESE ZELKOVA	8&8	3"-3 1/2" CAL.	UNIFORM, WELL DEV. 7° MIN. BRANCHING	
PC	4	Pyrus calleryang Chanticleer	CHANTICLEER CALLERY PEAR	D.CCD	21/2 - 3 CAL	UNIFORM, WELL DEV. / MIN. DRANCHING F	

#3 CONT.

2 1/4" PEAT POT 3" HT.

MULTI-STEM

UNIFORM, WELL DEV. 7' MIN. BRANCHING H

10'-12' HT.

2"-2 1/2" CAL.


	· NINII AI C	A ODOUNDOOVEDS				· · · · ·
LKEY KEY	NNIALS TITNAUQ	& GROUNDCOVERS  Y BOTANICAL NAME	COMMON NAME	ROOT	SIZE	COMMENTS
JH	470	Juniperus horizontalis "Wiltoni"	CREEPING JUNIPER	#3 CONT.	6 12" HT.	6' O.C.
LM	150	Liriope muscari 'Majestic'	LILYTURF	CONT.	6 12" HT.	12" O.C.
PA1	38	Pennisetum olopecuroides	FOUNTAIN GRASS	CONT.	12"18" HT.	36" O.C.
240	1	5 1 1 1 1 1 1 1 1 1 1 1	DWART FOUNTAIN ODAGE	CONT	19"_19" UT	24" 0.0


VIRGINIA CREEPER

## LIGHTING SCHEDULE


TYPE	LUMS	WATTS	POLE HEIGHT	MOUNT	MANUFACTURER	FIXTURE MODEL #	POLE MODEL #
LP1	9	48 W	12'	POLE	BEACON PRODUCTS	TRE31-LED48	FLAGLER AK
LP2	6	165W	20*	POLE	STERNER LIGHTING	EXEC-QL25	STR
LP3	7	50W		BOLLARD	BEACON PRODUCTS	FLA42	_

## LANDSCAPE KEY
















GATEWAY SIGNAGE AT INTERSECTION OF MIDDLESEX AVENUE AND MYSTIC AVENUE





50 MIDDLESEX AVENUE
FERVILLE, MASSACHUSETTS, MIDDLESEX COUNTY

REVISIONS No. Date Desc.

Designed D.J.F.
Drawn D.J.F.
Checked
Approved
Scale 1"=20'
Project No. 08C2978
Date 3/29/2011

CAD File:
LL08C297801


Title

LANDSCAPE

LANDSCAPE AND SITE LIGHTING PLAN

heet No.

LL-1



Q2008 BL COMPANIES, INC. THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF BL COMPANIES

Companies

ARCHITECTURE ENGINEERING PLANNING
LANDSCAPE ARCHITECTURE
LAND SURVEYING ENVIRONMENTAL SCIENCES

355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax




Scale

Date

Drawn Checked Approved Project No. 08C2978

3/29/2011 CAD File: LL08C297802

**FUTURE** LANDSCAPE AND SITE LIGHTING PLAN



- 28 DAY 3000 PSI CLASS "A"


-POUR FLUSH W/ PROP.


PAVEMENT GRADE

PROPOSED BIT. PAV.

PREPARED SUBGRADE


BLPC-002







# TYPICAL PAVEMENT MARKING










FRONT VIEW

# ELECTRICAL, TELEPHONE AND GAS TRENCH DETAIL


FACE OF CURB


# CHAIN LINK FENCE DETAIL



NOTE:
1. PROVIDE 2 COATS OF PAINT ON ALL SURFACES. 2. SEE PLAN FOR ACTUAL SPACE LOCATION AND DIMENSIONS.

**CONCRETE CURB** AND WALK DETAIL






SIDE VIEW

1. CONSTRUCTION JOINTS SHALL BE SPACED APPROXIMATELY EVERY 10 FEET BUT NOT LESS THAN 6 FEET. 1/4" THICK PREFORMED EXPANSION JOINT FILLER SHALL BE INSTALLED EVERY OTHER JOINT. AND AT INTERSECTION OF CONCRETE SIDEWALK AND CURB.

2. FORMWORK SHALL REMAIN INPLACE FOR 24 HOURS FOLLOWING CONCRETE POURING.

CONCRETE CURB DETAIL



BLPC-002

©2008 BL COMPANIES, INC. THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF BL COMPANIES

SECTION VIEW CONCRETE DUMPSTER PAD AND CONCRETE PAVEMENT

- FACE OF GRANITE CURB

- EXPANSION JOINT

6"x6"x W2.1xW2.1 WWF STEEL MAT REINFORCING

3/4" CRUSHED

SECTION VIEW

**CONCRETE PAVEMENT** 

1/4"/FT. (MAX.) ---

ACCESS AISLE 9'-0" 9'-0" 14'-0" SEE SITE LAYOUT -STANDARD PLAN FOR LOCATION "ACCESSIBLE" STALL SIZE & CONFIGURATION PARKING

UNIVERSAL

FOR "ACCESSIBLE" PARKING.

PAINT STRIPING - CAR PARKING

NOTE: THESE MARKINGS ARE TO BE PAINTED REFLECTIVE WHITE.

CROSSWALK MARKINGS

-SOLID WHITE LINES @ 3' O.C.

N.T.S ZPC-060

"ACCESSIBLE PARKING" SIGNAGE (TYP.)

4" WHITE PAINT LINE 9'-0"

**TYPICAL** PARKING SPACE DETAIL SHEET

Checked

Approved

Project No.

CAD File:

DN08C297801

DETAIL

Scale

Date

N.T.S.

08C2978

3/29/2011

**DN-1** 

Companies

ARCHITECTURE **ENGINEERING** PLANNING LANDSCAPE ARCHITECTURE

LAND SURVEYING

**ENVIRONMENTAL SCIENCES** 

355 Research Parkway

Meriden, CT 06450 (203) 630-1406


(203) 630-2615 Fax

**UILDING** 

GE GE


SEI

PROPO





NOTES: STEEL FOR POSTS SHALL CONFORM TO THE MECHANICAL REQUIREMENTS OF ASTM A 499-81 GRADE 80 AND TO THE CHEMICAL REQUIREMENTS OF ASTM AI-78 CARBON STEEL TEE RAIL HAVING NOMINAL WEIGHT OF "91 LBS OR GREATER PER LINEAR YARD. AFTER FABRICATION ALL STEEL POSTS SHALL BE GALVANIZED TO MEET THE REQUIREMENTS OF ASTM  $A\!-\!123$ . SIGN MOUNTING HEIGHT TO BE APPROVED BY THE ENGINEER.

#### TYPICAL METAL SIGN POSTS N.T.S. BLSD-001




### TYPICAL STORM SEWER TRENCH SECTION








# STANDARD MANHOLE STEP



# PRECAST STORM MANHOLE DETAIL








12.5 S.F. (WHITE)

(ARROWS TO BE CENTERED IN TRAVEL LANE)

# PAVEMENT ARROW DETAILS

-- & OF PARKING INTERNATIONAL HANDICAP SYMBOL

PAINT YELLOW



Companies ARCHITECTURE

**ENGINEERING** PLANNING LANDSCAPE ARCHITECTURE LAND SURVEYING **ENVIRONMENTAL SCIENCES** 

355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax



COUNTY DING.

BUIL CO Ö OP


Designed Checked Approved Scale Project No. 08C2978

3/29/2011 Date CAD File: DN08C297801


**DETAIL** SHEET


Q2008 BL COMPANIES, INC. THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF BL COMPANIES

BC - BITUMINOUS CONCRETE



TRASH ENCLOSURE GATE (HALF SECTION) BLSE-001 N.T.S.





BITUMINOUS SEALER ALTERNATE JOINT 1. 5' OR 6' DIA. PRECAST BASES MAY BE USED WHEN REQUIRED DUE TO SIZE OR NUMBER OF PIPES AT THE MANHOLE. PRECAST REDUCERS WILL BE PLACED ABOVE THE 5' & 6' BASES AS DIRECTED

COLD APPLIED

CONRETE OR BRICK INV.


2. WHEN INLET SEWER INVERT TO OUTLET SEWER INVERT ELVATION EXCEEDS 24" USE DROP CONNECTION.

BY THE ENGINEER. WALL THICKNESS TO INCREASE 1" FOR EACH 1' OF INSIDE DIAMETER INCREASE.


**PRECAST** SANITARY MANHOLE


- ROUNDED CONCRETE TOP PAINTED YELLOW 6" DIA. STEEL POST FILLED WITH CONCRETE AND PAINTED YELLOW — MIN. 18" DIA. CONCRETE BASE

PROTECTIVE POST (BOLLARD) DETAIL




TRASH ENCLOSURE SECTION BLSE-003






**CLEANOUT DETAIL** 



TYPICAL SANITARY SEWER TRENCH SECTION BLSS-010



©2008 BL COMPANIES, INC. THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF BL COMPANIES

ARCHITECTURE **ENGINEERING** PLANNING LANDSCAPE ARCHITECTURE LAND SURVEYING

**ENVIRONMENTAL SCIENCES** 355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax



COUNTY

**PROPO** 

Designed Drawn Checked

Approved N.T.S. Scale 08C2978 Project No. 3/29/2011 CAD File: DN08C297801

A.J.L.

DETAIL SHEET

Sheet No.

The above layout shows a bi-directional traffic access control system using a slide gate operator and optional non-contact safety devices. We strongly support adherence to applicable safety standards and make available any and all information with regard to manufacturers' compliance thereto.

- SLIDE GATE OPERATORS are available in a wide range of power, voltage and final drive configurations.
- ACCESS CONTROL DEVICE options include, but are not limited to, telephone entry systems, keypads, card readers, proximity readers and intercoms.
- IN-GROUND LOOPS are designed for vehicle detection through the use of an electronic "Loop Detector" which reads field variations produced by an inductive "Loop." They are typically used for free exit, safety and gate closure. In combination, they are integral parts of many sophisticated traffic control systems.
- PHOTOELECTRIC CELLS are designed for vehicle detection through the use of a photoelectric transmitter and receiver. They are typically used for free exit, safety and gate closure and are available in two basic configurations: the first offers a more stable signal and setup with separate transmitter and receiver units, however requires power on both sides of the gate; the second offers a combined transmitter/receiver that utilizes a reflector, mounted opposite the unit, to complete the send/receive circuit.

WARNING: Use of this slide gate access system is limited to vehicular slide gates only. This system must never be used to operate any gate that is intended for pedestrian use.



Copyright @ 2001-2005 Master Halco, Inc. All rights reserved.


©2008 BL COMPANIES, INC. THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF BL COMPANIES


Fencing Without Boundaries. TM

# SLIDE GATE CONTROLLERS

Bl

NOTE: FENCE STYLE/ TYPE FOR INFORMATION PURPOSES ONLY





SLIDE GATE DETAIL


N.T.S.

FD-001

Companies

ARCHITECTURE
ENGINEERING
PLANNING
LANDSCAPE ARCHITECTURE
LAND SURVEYING
ENVIRONMENTAL SCIENCES

355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax



OPOSED SELF-STORAGE BUILDING
50 MIDDLESEX AVENUE
TERVILLE, MASSACHUSETTS, MIDDLESEX COUNT

Desc.

REVISIONS lo. Date

Designed
Drawn
Checked
Approved
Scale
Project No.

Scale N.T.S.
Project No. 08C2978
Date 3/29/2011
CAD File:
DN08C297801


DETAIL SHEET

Sheet No.

## DECORATIVE LIGHT BASE

DECORATIVE LIGHT POLE

©2008 BL COMPANIES, INC. THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF BL COMPANIES



N.T.S.

STANDARD LIGHT POLE BASE DETAIL

7 1/4" DIA.

BEACON PRODUCTS LIGHTED FLAGLER AK CAST ALUMINUM

BLACK

-FOR USE WITH


5/8" DIA. X 12" X 3"

HOT DIP GALVANIZED

STEEL ANCHOR BOLTS

-3" PVC SCHEDULE 80 CONDUIT


WITH 3" PROJECTION




SLOT WIDTH IS 1/4" MAXIMUM, MEETS ADA COMPLIANCE. GRATE CAST FROM GRAY IRON OR ALUMINUM TREE OPENING SIZE.

18" STEEL ANGLE FRAME REQUIRED FOR INSTALLATION USE MODEL M36X60F OUTER FRAME DIM. IS 3/4" ± 1/8" GREATER THAN GRATE.

#### TREE GRATE



## **BENCH**



ANCHOR FOR BENCH

N.T.S

Companies

ARCHITECTURE ENGINEERING PLANNING LANDSCAPE ARCHITECTURE LAND SURVEYING ENVIRONMENTAL SCIENCES

> 355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax



COUNTY BUILDING

**(1)** 

0


Designed


W.E.V. Drawn Checked Approved Scale 08C2978 Project No. 3/29/2011


CAD File: DN08C297801


LANDSCAPE DETAIL SHEET











THREADED STEEL SHAFT BOLT HOLE

AVAILABLE OPTIONS: POWDER COATING 10 STANDARD COLORS, CUSTON COLORS (INCLUDING THE RAL RANGE) CUSTON PLAQUES & DECALS AVAILABLE WITH STEEL PLAGUES IN VARIOUS SIZES AND PRESSURE SENSITIVE VINYL OUTDOOR DECALS.

19"

STANDARD WITH TAPERED FORMED LID. AVAILABLE WITH OPTIONAL S-2A FORMED DONE (AS SHOWN), S-2A FORMED DOME WITH STAINLESS STEEL ASHTRAY, AND DS-32 FORMED DONE WITH SELF CLOSING DOOR

36-GALLON CAPACITY HIGH DENSITY PLASTIC LINER

(WEIGHT NOT TO EXCEED 6 LBS.) SITS ON 3/8" x 3° SUPPORT BARS

P.O. DRAWER 330 - DUNKIRK, NO 20754 USA


TOLL FREE: (800) 368-2573 (USA & CANADA) TEL (301) 855-8300 - FAX (410) 257-7579

WEB SITE: HTTP://WWW.VICTORSTANLEY.COM


THIS PRODUCT IS COVERED BY U.S. PATENT D417,053

LID IS SECURED WITH VINYL COATED GALVANIZED STEEL AIRCRAFT CABLE. CABLE IS LOOPED AROUND ATTACHWENT BRACKETS AND


1. ALL FABRICATED METAL COMPONENTS ARE STEEL SHOTBLASTED, ETCHED, PHOSPHATIZED, PREHEATED, AND ELECTROSTATICALLY POWDER-COATED WITH T.G.I.C. POLYESTER POWDER COATINGS. PRODUCTS ARE FULLY CLEANED AND PRETREATED, PREHEATED AND COATED WHILE HOT TO FILL CREVICES AND BUILD FILM COATING. COATED PARTS ARE THEN FULLY CURED TO COATING MANUFACTURER'S SPECIFICATIONS. THE THICKNESS OF THE RESULTING FINISH AVERAGES 8-10 MILS (200-250 MICRONS). 2. ANCHOR BOLT(S) NOT PROVIDED BY VICTOR STANLEY, INC.





### TRASH RECEPTACLE




©2008 BL COMPANIES, INC. THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF BL COMPANIES









SPECIAL PAVEMENT - PRECAST CONCRETE PAVERS SCALE: NTS

NOTES 1. CONNECTION BETWEEN SECTIONS TO UTILIZE MANUFACTURERS' INTERLOCKING SNAPDOWN SPLICING SYSTEM

2. CORNERS — NOTCH BASE ONLY AND FORM A CONTINUOUS CORNER

3. PERMALOC STRUCTUREDGE AS MANUFACTURED BY PERMALOC CORPORATION, HOLLAND MI. 1—800—356—9660, 616—399—9600


Steel Paver Restraint 3/16" x 2-1/4" Black DuraFlex — electrostatically applied baked on paint


METAL EDGE

N.T.S

- PLANTING SOIL MIX - 2" BLUESTONE CAP SET WITH 3/8" MORTAR BED - 1" OVERHANG - BRICKS IN RUNNING BOND SET ON 3/8" MORTAR BED. HOLD ONE COURSE BELOW FINISH GRADE. FINISH GRADE - REINFORCED CONCRETE FOOTING × 2 X 2

PLANTER DETAIL - TYPE 2





12" SQUARE CONCRETE PAVERS 45" STACK BOND

CONCRETE PLAZA AREA ENLARGEMENT

SCALE: 1"=10"

PLANTER DETAIL - TYPE 1

SHEET

Designed

Checked

Approved Scale

Project No.

CAD File: DN08C297801

DETAIL

LANDSCAPE

DN-6

W.E.V.

08C2978

3/29/2011

LANDSCAPE ARCHITECTURE LAND SURVEYING **ENVIRONMENTAL SCIENCES** 355 Research Parkway (203) 630-1406 (203) 630-2615 Fax

Companies

ARCHITECTURE

ENGINEERING


PLANNING



PROPO

NOTE:
\* IN AREAS OF MASS PLANTING, CONTINUOUSLY EXCAVATE
AND MULCH ENTIRE BED.

# SHRUB PLANTING



NOTES:


1. ROTOTILL FERTILIZER, LIME, AND OTHER AMENDMENTS INTO SOIL PRIOR TO PLANTING AND IN ACCORDANCE WITH SOIL ANALYSIS RECOMMENDATIONS.

- 2. THOROUGHLY WATER ALL PLANTING BEDS IMMEDIATELY AFTER PLANTING.
- 3. ADJUST BULB PLANTING DEPTH AS RECOMMENDED BY BULB SUPPLIER.

N.T.S.

# ANNUAL/PERENNIAL AND GROUNDCOVER BEDS

BLLD-002



TREE PLANTING

## LANDSCAPE NOTES

1. THE LANDSCAPE PLAN AND DETAIL SHEET ARE FOR LANDSCAPING INFORMATION ONLY. REFER TO THE SITE LAYOUT PLAN, LIGHTING PLAN, GRADING PLAN AND UTILITIES PLAN FOR ALL OTHER INFORMATION.

2. PLANTING LOCATIONS ARE APPROXIMATE AND ARE SUBJECT TO FIELD ADJUSTMENT DUE TO UTILITY LOCATIONS AND SITE CONDITIONS. CONTRACTOR SHALL LAY OUT THE WORK FOR THE REVIEW, ADJUSTMENT, AND APPROVAL OF OWNER OR LANDSCAPE ARCHITECT PRIOR TO PLANTING.

3. UTILITY LOCATIONS SHOWN IN THE DRAWINGS ARE APPROXIMATE. EXERCISE CARE WHEN DIGGING IN AREAS OF POTENTIAL CONFLICT WITH UNDERGROUND OR OVERHEAD UTILITIES. THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE DUE TO CONTRACTOR'S NEGLIGENCE AND SHALL REPLACE OR REPAIR ANY DAMAGE AT CONTRACTOR'S EXPENSE

4. NO PLANT SHALL BE PLACED IN THE GROUND BEFORE ROUGH GRADING HAS BEEN COMPLETED.

5. TOPSOIL SHALL BE INSTALLED AT A MINIMUM DEPTH OF 4". CONTRACTOR SHALL SUBMIT SAMPLES FROM EACH PROPOSED TOPSOIL SOURCE TO A CERTIFIED TESTING LABORATORY TO DETERMINE pH, FERTILITY, ORGANIC CONTENT AND MECHANICAL COMPOSITION. CONTRACTOR SHALL SUBMIT THE TEST RESULTS TO OWNER OR LANDSCAPE ARCHITECT FOR REVIEW. CONTRACTOR SHALL INCORPORATE AMENDMENTS FOR PROPER SOIL pH AND PLANT GROWTH AS RECOMMENDED BY TEST REPORTS AT NO INCREASE IN CONTRACT PRICE.

6. THE CONTRACTOR SHALL SUPPLY ALL LABOR, PLANTS, AND MATERIALS IN QUANTITIES SUFFICIENT TO COMPLETE THE WORK SHOWN ON THE DRAWINGS AND LISTED IN THE PLANT SCHEDULE. WHEN QUANTITIES LISTED IN THE PLANT SCHEDULE DIFFER FROM THOSE REQUIRED BY THE DRAWINGS, THE LARGER QUANTITY SHALL BE

7. LANDSCAPE PLANTING PITS MUST BE FREE DRAINING. PAVEMENT, COMPACTED SOIL, AND BLASTED ROCK SHALL BE REMOVED FROM PLANTING PITS AND LANDSCAPE ISLANDS TO A DEPTH OF 2' OR TO A GREATER DEPTH IF REQUIRED BY PLANTING DETAILS OR SPECIFICATIONS. REPLACE SOIL WITHIN ISLANDS WITH LOAM OR SANDY LOAM FREE OF STONES AND DEBRIS 1" OR GREATER IN DIAMETER AND ALL OTHER MATERIAL HARMFUL TO PLANT DEVELOPMENT.

8. PLANTING SOIL MIXTURE FOR ALL PLANTINGS SHALL CONSIST OF: 1 PART PEAT MOSS OR COMPOST, 3 PARTS TOPSOIL, "TRANSPLANT 1-STEP" FERTILIZER / BIOSTIMULANT / MYCORRHIZA INOCULATE AS MANUFACTURED BY ROOTS, INC. OR AN APPROVED EQUIVALENT, AND LIME AND OTHER AMENDMENTS AS INDICATED BY SOIL ANALYSIS.

9. PLANT REQUIREMENTS: ALL PLANTS SHALL CONFORM IN SIZE AND GRADE TO THE AMERICAN STANDARD FOR NURSERY STOCK, ANSI Z60.1 (LATEST EDITION). ALL PLANTS SHALL MEET THE ADDITIONAL REQUIREMENTS SET FORTH BELOW AND IN WRITTEN SPECIFICATIONS AS APPLICABLE. ALL TREES AND SHRUBS SHALL HAVE BEEN GROWN AT A COMMERCIAL NURSERY WITHIN 200 MILES OF THE PROJECT SITE UNLESS OTHERWISE APPROVED BY OWNER OR LANDSCAPE ARCHITECT. THEY SHALL BE TYPICAL OF THEIR SPECIES OR VARIETY. THEY SHALL BE HEALTHY, SYMMETRICAL, EVENLY AND DENSELY BRANCHED, AND DENSELY FOLIATED WHEN IN LEAF. THEY SHALL BE FREE OF BARK INJURY, DISEASE, AND INSECT PESTS. ALL TREES SHALL HAVE A STRAIGHT TRUNK WITH A SINGLE MAIN LEADER UNLESS OTHERWISE CHARACTERISTIC OF THE SPECIES OR VARIETY. THE OWNER OR LANDSCAPE ARCHITECT WILL ALLOW SUBSTITUTIONS ONLY UPON WRITTEN APPROVAL. SIZES SHALL CONFORM TO THE MEASUREMENT SPECIFIED ON THE DRAWINGS. PLANTS LARGER THAN SPECIFIED MAY BE USED IF APPROVED. THE USE OF SUCH PLANTS SHALL NOT INCREASE THE CONTRACT PRICE. ALL OVERSTORY TREES PLANTED ALONG PARKING AREAS, SIDEWALKS AND PEDESTRIAN ACCESSES SHALL NOT BRANCH BELOW 7' FEET IF THE TREE CALIPER IS 2 1/2" INCHES OR GREATER. ALL PLANT MATERIALS ARE SUBJECT TO INSPECTION AND ACCEPTANCE BY THE OWNER OR LANDSCAPE ARCHITECT AT THE NURSERY SOURCE. THE CONTRACTOR SHALL COORDINATE SOURCE VISITS WITH THE LANDSCAPE ARCHITECT AND SHALL ACCOMPANY THE OWNER AND/OR LANDSCAPE ARCHITECT FOR ALL INSPECTIONS. CERTIFICATES OF COMPLIANCE WITH SPECIFICATIONS ARE REQUIRED FOR ALL PLANTS.

10. ALL SHRUB BEDS SHALL BE MULCHED TO A DEPTH OF 3". ANNUAL AND PERENNIAL BEDS SHALL BE MULCHED TO A DEPTH OF 2". USE UNCOLORED, SHREDDED BARK MULCH AGED AT LEAST SIX MONTHS FOR ALL DEDGE.

11. GUARANTEE: GUARANTEE ALL PLANTS AND LAWNS FOR A MINIMUM OF 1 YEAR TO BE ALIVE AND IN VIGOROUS GROWING CONDITION AT THE END OF THE GUARANTEE PERIOD. THE GUARANTEE PERIOD FOR ALL PLANTS SHALL BEGIN UPON APPROVAL AS SPECIFIED UNDER SEMI—FINAL ACCEPTANCE. PLANT MATERIALS AND LAWNS APPROVED IN THE SPRING SHALL BE ALIVE AND IN SATISFACTORY GROWTH ON JUNE 1 OF THE FOLLOWING YEAR; PLANTING DONE IN LATE FALL (AFTER NOVEMBER 1ST) SHALL BE MAINTAINED AND GUARANTEED UNTIL THE SECOND SPRING'S LEAFING. REPLACEMENTS: ALL PLANTS SHALL BE FREE OF DEAD OR DYING BRANCHES AND BRANCH TIPS, AND SHALL BEAR FOLIAGE OF A NORMAL DENSITY, SIZE AND COLOR. PROMPTLY REMOVE DEAD, UNSIGHTLY, UNHEALTHY, OR EXCESSIVELY PRUNED PLANTS. THESE AND ANY PLANTS MISSING DUE TO THE CONTRACTOR'S NEGLIGENCE, SHALL BE REPLACED OR ADDED WITH THE SAME KIND AND SIZE AS ORIGINALLY SPECIFIED AS SOON AS CONDITIONS PERMIT. METHOD OF REPLACEMENT SHALL BE THE SAME AS SPECIFIED FOR THE ORIGINAL PLANTING WITH REPLACEMENTS MATCHING ADJACENT SPECIMENS OF THE SAME SPECIES. REPLACEMENTS SHALL BE MADE AS MANY TIMES AS NECESSARY TO ENSURE HEALTHY PLANTS AND THEY SHALL BE MAINTAINED AND GUARANTEED. REPLACEMENTS SHALL BE MADE AT THE CONTRACTOR'S EXPENSE AND SHALL BE GUARANTEED FOR ONE FULL YEAR FROM TIME OF REPLACEMENT.

12. LAWN SEEDING MIXTURE:

15 % PERENNIAL RYEGRASS (BLEND OF 3 IMPROVED HYBRIDS)

25 % FINE LEAF OR CREEPING FESCUE (BLEND OF 3 IMPROVED HYBRIDS)

60 % KENTUCKY BLUEGRASS (BLEND OF 3 IMPROVED HYBRIDS)

SEEDING RATE: 5 LBS/1,000 S.F.

SEEDING DATES: AUGUST 15 — OCTOBER 1 AND APRIL 15 — JUNE 15,

UNLESS OTHERWISE APPROVED BY OWNER.

13. ALL SLOPES STEEPER THAN 3:1 RECEIVING A GRASS SEEDING MIXTURE SHALL BE COVERED WITH AN EROSION CONTROL BLANKET OF STRAW FIBER AND BIODEGRADABLE OR PHOTODEGRADABLE NETTING.

14. UNLESS OTHERWISE NOTED IN DRAWING SET, NEW TREELINES SHALL EQUAL CLEARING AND GRUBBING LIMITS.

15. ALL DISTURBED AREAS NOT OTHERWISE DEVELOPED SHALL BE SEEDED WITH THE LAWN SEEDING MIXTURE.


16. IF SHEET IS LESS THAN 24" X 36" IT IS A REDUCED PRINT AND SHOULD BE SCALED ACCORDINGLY.

Companies

ARCHITECTURE
ENGINEERING
PLANNING

LANDSCAPE ARCHITECTURE
LAND SURVEYING
ENVIRONMENTAL SCIENCES

355 Research Parkway Meriden, CT 06450 (203) 630-1406 (203) 630-2615 Fax



ROPOSED SELF-STORAGE BUILDING 50 MIDDLESEX AVENUE MASSACHUSETTS, MIDDLESEX COUNT

SIONS

Drawn
Checked
Approved
Scale
Project No.

Date 3/29/2011 CAD File: DN08C297801

08C2978

LANDSCAPE DETAIL

SHEET

**DN-7** 

©2008 BL COMPANIES, INC. THESE DRAWINGS SHALL NOT BE UTILIZED BY ANY PERSON, FIRM OR CORPORATION WITHOUT THE SPECIFIC WRITTEN PERMISSION OF BL COMPANIES